

ADA 123797

1

INSTALLATION
RESTORATION PROGRAM

PHASE I - RECORDS SEARCH

ROBINS AFB, GEORGIA

PREPARED FOR


UNITED STATES AIR FORCE
AFESC/DEV

Tyndall AFB, Florida

DTIC FILE COPY

APRIL, 1982

DTIC
ELECTED
JAN 26 1983
S D
D



88 01 12 037

PII Redacted

ES ENGINEERING-SCIENCE

This report has been prepared for the U.S. Air Force by Engineering-Science for the purpose of aiding in the implementation of the Air Force Installation Restoration Program. It is not an endorsement of any product. The views expressed herein are those of the contractor and do no necessarily reflect the official views of the publishing agency, the United States Air Force or the Department of Defense.

INSTALLATION RESTORATION PROGRAM
PHASE I: RECORDS SEARCH
ROBINS AFB, GEORGIA

Prepared For

United States Air Force
AFESC/DEV
Tyndall AFB, Florida

| | |
|--|-------------------------|
| Accession For | |
| NTIS GRA&I <input checked="" type="checkbox"/> | |
| DTIC TAB <input type="checkbox"/> | |
| Unannounced <input type="checkbox"/> | |
| Justification | |
| By Per Ltr. on file | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A | |



April, 1982

By

ENGINEERING-SCIENCE, INC.
57 Executive Park South, N.E.
Suite 590
Atlanta, Georgia 30329

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited

This report has been prepared for the U.S. Air Force by Engineering-Science for the purpose of aiding in the implementation of the Air Force Installation Restoration Program. It is not an endorsement of any product. The views expressed herein are those of the contractor and do no necessarily reflect the official views of the publishing agency, the United States Air Force or the Department of Defense.

ES ENGINEERING-SCIENCE

57 EXECUTIVE PARK SOUTH, N.E., SUITE 590 • ATLANTA, GEORGIA 30329 • 404/325-0770

CABLE ADDRESS: ENGINSCI
TELEX: 54-2882

9654

April 13, 1982

Mr. Bernard Lindenberg
AFESC/DEVP
Tyndall AFB, Florida 32403

Dear Mr. Lindenberg:

Enclosed is the Engineering-Science, Inc. (ES) final report entitled "Installation Restoration Program, Phase I - ~~Records Search~~, Robins AFB, Georgia." This report has been prepared in accordance with the ES proposal dated July 15, 1981 and Air Force Contract Number F08637-80-C-0009 Call #0009.

Presented in this report are introductory background information on the Installation Restoration Program, a description of the Robins AFB installation including past activities, mission and environmental setting, a review of industrial activities at Robins AFB, an inventory of major solid and hazardous waste from past activities, a review of past and present waste handling, treatment and disposal facilities, an evaluation of the pollution potential of waste disposal sites, and recommendations for the Installation Restoration Program, Phase II, Problem Confirmation and Quantification.

Any questions concerning this report should be directed to the Office of Public Affairs, Robins Air Force Base, 912/926-5202.

We appreciate the opportunity to work with you and the other Air Force personnel who contributed information to us for the completion of this assessment.

Very truly yours,

ENGINEERING-SCIENCE, INC.

E. J. Schroeder

E. J. Schroeder, P.E.
Manager, Solid & Hazardous Waste

EJS/lmr

Enclosure

TABLE OF CONTENTS

| | <u>Page</u> | |
|-------------------|--|------|
| LIST OF FIGURES | iv | |
| LIST OF TABLES | v | |
| EXECUTIVE SUMMARY | 1 | |
| CHAPTER 1 | INTRODUCTION | 1-1 |
| | Background | 1-1 |
| | Purpose and Scope | 1-1 |
| | Methodology | 1-2 |
| CHAPTER 2 | INSTALLATION DESCRIPTION | 2-1 |
| | Location, Size and Boundaries | 2-1 |
| | Base History | 2-1 |
| | Organization and Mission | 2-5 |
| CHAPTER 3 | ENVIRONMENTAL SETTING | 3-1 |
| | Meteorology | 3-1 |
| | Geography | 3-1 |
| | Topography | 3-4 |
| | Drainage | 3-4 |
| | Surface Soils | 3-4 |
| | Geology | 3-9 |
| | Stratigraphy | 3-9 |
| | Distribution | 3-10 |
| | Hydrogeology | 3-10 |
| | Ground-Water Quality | 3-16 |
| | Surface Water Quality | 3-22 |
| | Wetland Areas | 3-23 |
| | Summary of Environmental Settings | 3-25 |
| CHAPTER 4 | FINDINGS | 4-1 |
| | Past Shops and Base Activity Review | 4-1 |
| | Industrial Shops | 4-2 |
| | Fire Protection Training | 4-9 |
| | Pesticide Utilization | 4-14 |
| | Fuel Management | 4-15 |
| | Description of Past On-Base Disposal Methods | 4-18 |
| | Landfills | 4-19 |
| | Waste Dumps | 4-24 |

| | |
|--|------------|
| Sludge Lagoon | 4-28 |
| Hazardous Waste Burial Site | 4-28 |
| Low-Level Radioactive Waste Sites | 4-30 |
| Industrial Wastewater Treatment Plants | 4-33 |
| Sanitary Wastewater Treatment Facilities | 4-34 |
| Storm Sewer System | 4-36 |
| Refuse Incineration | 4-36 |
| Evaluation of Past Disposal Activities and Facilities | 4-36 |
| CHAPTER 5 CONCLUSIONS | 5-1 |
| CHAPTER 6 RECOMMENDATIONS | 6-1 |
| APPENDIX A BIOGRAPHICAL DATA | |
| APPENDIX B INSTALLATION HISTORY, ORGANIZATION AND MISSION | |
| APPENDIX C SUPPLEMENTAL ENVIRONMENTAL SETTING INFORMATION | |
| APPENDIX D MASTER LIST OF INDUSTRIAL SHOPS | |
| APPENDIX E PHOTOGRAPHS | |
| APPENDIX F WATER SUPPLY WELL LOGS | |
| APPENDIX G HAZARD EVALUATION METHODOLOGY | |
| APPENDIX H SITE RATING FORMS | |
| APPENDIX I REFERENCES | |
| APPENDIX J GLOSSARY | |

LIST OF FIGURES

| <u>Number</u> | <u>Title</u> | <u>Page</u> |
|---------------|---|-------------|
| 1 | Contaminated Site Locations | 4 |
| 1.1 | Decision Tree | 1-5 |
| 2.1 | Regional Location | 2-2 |
| 2.2 | Area Location | 2-3 |
| 2.3 | Site Plan | 2-4 |
| 3.1 | Physiographic Provinces of Georgia | 3-3 |
| 3.2 | Major Drainage Basins of Georgia | 3-5 |
| 3.3 | Surface Drainage | 3-6 |
| 3.4 | Soil Associations | 3-7 |
| 3.5 | Surficial Geology | 3-12 |
| 3.6 | Generalized Cross Section of Major Geologic Units | 3-13 |
| 3.7 | Principal Aquifers of The Coastal Plain of Georgia | 3-15 |
| 3.8 | Well Locations, City of Warner Robins | 3-17 |
| 3.9 | Base Water-Supply Well Locations | 3-19 |
| 3.10 | Boring and Monitoring Well Locations | 3-21 |
| 3.11 | Surface Water Quality Monitoring Station Locations | 3-24 |
| 4.1 | Fire Protection Training Areas | 4-10 |
| 4.2 | Fire Protection Training Area No. 2 | 4-12 |
| 4.3 | Fire Protection Training Area No. 3 & No. 4 | 4-13 |
| 4.4 | Pesticide Storage Area | 4-16 |
| 4.5 | Landfill Locations | 4-20 |
| 4.6 | Landfills No. 1 & No. 2 | 4-22 |
| 4.7 | Landfill No. 3 | 4-25 |
| 4.8 | Landfill No. 4 and Sludge lagoon | 4-26 |
| 4.9 | Waste Dump Locations | 4-27 |
| 4.10 | Hazardous Waste Burial Site | 4-29 |
| 4.11 | Radioactive Waste Burial Site and Aircraft Wash Areas | 4-31 |
| 4.12 | Radioactive Waste Burial Site | 4-32 |
| 4.13 | Wastewater Treatment Facilities | 4-35 |

LIST OF TABLES

| <u>Number</u> | <u>Title</u> | <u>Page</u> |
|---------------|---|-------------|
| 1 | Priority Ranking of Potential Contamination Sources | 5 |
| 2 | Recommended Monitoring Program for Phase II | 7 |
| 3.1 | Robins AFB Climatic Data | 3-2 |
| 3.2 | Robins AFB Base Soils | 3-8 |
| 3.3 | Geologic Formations | 3-11 |
| 3.4 | City of Warner Robins Municipal Wells | 3-18 |
| 3.5 | Summary of Robins AFB Wells | 3-20 |
| 4.1 | Industrial Operations (Shops) | 4-3 |
| 4.2 | Summary of Major Fuel Oil and Chemical Storage Capacities | 4-17 |
| 4.3 | Summary of Landfill Disposal Sites | 4-21 |
| 4.4 | Summary of On-Base Oil/Water Separators | 4-37 |
| 4.5 | Summary of HARM Scores for Potential Contamination Sources | 4-38 |
| 5.1 | Priority Ranking of Potential Contamination Sources | 5-2 |
| 6.1 | Recommended Monitoring Program for Phase II | 6-5 |
| 6.2 | List of Analytical Parameters | 6-8 |

EXECUTIVE SUMMARY

EXECUTIVE SUMMARY

The Department of Defense (DOD) has developed a program to identify and evaluate past hazardous material disposal sites on DOD property, to control the migration of hazardous contaminants, and to control hazards to health or welfare that may result from these past disposal operations. This program is called the Installation Restoration Program (IRP). The IRP has four phases consisting of Phase I, Initial Assessment/Records Search, Phase II, Problem Confirmation, Phase III, Technology Base Development, and Phase IV, Operations. Engineering-Science (ES) was retained by the Air Force Engineering and Services Center to conduct the Phase I, Initial Assessment/Records Search at Robins AFB under Contract No. F08637-80-G009, Call No. 0009, using funding provided by the Air Force Logistics Command.

INSTALLATION DESCRIPTION

Robins AFB is located in middle Georgia approximately 90 miles southeast of Atlanta and 18 miles south of Macon. The base was activated in 1942 and presently comprises 8,855 acres. The primary mission of the base is serving as the parts and equipment logistics manager for a variety of aircraft. This mission has not changed significantly since the mid 1940's.

ENVIRONMENTAL SETTING

The environmental setting data reviewed for this study indicate the following key items concerning the impact of past waste disposal practices on the base:

- o Alluvial deposits cover the upper 20 to 40 feet of the base. The eastern part of the base is swampy with peat deposits covering the upper 10 to 15 feet and underlain by a thin layer of clay. The western part of the site consists of more sandy alluvial deposits which extend eastward below the swamp deposits.

- o The water table beneath the site is shallow, particularly to the east where a surface discharge contributes toward the creation of a swampy area. In the western part of the base, the surface soils are sandy and infiltration of precipitation is expected to be high. This infiltration would directly recharge the shallow aquifer.
- o The primary regional aquifer, the Cretaceous aquifer, underlies Robins AFB at a depth of about 40 to 50 feet and extends to a depth of approximately 650 feet below the surface. It consists of sand with a few clay lenses interspersed throughout its thickness.
- o Robins AFB obtains its water supply from twelve wells distributed over the installation. The City of Warner Robins has a separate system consisting of 11 wells, located throughout the city. All wells are drilled into the Tuscaloosa Formation of the Cretaceous aquifer.
- o Recharge for the Cretaceous aquifer occurs west of Robins AFB where the Providence sand outcrops at the surface. Some recharge may also occur beneath the base as some interconnection between alluvial and underlying deposits may occur.
- o Area precipitation rates (44.1 inches per year) are higher than potential evapotranspiration rates (42 inches per year).
- o Approximately 1200 acres of wetlands in the form of an unimproved river swamp system are located on the east side of the base. The wetlands are known to harbor two species of animals listed by the Federal government as threatened or endangered; American alligator and the red-cockaded woodpecker.

METHODOLOGY

During the course of this project, interviews were conducted with base personnel (past and present) familiar with past waste disposal practices, file searches were performed for facilities which have generated, handled, transported, and disposed of waste materials, interviews were held with local, state and federal agencies, and site inspections were conducted at facilities that have generated, treated,

stored, and disposed of hazardous waste. Thirteen disposal sites located on the Robins AFB property were identified as containing hazardous waste resulting from past waste disposal activities, (Figure 1). These sites have been assessed using a hazardous assessment rating methodology (HARM) which takes into account factors such as site characteristics, waste characteristics, potential for contaminant migration and waste management practices. The details of the rating procedure are presented in Appendix E and the results of the assessment are given in Table 1. The rating system is designed to indicate the relative need for follow-on action. *Review and data of further development of potential contaminant migration are included.*

FINDINGS AND CONCLUSIONS

The following conclusions have been developed based on the results of the project team's field inspection, review of base records and files and interviews with base personnel.

The areas determined to have a high potential for contaminant migration are as follows:

- o Sludge Lagoon
- o Landfill No. 4
- o DDT Spill (1979)

The areas determined to have a moderate potential for contaminant migration are as follows:


- o Fire Protection Training Area No. 2
- o Landfill No. 1
- o Landfill No. 2
- o JP-4 Spill (1965)
- o Hazardous Waste Burial Site
- o Fire Protection Training Area No. 1
- o Laboratory Chemical Disposal Site

The areas determined to have a low potential for contaminant migration are as follows:

- o Landfill No. 3
- o Fire Protection Training Area No. 3
- o Low Level Radioactive Waste (Solid) Burial Site

FIGURE 1

ROBINS AFB SITES WITH POTENTIAL FOR CONTAMINANT MIGRATION



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

TABLE 1
PRIORITY RANKING OF POTENTIAL CONTAMINATION SOURCES
ROBINS AFB

| Rank | Site Name | Date of Operation or Occurrence | Overall Total Score |
|------|---|---------------------------------|---------------------|
| 1 | Sludge Lagoon | 1963-1978 | 77 |
| 2 | Landfill No. 4 | 1965-1978 | 73 |
| 3 | DDT Spill (1979) | 1979 | 70 |
| 4 | Fire Protection Training Area No. 2 | mid 1950's to mid 1960's | 64 |
| 5 | Landfill No. 1 | 1943-1951 | 59 |
| 6 | Landfill No. 2 | 1951-1953 | 58 |
| 7 | JP-4 Spill (1965) | 1965 | 57 |
| 8 | Hazardous Waste Burial Site | 1976, 1977 | 54 |
| 9 | Fire Protection Training Area No. 1 | 1943-mid 1950's | 52 |
| 10 | Laboratory Chemical Disposal Site | early 1960's | 51 |
| 11 | Landfill No. 3 | 1964 | 47 |
| 12 | Fire Protection Training Area No. 3 | mid 1960's to 1969 | 45 |
| 13 | Low Level Radioactive Waste (Solid) Burial Site | 1940's to 1950's | 31 |

Note: This ranking was performed according to the Hazardous Assessment Rating Methodology (HARM) described in Appendix G. Individual site rating forms are in Appendix H.

RECOMMENDATIONS

The detailed recommendations developed for further assessment of potential contaminant migration are presented in Chapter 6. These recommendations are summarized as follows:

- o Sludge Lagoon and Landfill No. 4 - Conduct geophysical surveys and additional ground-water monitoring.
- o DDT Spill Site - Remove contaminated soils and sample soils to verify clean up.
- o Fire Protection Training Area No. 2 - Collect and analyze soil borings in and around the site.
- o Landfill No. 1 and JP-4 Spill Site - Conduct geophysical surveys or sample the top of the water table. Also sample landfill leachate stream.
- o Landfill No. 2 and Fire Protection Training Area No. 1 - Conduct ground-water monitoring program.
- o Hazardous Waste Burial Site - Conduct ground-water monitoring program.
- o Laboratory Chemical Disposal Site - Conduct geophysical survey and collect and analyze soil borings.
- o Water Supply Wells - Sample and analyze well water.
- o Surface Water - Conduct additional surface water monitoring on the base.

CHAPTER 1
INTRODUCTION

CHAPTER 1

INTRODUCTION

BACKGROUND

The United States Air Force, due to its primary mission, has long been engaged in a wide variety of operations dealing with toxic and hazardous materials. Federal, state and local governments have developed strict regulations to require that disposers identify the locations and contents of disposal sites and take action to eliminate the hazards in an environmentally responsible manner. The Department of Defense (DOD) has issued Defense Environmental Quality Program Policy Memorandums 80-6 and 81-5 which require the identification and evaluation of past hazardous material disposal sites on DOD property, the control of migration of hazardous contaminants, and the control of hazards to health or welfare that resulted from these past operations. This program is called the Installation Restoration Program (IRP). The IRP will be a basis for response actions on Air Force Installations under the provisions of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980.

PURPOSE AND SCOPE OF THE ASSESSMENT

The Installation Restoration Program has been developed as a four-phased program as follows:

Phase I - Initial Assessment/Records Search

Phase II - Problem Confirmation

Phase III - Technology Base Development

Phase IV - Operations (Control Measures)

Engineering-Science (ES) was retained by the Air Force Engineering and Services Center to conduct the Phase I Records Search at Robins AF Base under Contract No. F08637-80-G0009, Call No. 0009, using funding provided by the Air Force Logistics Command. This report contains a

summary and an evaluation of the information collected during Phase I of the IRP.

The goal of the first phase of the program was to identify the potential for environmental contamination from past waste disposal practices at Robins AFB, and to assess the potential for contaminant migration. The activities undertaken in Phase I included the following:

- Review site records
- Interview personnel familiar with past generation and disposal activities
- Inventory wastes
- Determine quantities and locations of current and past hazardous waste storage, treatment and disposal
- Define the environmental setting at the base
- Review past disposal practices and methods
- Conduct field inspection
- Gather pertinent information from federal, state and local agencies
- Assess potential for contaminant migration

To perform the on-site portion of the records search phase, ES assembled the following core team of professionals:

- E. J. Schroeder, Environmental Engineer and Project Manager, MSCE, 14 years of professional experience
- R. E. Zimmermann, Hydrogeologist, BS Geology, 4 years of professional experience
- G. M. Gibbons, Environmental Engineer, MSCE, 3 years of professional experience
- M. I. Spiegel, Environmental Scientist, BS Environmental Science, 5 years of professional experience
- R. M. Reynolds, Chemical Engineer, BSChE, 8 years of professional experience

More detailed information on these individuals is presented in Appendix A.

METHODOLOGY

The methodology utilized in the Robins AFB Records Search began with a review of past and present industrial operations conducted at the

base. Information was obtained from available records such as shop files and real property files, as well as interviews with past and present base employees from the various operating areas of the base. Those interviewed included current and past environmental personnel associated with the Civil Engineering Squadron, the Bicenvironmental Engineering Services Division Office, and the Directorate of Maintenance. Several current or past personnel associated with the fire protection, wastewater treatment plant, pesticide program, fuels management and solid waste collection and disposal were interviewed extensively. Experienced personnel from the tenant organizations were also interviewed. Formal interviews were conducted with 62 personnel to obtain the needed past activity information.

Concurrent with the base interviews the applicable federal, state and local agencies were contacted for pertinent base related environmental data. The agencies contacted and interviewed are listed as follows:

- o U.S. Environmental Protection Agency, Region IV, Atlanta, Georgia
- o U.S. Soil Conservation Service, Atlanta, Georgia
- o U.S. Geological Survey, Atlanta, Georgia
- o Georgia Geological Survey, Atlanta, Georgia
- o Georgia Environmental Protection Division, Atlanta, Georgia
- o City of Warner Robins Water Department, Warner Robins, Georgia
- o Georgia Game and Fish Division of the Department of Natural Resources, Fort Valley, Georgia.

The next step in the activity review was to determine the past management practices regarding the use, storage, treatment, and disposal of hazardous materials from the various operations on the base. Included in this part of the activities review was the identification of all known past disposal sites and other possible sources of contamination such as fuel-saturated areas resulting from spills.

An aerial overflight and a general ground tour of identified sites were then made by the ES Project Team to gather site specific information including (1) visual evidence of environmental stress, (2) the presence of nearby drainage ditches or surface-water bodies, and (3)

visual inspection of these water bodies for any obvious signs of contamination or leachate migration.


A decision was then made, based on all of the above information, whether a potential exists for hazardous material contamination at any of the identified sites using the decision tree shown in Figure 1.1. If no potential exists, the site was deleted from further consideration. For those sites where a potential for contamination was identified, a determination of the potential for migration of the contamination was made by considering site-specific conditions. If the potential for contaminant migration was considered significant, then the site was evaluated and prioritized using the hazardous assessment rating methodology (HARM).

The HARM score indicates the relative potential for contaminant migration at each site. For those sites showing a high potential, recommendations are made to quantify the potential contaminant migration problem under Phase II of the Installation Restoration Program. For those sites showing a moderate potential, a limited Phase II program may be recommended to confirm that a contaminant migration problem does or does not exist. For those sites showing a low potential, no further follow-up Phase II work would be recommended.

FIGURE 1.1

PHASE I INSTALLATION RESTORATION PROGRAM

DECISION TREE



CHAPTER 2
INSTALLATION DESCRIPTION

CHAPTER 2

INSTALLATION DESCRIPTION

LOCATION, SIZE AND BOUNDARIES

Robins AFB is located in middle Georgia approximately 90 miles southeast of Atlanta and 18 miles south of Macon as shown in Figures 2.1, 2.2 and 2.3. The base lies within the lower Ocmulgee River Basin and drains primarily to Horse Creek. The boundaries of the base cover 8,855 acres with facilities for operation, industrial, administrative and supply functions. Present land areas adjacent to the base are primarily as follows:

North - commercial, residential

East - dense forest, swamp

South - commercial, residential

West - commercial, residential

The most prominent physiographic features of the area are the Ocmulgee River and the swamp surrounding the east portion of the base.

BASE HISTORY

The initial construction of Robins AFB began in 1941 on a 3,000 acre tract of land donated by the City of Macon and Bibb County. The base was officially activated in March 1942. Subsequent acquisitions by the Federal government increased the size of the installation to its present 8,855 acres. The original intent was to establish Robins AFB as a maintenance and supply depot, but the installation also was used as a training center. Original facilities included both temporary and permanent structures. After World War II, the base ceased its training functions while continuing its supply and maintenance role.

A second growth surge began in 1949 when the Fourteenth Air Force Headquarters moved to Robins AFB, where it remained until deactivated in 1960. The largest construction program commenced in 1958 to prepare facilities for the 19th Bombardment wing as a tenant organization. Runway enlargement and family housing areas were included in this

FIGURE 2.1




FIGURE 2.2





FIGURE 2.3

ROBINS AFB

SITE PLAN



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

program. In 1962, the runways were further rehabilitated to better accomodate the B-52 and KC-135 aircraft. In 1974, the Technology Repair Center (TRC) was created as a function of the Warner Robins Air Logistics Center (WR-ALC). In addition to depot maintenance responsibility for assigned aircraft, the WR-ALC, TRC, performed repair services on aircraft component systems.

A complete description of Robins Air Force Base history is presented in Appendix B.

ORGANIZATION AND MISSION

The primary mission of Robins AFB are the responsibilities assigned to the Warner Robins Air Logistics Center (WR-ALC). The WR-ALC has a threefold mission as follows:

- a. It is the worldwide logistics manager for assigned aircraft and commodities;
- b. It is the repair center for aircraft and five distinct technologies;
- c. It serves as a storage center at wholesale and retail levels for Air Force spare parts and systems.

The WR-ALC is logistics manager for five Air Force transport aircraft (C-141, C-130, C-7, C-140, C-123), the F-15 fighter, a bomber used in reconnaissance (B-57), eight missiles, five helicopters, seven utility aircraft and seven drones and remotely piloted vehicles. In addition, electronics equipment managed at WR-ALC ties its support to every element of the aerospace combat forces.

WR-ALC is the exclusive technology repair center for airborne electronics for the Air Force. In addition, aircraft repair and maintenance responsibilities for the F-15, C-141 and C-130 are assigned to the WR-ALC. The WR-ALC has various shops (plating, machining, metal bonding, etc.) which support the major workload activities.

The third major mission involves receiving, storing, issuing and transporting material. These functions are carried out in automated warehouses on base. In conjunction with its worldwide missions, WR-ALC has a geographical area of responsibility for logistics support of Air Force installations which include Eastern United States, Newfoundland,

Greenland, Iceland, Bermuda, The Azores and activities in Europe, Africa and the Mid-East.

The 2853rd Air Base Group provides the services and support to carry out the mission of the WR-ALC and other tenant organizations on Robins AFB. Descriptions of the tenant organizations and their missions are presented in Appendix B.

CHAPTER 3

ENVIRONMENTAL SETTING

CHAPTER 3

ENVIRONMENTAL SETTING

The environmental setting of Robins AFB is described in this chapter with the primary emphasis directed toward identifying features which may affect the movement of hazardous waste contaminants. A summary of the environmental setting pertinent to the study are highlighted at the end of the section.

METEOROLOGY

Temperature and precipitation data furnished by the Global Climatology Branch, Robins AFB, are presented in Table 3.1. The period of record is 33 years. The summarized data indicate that the mean annual precipitation is 44.1 inches. Using Thornthwaites Equation (Chow, 1964, p.11.27-28) potential evapotranspiration for the Warner Robins Area is 42.0 inches.

GEOGRAPHY

Robins Air Force Base lies along the upper margin of the Coastal Plain province. The Coastal Plain is part of a large coastal province extending from Long Island, N.Y., to the Mexican border (LeGrand, 1962). Just north of the study area, lies the Piedmont Province (Figure 3.1). The line separating the Piedmont from the Coastal Plain is generally known as the Fall Line. This line separates the more resistant crystalline rocks of the Piedmont from the less resistant deposits of the Coastal Plain.

Locally, Robins AFB lies within the Coastal Plain province but is situated on alluvial deposits along the Ocmulgee River. These deposits form a low terrace about 3 miles wide extending westward from the river to the City of Warner Robins.


TABLE 3.1
ROBINS AFB CLIMATIC DATA

| Month | Precipitation | | Temperature | | |
|-----------|---------------|--------------|------------------|--------------|------------------|
| | Mean (in.) | Max (in.) | Mean max (°F) | Mean (°F) | Mean min (°F) |
| January | 4.0 | 8.4 | 57.5 | 47.5 | 37.2 |
| February | 4.5 | 9.0 | 60.7 | 50.2 | 39.2 |
| March | 4.8 | 10.6 | 67.7 | 56.9 | 45.7 |
| April | 3.2 | 8.4 | 76.9 | 65.4 | 53.6 |
| May | 3.5 | 7.2 | 84.0 | 73.1 | 61.7 |
| June | 3.7 | 7.0 | 88.9 | 78.9 | 68.5 |
| July | 5.1 | 9.3 | 90.3 | 81.1 | 71.6 |
| August | 3.8 | 6.7 | 90.2 | 80.7 | 70.9 |
| September | 2.9 | 7.9 | 85.3 | 75.8 | 65.9 |
| October | 2.2 | 7.4 | 77.1 | 65.8 | 54.0 |
| November | 2.2 | 5.4 | 67.3 | 55.6 | 43.5 |
| December | 4.4 | 11.5 | 59.5 | 49.2 | 38.5 |
| Annual | 44.3 | -- | 75.5 | 65.0 | 54.2 |

Source: Global Climatology Branch, Robins AFB

FIGURE 3.1

PHYSIOGRAPHIC PROVINCES OF GEORGIA



Topography

The Coastal Plain is basically level with an eastward slope of approximately 2-3 feet per mile from the Fall Line to the Georgia coast (Thomson et al, 1956). Robins AFB is located on a low alluvial terrace of the Ocmulgee River. The slope of the base east of Highway 247 is towards the east with elevations of 300 feet MSL on the western edge of the site and 240 feet MSL on the east along the Ocmulgee River. Much of the area bordering the base is low lying swamp land and parts of the base have been constructed over reclaimed swamp land.

Drainage

Robins AFB lies within the drainage basin of the Ocmulgee River, known as the Altamaha basin (Figure 3.2). The installation is drained by several unnamed intermittent streams as well as overland flow. Direction of surface flow is to the east, through the swamp (Figure 3.3).


A large portion of precipitation on the site may not become surface flow but rather infiltrate through the sandy soil. Based on the intensity of precipitation and on the amount of moisture in the soil, this water most likely will recharge the shallow aquifer. Approximately 4.2 inches of total annual precipitation will become recharge to the shallow aquifer. Flooding is a problem on the eastern boundary of the base where the water table intersects the surface and results in swamp development. During flooding periods, Hannah Road would become inundated, as would several other areas at the base including parts of some past waste disposal sites.

Surface Soils

Surface soils of the Robins Air Force Base area have been reported by the USDA, Soil Conservation Service (1967). Twenty soil types have been mapped within installation boundaries and are depicted on Figure 3.4. The individual soil types are discussed on Table 3.2. Base soils fall within two distinct groups: sandy upland soils, and wet, organic lowland types. All the soil types present on the installation exhibit moderate to severe constraints on the development of waste disposal facilities, due either to permeability or flooding potential.

FIGURE 3.2

MAJOR DRAINAGE BASINS OF GEORGIA



LEGEND

— MAJOR DRAINAGE BASIN BOUNDARY

SOURCE: THOMSON, HERRICK, BROWN ET AL.(1956)

0 50 MILES
SCALE





FIGURE 3.3

SURFACE DRAINAGE


ROBINS AFB



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

FIGURE 3.4

ROBINS AFB SOIL ASSOCIATIONS



SOURCE: USDA-SOIL CONSERVATION SURVEY (1987)

TABLE 3.2
ROBINS AIR FORCE BASE SOILS

| Symbol | Description | USDA Texture | Thickness (in.) | Unified Classification | Permeability (in/hr) | HWD Facility Use Constraints |
|------------------|--|--|--------------------|---------------------------|-------------------------|---------------------------------|
| AvP | Alluvial land, wet, 0-2 percent slopes | Organic clay loam, clay | 36+ | SC, CL, CH, OH | Not estimated | Severe - floods |
| Cls | Chastain leaf soils, 0-2 percent slopes | Silt loam, silty clay loam, silty clay; clay | 50 | ML, CL | <0.2 - 0.63 | Severe - floods |
| LcB | Lucy sand, 0-5 percent slopes | Sand, loamy sand, sandy | 60 | SP, SM, SC, CL | 0.63 - >6.3 | Severe - High permeability |
| LcC | Lucy sand, 5-8 percent slopes | Sand, loamy sand, sandy | 60 | SP, SM, SC, CL | 0.63 - >6.3 | Severe - High permeability |
| LcD | Lucy sand, 8-12 percent slopes | Sand, loamy sand, sandy | 60 | SP, SM, SC, CL | 0.63 - >6.3 | Severe - High permeability |
| LcM | Local alluvial land, 0-2 percent slopes | This unit is highly variable. | 24-36 | Properties not estimated | Severe - floods | |
| LqB | Lakeland fine sand, 0-5 percent slopes | Fine sand, sand | 60 | SP, SM | >6.3 | Severe - High permeability |
| LqD | Lakeland fine sand, 5-12 percent slopes | Fine sand, sand | 60 | SP, SM | >6.3 | Severe - High permeability |
| NgA | Norfolk loamy fine sand, 0-2 percent slopes | Loamy fine sand, sandy clay loam | 58 | SM, SC, CL | 0.63 - >6.3 | Moderate Permeability |
| NgB | Norfolk loamy fine sand, 2-5 percent slopes | Loamy fine sand, sandy clay loam | 58 | SM, SC, CL | 0.63 - >6.3 | Moderate permeability |
| NgB ₂ | Norfolk loamy fine sand, 2-5 percent slopes, eroded | Loamy fine sand, sandy clay loam | 58 | SM, SC, CL | 0.63 - >6.3 | Moderate permeability |
| NgC ₂ | Norfolk loamy fine sand, 5-8 percent slopes, eroded | Loamy fine sand, sandy clay loam | 58 | SM, SC, CL | 0.63 - >6.3 | Moderate permeability |
| OgA | Orangeburg loamy fine sand, 0-2 percent slopes | Loamy fine sand, sandy clay loam | 64 | SM, SC | 0.63 - >6.3 | Moderate permeability |
| OgB | Orangeburg loamy fine sand, 2-5 percent slopes | Loamy fine sand, sandy clay loam | 64 | SM, SC | 0.63 - >6.3 | Moderate permeability |
| OgB ₂ | Orangeburg loamy fine sand, 2-5 percent slopes, eroded | Loamy fine sand, sandy clay loam | 64 | SM, SC | 0.63 - >6.3 | Moderate permeability |
| OgC ₂ | Orangeburg loamy fine sand, 5-8 percent slopes, eroded | Loamy fine sand, sandy clay loam | 64 | SM, SC | 0.63 - >6.3 | Moderate permeability |
| Swa | Swamp | Loamy fine sand, sandy clay loam | 64 | SM, SC | 0.63 - >6.3 | Moderate permeability |
| VOD ₂ | Vaucuse-Hoffmann complex, 8-12 percent slopes, eroded | Pine sandy loam, sandy clay loam | 70 | SM, SC, CL | 0.63 - 6.3 | Moderate permeability |
| | Perennial wetland | | | Properties not estimated | Severe - floods | |
| | Loamy sand, sandy clay loam | 60 | SM, SC, CL | 0.63 - >6.3 | Moderate permeability | |

GEOLOGY

The geology of the Warner Robins AFB has been reported by LeGrand (1962), Herrick (1961, 1963, and 1965), Thomson et al. (1956), Herrick and Vorhis (1963), Sonderegger (1978), Pollard (1980), and Mitchell (1979) among others. A brief review of their work has been summarized in support of this investigation.

Stratigraphy

Stratigraphy of the area was studied in order to understand the occurrence and movement of ground water beneath the site. Geologic units ranging from Cretaceous to Quaternary have been described in the Warner Robins area and are presented in Table 3.3. The lithologies of these units are typically unconsolidated material. Older Cretaceous units are encountered at depths of approximately 1700 feet. Crystalline basement rocks are typically encountered at depths greater than 1750 feet below ground surface (LeGrand, 1962).

Regionally, the site is located within the upper Coastal Plain province, but locally, lies on an alluvial terrace of the Ocmulgee River. Sections of the base constructed in swamps have been built up over fill material and do not represent original stratigraphic sequences. The uppermost native unit consists of alluvial deposits of two types depending upon exact location on the base (refer to Geologic Map and legend, Figure 3.5). In the lowland or swampy areas typical of the eastern portion of the base, as well as beneath many of the artificially filled areas, a 5 to 15 foot thick layer of peat and fine silts are encountered, generally underlain by a thin (3 to 5 feet) layer of clay. In upland areas typical of the western half of the base, however, fine alluvial sands and silts are present at the surface and grade into sands and fine gravels with increasing depth. A clay layer not known to exist below these deposits. These sand and fine gravel alluvial deposits also underlie the organic deposits in the lowlands. These are recent deposits and may be 20 to 25 feet thick.

Directly below the surficial alluvial deposits are the most significant geologic units, comprised primarily of several hundred feet of permeable sands. The uppermost major unit is the Providence Sand. It is the youngest and uppermost Cretaceous formation in Georgia.

It consists of light colored sands, interbedded with numerous layers of clay. Thickness of the Providence Sand ranges from 60 to 120 feet and is approximately 60 feet at Robins AFB (LeGrand, 1962).

Immediately underlying the Providence Sand is the Tuscaloosa Formation. Although it does not crop out at the base, it is the oldest outcropping formation of Georgia's Coastal Plain Region (LeGrand 1962). Lithologically, the Tuscaloosa is almost identical to the Providence Sand. It also consists of a light-colored sand with numerous lenticular masses of clay interbedded throughout the formation. These clay beds are generally lenses which can not be traced far. Thickness of this formation ranges from 500 to 600 feet. A generalized geologic section depicting the relationships of major geologic units is presented as Figure 3.6. The Tuscaloosa Formation is a superb aquifer capable of producing tremendous quantities of excellent quality water. Both Robins AFB and the City of Warner Robins use this formation as a source of their water supplies.

Immediately below the Tuscaloosa formation are crystalline rocks of Paleozoic, or possibly older, age. No records were found of wells reaching bedrock, therefore, the exact depth to these units is uncertain. Due to the depth and nature of these formations, they would not be a significant source of water in this area.

Distribution

The areal distribution of geologic units significant to this study is mapped on Figure 3.5, which is modified from the work published by H. E. LeGrand (1962). Most of the site is immediately underlain by alluvial deposits of the Ocmulgee River. The depth to consolidated deposits is not confirmed, but presumed to be at least 1700 feet below the surface, based upon regional geologic data. The western half of the base is dominated by sandy alluvial deposits while the eastern part of the base is underlain by peat and fine grained organic silt deposits.

HYDROGEOLOGY

Ground-water hydrology of the Warner Robins Area has been reported by LeGrand (1962), Mitchell (1979), Pollard and Vorhis (1980), Thomson (1956), Herrick (1961) and Sonderegger (1978). Supporting information

TABLE 3.3
GEOLOGIC FORMATIONS IN ROBINS AFB AREA

| System | Series | Formation | Thickness (feet) |
|------------|------------------------------------|---|---|
| Quaternary | Pliocene to Recent | Swamp Deposits: Alluvial Deposits: | Peat, organic silty clays deposited in Ocmulgee River generally over alluvian. Silts, sands and gravels deposited along major stream borders and in interstream areas. |
| Tertiary | NONE PRESENT UNDERLYING ROBINS AFB | | |
| Cretaceous | Upper | Providence Sand: | Light colored sand interbedded with lenticular layers of clay. |
| | | Tuscaloosa Formation: | Light colored sand interbedded with several lenticular layers of clay. |
| | | Source: LeGrand, 1962 | |

FIGURE 3.5





FIGURE 3.6

GENERALIZED CROSS SECTION OF MAJOR GEOLOGIC UNITS



has been obtained from Robins AFB water department files and files from the City of Warner Robins water plant. Additional information on permeabilities and shallow ground-water quality were obtained from a report by Law Engineering Testing Company (LETCO, 1980).

The Coastal Plain province in Georgia extends from the Fall Line on the north to Florida in the south and from the Savannah River and the Atlantic Ocean on the east to the Chattahoochee River on the west.


The Coastal Plain may be divided into three areas (Figure 3.7) according to aquifer availability and utilization (Thomson, Herrick, Brown et al, 1956). Along the Fall Line, and for a distance of 30 to 60 miles south of it, sand and gravel of Cretaceous age constitute the principle aquifer. Sands and gravels of both the Providence Sand and Tuscaloosa Formation comprise the Cretaceous aquifer which extend to a depth of 600 to 700 feet below the surface at Robins AFB.

An important consideration in assessing ground-water contamination is the water present in the upper alluvial deposits. These deposits are not used locally as a source of water supply, although some degree of interconnection may occur between this and the underlying formations.

Ground water exists beneath Robins AFB under both water table and artesian conditions. The water table is present throughout the base in the upper sandy alluvial deposits. The water table discharges to the east and contributes to the development of a swampy area extending to the Ocmulgee River, LeGrand, (1962). There appears to be a confining bed just below the swamp deposits which would create weak artesian conditions immediately below this upper layer. Both the land surface and the beds are inclined towards the southeast, but the inclination of the beds is steeper. The numerous interbedded clay layers in both the Providence Sand and the Tuscaloosa Formation create artesian conditions within them. Surface water recharge, particularly precipitation, enters the ground, percolates to the water table and flows downgradient to a point where the zone of saturation is interrupted by an impermeable bed. Part of the water may pass above the bed and continue to flow under water table conditions and the other part of it flows beneath the confining bed. This is confined or artesian water; it will rise in a tightly cased well to a height above the bottom of the confining bed. The interlayering of clay and sand results in a composite artesian

FIGURE 3.7

PRINCIPAL AQUIFERS OF THE COASTAL PLAIN OF GEORGIA



system consisting of several artesian sand aquifers, and intervening clay confining beds.

In the study area, deposits of Cretaceous age furnish adequate water supplies to present users and are capable of yielding large supplies to future developers. The City of Warner Robins obtains its water from wells screened in various sand layers of the Tuscaloosa Formation (See Well Logs - Appendix F). Figure 3.8 shows the location of these wells and Table 3.4 gives a brief summary of the wells. The city wells have capacities which range from 1000 to 1600 gpm indicating the large quantity of water available from this aquifer. Robins AFB has 12 wells. The logs of these wells are shown also in Appendix F. Of these 12 wells, numbers 1 through 8 are used as a drinking water source. Locations and a summary of these wells are given in Figure 3.9 and Table 3.5. Well No. 9 furnishes water supplies to the Federal Aviation Administration (FAA) building. Well No. 10 is not connected to the public system but is an independent two-inch diameter well used for drinking water supply at the skeet range. Wells No. 11 and No. 12 are used for water level maintenance at Luna and Scout Lakes.


Ground-Water Quality

Ground-water flow direction in the Cretaceous aquifer is in an easterly-southeasterly direction (LeGrand, 1962), discharging to the Ocmulgee River locally. Natural ground-water quality in the Cretaceous aquifer has been reported to be excellent (LeGrand, 1962). Results from samples collected from these wells in January of 1978 indicated the quality to be excellent with very little mineral content present. Results did not indicate any contamination of these wells for the parameters tested; an organic scan was not run.

Shallow ground water in the vicinity of Landfill No. 4 was reported by Law Engineering Testing Company (LETCO, 1980) to be contaminated. Several shallow monitoring wells installed by LETCO (Figure 3.10) indicate the presence of various concentrations of chloride, dissolved solids, nitrate, cyanide, arsenic, calcium, chromium, lead, manganese and zinc. An organic scan was run on monitoring wells nos. 4, 5, 15, and 18. The results of this analyses indicated the presence of methylene chloride, phenol, diethylphthalate, bis(2-ethylhexyl)phthalate, benzene, chlorobenzene, trans-1,2,dichloroethylene,

FIGURE 3.8

City of Warner Robins WELL LOCATIONS



SOURCE: CITY OF WARNER ROBINS, WATER DEPARTMENT DOCUMENTS (1981)

TABLE 3.4
CITY OF WARNER ROBINS MUNICIPAL WELLS


| Well No. | Casing Diam. (in.) | Total Depth (feet) | Capacity (GPM) | Static Depth Below Ground Surface (Feet) | Motor H.P. | Date Drilled | Remarks |
|----------|-----------------------|-----------------------|-------------------|---|------------|--------------|--|
| 1A | 12 | 540 | 1557 | 129 | 150 | 1981 | 10' screens at 340', 370' and 420' 20' screens at 440', 470' & 510' |
| 2A | 25 | 580 | 1613 | 132 | 150 | 1979 | 10' screens at 174', 300', 478' and 495' 40' screen at 400' |
| 3 | 10 | 415 | 1000 | 105 | 75 | 1961 | 10' screen at 360' 20' screen at 275' 15 ' screen at 390' |
| 4 | 12 | 390 | 1559 | 122 | 100 | 1960 | 10' screen at 240' and 320' 20' screen at 360' |
| 5 | 12 | 422 | 1100 | 132 | 75 | 1962 | 10' screens at 235' & 270' 20' screen at 392' 5' screen at 349' |
| 6 | 12 | 435 | 1050 | 116 | 100 | 1968 | 10' screens at 250', 390' and 415' 20' screen at 290' |
| 7 | 12 | 440 | 1641 | 105 | 150 | 1972 | 10' screen at 240', 20' screen at 345', 30' screen at 400' |
| 8 | 12 | 430 | 1641 | 101 | 150 | 1970 | 20' screens at 240', 360' and 400' 15' screen at 305' |
| 9 | 12 | 490 | 1613 | 101 | 150 | 1971 | 10' screens at 330' and 405' 20' screens at 360' and 460' |
| 10 | 12 | 480 | 1613 | 56 | | 1976 | |
| 11 | 12 | 440 | 1600 | 47 | 100 | 1976 | |

Source: City of Warner Robins Water Plant Files

FIGURE 3.9

WATER SUPPLY WELL LOCATIONS

ROBINS AFB



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

TABLE 3.5
SUMMARY OF ROBINS AFB WELLS


| Bldg No. | Well No. | Casing Diam. | Feet Depth | Capacity (GPM) | Orig. Static Level | Motor H.P. | Pump Type | Date Drilled | Remarks |
|----------|----------|---------------------------------|------------|----------------|--------------------|------------|------------------|--------------|-----------|
| 186 | 1 | 12" | 362 | 835 | | 100 | Vertical turbine | 1941 | Redrilled |
| | 1A | 12" | 389 | 950 | | | | 1975 | |
| 164 | 2 | 12" | 255 | 900 | | 100 | | 1941 | Redrilled |
| | 2A | 12" | 386 | 900 | | | | 1974 | |
| | 3 | 12" | 298 | 1300 | | | Vertical turbine | 1942 | |
| 648 | 4 | 12" | 430 | 775 | | 60 | | 1943 | |
| | 4A | 12" | 385 | 992 | | 60 | | 1956 | |
| 511 | 5 | 12" | 355 | 700 | | | | 1942 | Redrilled |
| | 5A | 12" | 430 | 1230 | 45' | 100 | | 1963 | |
| | 6 | 12" | 367 | 1500 | 45' | 150 | | 1943 | Redrilled |
| | 6A | 12" | 495 | 1500 | 63' | | | 1976 | |
| | 7 | | | | | | | 1944 | Redrilled |
| | 7A | 12" | 490 | 992 | 38' | 100 | | 1958 | |
| 61 | 8 | 8" | 522 | 900 | 9' | 75 | | 1958 | |
| | 9 | 6" | 140 | 30 | 60' | 3 | Submersible | 1958 | |
| | 9A | - | 135 | 300 | | 7 1/2 | Submersible | 1970 | 6"Outlet |
| | 10 | (Small well - data unavailable) | | | | | | | |
| | 11 | | 180 | 10 | 45' | 1 | Jet pump | 1968 | 2"Outlet |
| | 12 | | | 20 | | 1 | Submersible | 1966 | 4"Outlet |

Source: Robins AFB Files

Note: The A notation after the Well No. indicates that the well was redrilled.

FIGURE 3.10

ROBINS AFB BORING & MONITORING WELL LOCATIONS



LEGEND

- AUGER BORING (Diamond)
- MONITORING WELL (TEST BORING) (Solid Circle)
- MONITORING WELL (AUGER BORING) (Inverted Triangle)
- INTERMITTENT STREAM (Dashed Line)
- PERENNIAL STREAM (Solid Line)

SOURCE: LETCO (1980)

trichloroethylene, and 1,1,2,2 tetrachloroethylene in the shallow ground water downgradient of Landfill No. 4 and the sludge lagoon. A summary of the LETCO ground-water quality data is included in the appendix. This study was conducted at Landfill No. 4 and shallow ground-water quality elsewhere on the base has not been investigated.

In the area of Landfill No. 4, weak artesian conditions may exist below the thin clay layer which underlies the swamp deposits (LeGrand, 1962, Figures 6). Both of these factors (clay layer and artesian conditions) may affect the concentrations of contaminants entering the lower aquifer. The upper clay layer, which is probably restricted to the zone underlying the swamp deposits, may act as a confining bed preventing any further infiltration. It is important to note however, that organic compounds such as methylene chloride and other chlorinated hydrocarbons have the ability to move through clay more rapidly than water would move through clay (Roberts et al, 1980, and Giger and Molnar-Kubica, 1978). The mechanisms through which this occurs are extremely complex but have been shown through experimentation. Under normal circumstances, weak artesian conditions appear to exist in the deposits immediately below the clay. This may cause the "upwelling" of water from below the fill rather than infiltration from the fill into the aquifer. The fate of organics in the subsurface is extremely difficult to predict because of the uncertainty involved in describing precise attenuation mechanisms occurring under unsaturated and saturated conditions.

SURFACE WATER QUALITY

Robins AFB has several streams and surface drainage systems which originate on or flow through the base property. All of these streams drain in a general west-to-east course and ultimately flow to the Ocmulgee River either via defined creek beds such as Horse Creek or by dissipated overland drainage through the adjacent swamp areas. The streams have been monitored routinely at several locations by the base Bioenvironmental Engineering Services Division (BESD) in compliance with State permit requirements. In addition to the required monthly sampling program, the BESD conducted a baseline chemical characterization survey of the non-potable surface waters within the base between 1978 and 1979

(Talley, et al., 1979). Figure 3.11 depicts the surface water monitoring stations presently sampled for NPDES permit compliance as well as the additional stations sampled during the 1978-1979 baseline survey. Summaries of the data compiled during the 1978-1979 study and the 1981 NPDES data are included in Appendix C.

The 1978-1979 water quality survey detected levels of phenol from 0.05 to 1.5 mg/l in the Hannah Road runoff ditch, Station 004. Ammonia-nitrogen concentrations at Station 004 ranged between 4.0 and 8.6 mg/l and manganese concentrations ranged from 0.057 to 0.18 mg/l. The phenol and ammonia values may be attributable to the sanitary sewage treatment plant No. 1 discharge or to seepage from past landfills adjacent to the creek. The 1981 NPDES data revealed only one sample which exceeded the 2.0 mg/l ammonia nitrogen limitation at a concentration of 2.4 mg/l. Phenols were not sampled at this location; however, the phenol data collected directly from the sanitary treatment plant No. 1 effluent (Station 009) were at or below the NPDES limits. Oil and grease concentrations ranged from 0.3 to 6.2 mg/l at Station 004 and from 0.2 to 4.7 mg/l at Station 009. The oil and grease concentrations at Station 004 was frequently higher than those detected upstream at Station 009, signifying that oil and grease may be entering the ditch at some point downstream of the industrial wastewater treatment plant.


All remaining monitoring stations were found to have good water quality values. The only noticeably high constituent detected was total iron in samples collected from Stations 001 and 005 during the 1978-1979 survey. These concentrations ranged from 0.28 to 3.4 mg/l for Station 001 and 0.57 to 1.8 mg/l for Station 005.

WETLAND AREAS

Robins AFB has 1,178 acres of wetlands in the form of an unimproved river swamp system. The swamp area provides important functions for the sustenance of aquatic life and water quality in the river and streams receiving its drainage. These functions include providing breeding

FIGURE 3.11

ROBINS AFB SURFACE WATER QUALITY MONITORING STATION LOCATIONS



grounds for various aquatic organisms as well as providing the streams with vital organic matter which serves as a food source for the many organisms inhabiting these areas. In addition, the swamp is known to harbor two species of animals listed by the Federal government as threatened or endangered. These species are the American alligator and the red-cockaded woodpecker. Ten alligators have been sighted on Robins AFB and it is estimated that approximately 15-20 alligators actually exist on base. Approximately ten red-cockaded woodpeckers have been sighted on the base. A list of the threatened or endangered vertebrate species potentially present is included in Appendix C. There are also several species of threatened or endangered plants which potentially occur within the swamp area.

Summary of Environmental Settings

The environmental setting data reviewed for this study indicate the following key items concerning the impact of past waste disposal practices on the base:

- o Alluvial deposits cover the upper 20 to 40 feet of the base. The eastern part of the base is swampy with peat deposits covering the upper 10 to 15 feet and underlain by a thin layer of clay. The western part of the site consists of more sandy alluvial deposits which extend eastward below the swamp deposits.
- o The water table beneath the base is shallow, particularly to the east where a surface discharge contributes toward the creation of a swampy area. In the western part of the base, the surface soils are sandy and infiltration of precipitation is expected to be high. This infiltration may directly recharge the shallow aquifer.
- o The primary regional aquifer, the Cretaceous aquifer, underlies Robins AFB at a depth of about 40 to 50 feet and extends to a depth of approximately 650 feet below the surface. It consists of sand with a few clay lenses interspersed throughout its thickness.
- o Robins AFB obtains its water supply from twelve wells distributed over the installation. The City of Warner Robins has a separate system consisting of 11 wells, located throughout the

city. All wells are drilled into the Tuscaloosa Formation of the Cretaceous aquifer.

- Recharge for the Cretaceous aquifer occurs west of Robins AFB where the Providence sand outcrops at the surface. Some recharge may also occur beneath the base as some interconnection between alluvial and underlying deposits may occur.
- Area precipitation rates (44.1 inches per year) are higher than potential evapotranspiration rates (42 inches per year).
- Approximately 1200 acres of wetlands in the form of an unimproved river swamp system are located on the east side of the base. The wetlands are known to harbor two species of animals listed by the Federal government as threatened or endangered; American alligator and the red-cockaded woodpecker.

From these major points, it may be seen that the potential for the generation and migration of contamination caused by past waste disposal practices is high. The presence of shallow ground-water contaminants has been documented near landfill No. 4 (LETCO, 1980). Although the production wells located on the base are several hundred feet deep, some degree of interconnection between upper and lower aquifers potentially could occur. Information obtained from base production wells and from ground-water monitoring data (LETCO, 1980) indicate that the base is located in a ground-water discharge area; i.e. the hydraulic gradient is upward. However, the production wells will alter this gradient within their particular zone of influence and may induce the downward movement of leachate. On the eastern edge of the base, some migrating contaminants may be transported in shallow ground-water flow and discharged at the surface into the swamp.

CHAPTER 4

FINDINGS

CHAPTER 4

FINDINGS

To assess hazardous waste management at Robins Air Force Base, waste generation and disposal methods were reviewed. This chapter summarizes the hazardous waste generated by activity, describes waste disposal methods, identifies the disposal sites located on the base, and evaluates the potential for contaminant migration.

PAST SHOP AND BASE ACTIVITY REVIEW

To identify past base activities that resulted in generation and disposal of hazardous waste, a review was conducted of current and past waste generation and disposal methods. This review consisted of interviews with base employees, a search of files and records, and site inspections.

The source of most hazardous wastes on Robins AFB can be associated with one of the following activities:

- o Industrial shops
- o Fire protection training
- o Pesticide utilization
- o Fuels management

The following discussion addresses only those wastes generated on base which are either hazardous or potentially hazardous. In this discussion a hazardous waste is defined as hazardous by the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA). A potentially hazardous waste is one which is suspected of being hazardous although insufficient data are available to fully characterize the waste material.

Industrial Shops

The industrial operations at Robins AFB can be divided into two major groups as follows: The Directorate of Maintenance and other base facilities or tenant organizations. Five major divisions embody the majority of the shop activities for the Directorate of Maintenance. The divisions include the Aircraft Division, Plant Management Division, Airborne Electronics Division, Quality Division and Industrial Products Division. A principal source of waste materials generated at Robins AFB has been the Directorate of Maintenance areas.

Other base maintenance support activities include the industrial shops from the Directorate of Distribution, the 2853rd Air Base Group, the 2853rd Civil Engineering Squadron, the 5th Combat Communications Group, the 19th Bombardment Wing, and the 1926th Communication Installation Group. These industrial operations include primarily vehicle, electrical and aircraft maintenance and repair.

In order to identify those shops which handle hazardous materials and/or generate hazardous waste, a review was made of the Bioenvironmental Engineering Services Division shop files. The results of this file review are shown in Appendix D, Master List of Industrial Shops.

For those shops identified that handled hazardous materials or generated hazardous waste, key personnel within the Directorate of Maintenance and other base maintenance support functions were interviewed. A timeline of disposal methods was established for major wastes generated. The information from the interviews with base personnel and base records is summarized in Table 4.1. This table shows the building locations as well as the waste material names, waste quantities, and disposal method timeline.

INDUSTRIAL OPERATIONS (Shops)

HAZARDOUS WASTE MANAGEMENT

1 of 6

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY ⁽¹⁾ | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | |
|-----------------------------|--|---|--|--|--------------------------------------|---------------------------------------|------------------------------|
| | | | | 1950 | 1960 | 1970 | 1980 |
| DIRECTORATE of DISTRIBUTION | | | | | | | |
| HAZARDOUS CHEMICAL STORAGE | 327 | NON-SALABLE PAINT STRIPPERS NON-SALABLE, EXPIRED SHELF-LIFE CHEMICALS | 10 to 15 GALS./YR. 15 to 30 LBS./YR. | SANITARY SEWER | IWTP ⁽²⁾ | DPDO ⁽⁴⁾ ON-BASE LANDFILLS | DPDO OFF-BASE CONTRACTORS |
| PAINT SHOP | 354 | DDT PAINT SHOP WASTES, MISCELLANEOUS | 20 to 40 LBS./2 to 5 YRS. 25 GALS./MO. | DPDO ON-BASE LANDFILLS | DPDO OFF-BASE CONTRACTORS | DRUMMED TO BASE LANDFILLS | DPDO |
| CUN ROOM (Cleaning) | 368 | SOLVENTS | 25 GALS./18 MOS. | 1980 | | | |
| DIRECTORATE of MAINTENANCE | | | | | | | |
| AIRCRAFT DIVISION | | | | | | | |
| CORROSION CONTROL | 54 (1979 to Present) 110 (to 1979) | PHENOLIC/NON-PHENOLIC PAINT STRIPPERS PHOSPHORIC ACID CLEANER CHROMIC ACID CLEANER | 1,500 to 2,000 GALS./WK. 800 GALS./MO. 800 GALS./MO. 55 GALS./WK. | NEGLIGIBLE STRIPPING 1957 | STORM SEWER | IWTP | |
| PD-683 | 7/89 (Bldg. 89 - 1964 to Present) 41, 47, 48 & 49 | PD-680 PAINT RESIDUE, THINNERS & SOLVENTS HYDRAULIC FLUID PD-680 WASTE OILS | 800 GALS./MO. 100 GALS./MO. 50 GALS./MO. | NEUTRALIZED TO SANITARY SEWER CHEMICAL REDUCTION TO STORM SEWER | IWTP | | |
| PAINT SHOP | | | | BURNED IN FPT AREAS | DPDO | | |
| NOSE DOCKS | | | | STORM SEWER OR BURNED IN FPT AREAS | SLUDGE LAGOON OR ON-BASE LANDFILL | DPDO | |
| ENGINE REPAIR SHOP | 125 | | | BURNED IN FPT AREAS | DPDO | | |
| LANDING GEAR SHOP | 125 | | 50 GALS./2 MOS. | BURNED IN FPT AREAS | DPDO | | |

KEY

- ?/ ACTIVITY ASSUMED TO OCCUR IN A SHOP LOCATED ELSEWHERE
- CONFIRMED TIME-FRAME DATA BY SHOP PERSONNEL
- - - ESTIMATED TIME-FRAME DATA BY SHOP PERSONNEL

(1) BASED ON CURRENT RATES AND BEST ESTIMATES OF PAST RATES

(2) IWTP = INDUSTRIAL WASTE TREATMENT PLANT

(3) FPT = FIRE PROTECTION TRAINING

(4) DPDO = DEFENSE PROPERTY DISPOSAL OFFICE

INDUSTRIAL OPERATIONS (Shops)

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | |
|-------------------------------|---|--|---|--|---------------------------------------|------|------|
| | | | | 1950 | 1960 | 1970 | 1980 |
| AIRBORNE ELECTRONICS DIVISION | | | | | | | |
| COMPOSITE - ALL SHOPS | 640 & 645 | ACETONE PD-680 METHYLENE CHLORIDE METHYL ETHYL KETONE PAINT THINNERS POLYSULFIDE SEALANT TRICHLOROETHYLENE (to '79) TRICHLOROETHANE (from '79) PAINT WASTE | 600 to 800 GALS./MO. (1950s to 1972) 100 GALS./WK. (1972 to Present) | BURNED IN FPT AREAS | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO | |
| INDUSTRIAL PRODUCTS DIVISION | | | | | | | |
| PAINT SHOP | 125 (Bldg. 140 - 1971 to Present) | PAINT RESIDUE, THINNERS & SOLVENTS PD-680 TRICHLOROETHYLENE WASTE OILS | 50 to 100 GALS./1/2 WKS. 110 GALS./MO. 50 GALS./WK. 100 GALS./MO. 110 GALS./MO. | BURNED IN FPT AREAS | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO | |
| TURRET SHOP | 7/140 (Bldg. 140 - 1971 to Present) | METHYL ETHYL KETONE HYDRAULIC FLUID TRICHLOROETHYLENE CARBON REMOVER, PHENOLIC CHROME BATHS | 50 GALS./MO. 50 GALS./MO. 50 GALS./MO. 100 GALS./MO. 200 to 400 GALS./YR. | BURNED IN FPT AREAS | SLUDGE LAGOON | DPDO | |
| PROPELLER & PROP CLEANING | 7/140 (Bldg. 140 - 1971 to Present) | WASTE ACID CLEANERS SLUDGE CYANIDE BATHS | 100 GALS./MO. (1969 to Present) 200 LBS./YR. (1955 to 1969) 500 GALS./YR. (1969 to 1971) | CHEMICAL REDUCTION TO STORM SEWER | STORM SEWER | INTP | |
| ELECTROPLATING SHOP | | | | | SANITARY SEWER | INTP | |

INDUSTRIAL OPERATIONS (Shops)

HAZARDOUS WASTE MANAGEMENT

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | |
|---|--|--|---|---|---------------------------------------|---------------------------------------|--------------|
| | | | | 1950 | 1960 | 1970 | 1980 |
| INDUSTRIAL PRODUCTS DIVISION (continued) | | | | | | | |
| ELECTROPLATING SHOP (continued) | [112 (1959 to Present) 130 (1955 to 1969) 125 (1969 to 1981)] | WASTE ALKALINE CLEANERS TRICHLOROETHYLENE TRICHLOROETHANE PERCHLOROETHYLENE | 400 GALS./3 MOS. 150 GALS./WK. 150 GALS./WK. 150 GALS./WK. | STORM SEWER BURNED IN FPT AREAS | IWTP DPDO | DPDO | |
| HYDROSTATIC TESTING | 150 | PAINT WASTES & RESIDUE | 30 GALS./MO. | STORM SEWER BURNED IN FPT AREAS | IWTP DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO |
| BATTERY SHOP | 150 | WASTE ACIDS | 25 GALS./MO. | SANITARY SEWER BURNED IN FPT AREAS | IWTP DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO |
| PARTS CLEANING & METAL BOND | 169 | PAINT STRIPPER, PHENOLIC TRICHLOROETHANE | 110 GALS./DAY 55 GALS./WK. | BURNED IN FPT AREAS | IWTP DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO |
| PLASTICS SHOP & RADOME SHOP | 670 & 680 | METHYL ETHYL KETONE TOLUENE | 150 GALS./MO. | STORM SEWER OR BURNED IN FPT AREAS | IWTP DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO |
| 5 COMBAT COMMUNICATIONS GROUP (CCG) | | | | | | | |
| GROUND POWER SHOP | 614 | WASTE GENERATOR OIL | 50 GALS./3 WKS. | 1964 DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS | 1974 DPDO | |
| VEHICLE MAINTENANCE | 655 | SKIMMED OIL SLUDGE | | | | | |
| 19 BOMBARDMENT WING (BW) | | | | | | | |
| FIELD MAINTENANCE SQUADRON (FMS) | | | | | | | |
| FUEL SYSTEM SHOP | 52 | SKIMMED OIL/FUEL SLUDGE | 200 GALS./4 MOS. | | | SLUDGE LAGOON OR ON-BASE LANDFILLS | 1965 DPDO |

TABLE 4.1 (continued)
INDUSTRIAL OPERATIONS (Shops)
HAZARDOUS WASTE MANAGEMENT

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | | | |
|---|-------------------------|---|--|--|------------------------------------|------|-------------------|------|--|
| | | | | 1950 | 1960 | 1970 | 1976 | 1980 | |
| 19 BOMBARDMENT WING (BW) (continued) | | | | | | | | | |
| FIELD MAINTENANCE SQUADRON (FMS) | | | | | | | | | |
| PNEUMdraulics Shop | 79 | PD-680 HYDRAULIC FLUID WASTE BATTERY ACID PAINT RESIDUE THINNERS PAINT STRIPPERS ACID CLEANERS METAL BRIGHTENERS | 160 GALS./6 MOS. 1 QT./MO. 10 GALS./6 MOS. | 1965 | DPDO DISPOSED OF AT BLDG. 75 | 1965 | WTP VIA BLDG. 159 | 1965 | |
| ELECTRIC SYSTEMS SHOP | 79 | | | | | | | | |
| CORROSION CONTROL | 80 | | | | | | | | |
| AEROSPACE GROUND EQUIPMENT (AGE) REPAIR SHOP & ACE SERVICEING SHOP | 82 & 85 | JP-4 MOGAS HYDRAULIC FLUID PAINT THINNER PAINT STRIPPER LUBRICATION OIL | 100 GALS./MO. 100 GALS./MO. | 1965 | DPDO | 1965 | DPDO | 1965 | SLUDGE LAGOON OR ON-BASE LANDFILLS DPDO |
| PROPELLION BRANCH | 76 | JP-4 ENGINE OIL | 200 GALS./MO. | 1965 | DPDO | 1965 | DPDO | 1965 | SLUDGE LAGOON OR ON-BASE LANDFILLS DPDO |
| MUNITION MAINTENANCE SQUADRON EQUIPMENT MAINTENANCE BRANCH | 86 | HYDRAULIC FLUID PD-680 | 100 GALS./MO. 10 GALS./MO. | Also included in ACE Shop waste total 36 GALS./MO. | 1965 | DPDO | 1965 | DPDO | SLUDGE LAGOON OR ON-BASE LANDFILLS DPDO |

TABLE 4.1 (continued)
INDUSTRIAL OPERATIONS (Shops)

HAZARDOUS WASTE MANAGEMENT

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | |
|---|-------------------------|--------------------------|--|---|------|------|------|
| | | | | 1960 | 1965 | 1970 | 1980 |
| 19 BOMBARDMENT WING (BW) (continued) | | | | | | | |
| ORGANIZATION MAINT. SQUADRON | | | | | | | |
| BOMBER-PHASE MAINTENANCE | 67 | ENGINE OIL | 100 GALS./MO. | | DPDO | | |
| TANKER-PHASE MAINTENANCE | 81 | HYDRAULIC FLUID | 100 GALS./MO. | | DPDO | | |
| 1928 COMMUNICATIONS & INSTALLATION GROUP | | | | | | | |
| MINOR VEHICLE MAINTENANCE | 978 | SKIMMED OIL SLUDGE | 20 to 30 GALS./YR. | | | | |
| WEATHER EQUIPMENT REPAIR | 1644 | WASTE OILS, FLUIDS | 5 GALS./YR. | | | | |
| 2853 AIR BASE GROUP (ABG) | | | | | | | |
| VEHICLE TRANSPORTATION DIVISION | | | | | | | |
| FUEL VEHICLE REPAIR | 190 | MOTOR OIL | BURNED IN FPT AREAS | | | | |
| VEHICLE MAINTENANCE SHOP | 302 | AUTOMATIC TRANS. FLUID | DPDO | | | | |
| AUTO MAINTENANCE SHOP | 307 | HYDRAULIC FLUID | | | | | |
| PAINT & BODY SHOP | 304 | THINNERS & PAINT REMOVER | STORM SEWER OR BURNED IN FPT AREAS | | | | |
| | | PAINT BOOTH SLUDGE | SLUDGE LAGOON OR ON-BASE LANDFILLS | | | | |
| | | PAINT RESIDUE | SLUDGE LAGOON OR ON-BASE LANDFILLS | | | | |
| 2853 CIVIL ENGINEERING SQUADRON (CES) | | | | | | | |
| INDUSTRIAL WASTE TREATMENT PLTS. | 141, 147 & 314 | IWTP SLUDGES | SANITARY SEWER, STORM SEWER OR ON-BASE LANDFILLS | | | | |
| TRANSFORMER STORAGE | 1190 | PCB TRANSFORMERS | SLUDGE LAGOON | | | | |
| | | | ELECTRIC REHABILITATION CONTRACTORS (CES) | | | | |
| | | | DPDO | | | | |

INDUSTRIAL OPERATIONS (Shops)

HAZARDOUS WASTE MANAGEMENT

| SHOP NAME | LOCATION (BLDG. NO.) | WASTE MATERIAL | WASTE QUANTITY | METHOD(S) OF TREATMENT, STORAGE & DISPOSAL | | | |
|--|-------------------------|-----------------------------|-------------------------------------|---|---------------------------------------|------|-------------------------------------|
| | | | | 1950 | 1960 | 1970 | 1980 |
| 2853 CIVIL ENGINEERING SQUADRON (CES) | | | | STORM SEWER, OR BURNED IN FPT AREAS | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO | |
| PAINT SHOP | 275 | PAINT RESIDUE THINNERS | 100 GALS./3 MOS. 50 GALS./3 MOS. | STORM SEWER, OR BURNED IN FPT AREAS | SLUDGE LAGOON OR ON-BASE LANDFILLS | DPDO | |
| ENTOMOLOGY UNIT | 295 & 296 | RINSED CONTAINERS | 10 to 20 EA./YR. | | | | ON-BASE LANDFILLS → COUNTY LANDFILL |
| | | OFF-SPEC GRANULAR MALATHION | 40 TONS (One-Time Occurrence) | | ON-BASE LANDFILL → 1964 | | |
| | | AEROSOL CANS OF DDT | 240 CANS (One-Time Occurrence) | | HAZARDOUS WASTE BURIAL SITE ▲ 1976 | | |
| CROUNDS SHOP | 591 & 593 | RINSED CONTAINERS | 10 to 12 EA./YR. | | ON-BASE LANDFILLS → 1967 | | |

From the early 1940's to approximately 1965, many ignitable waste chemicals and petroleum compounds were burned in fire protection training pits during training exercises. Waste solvents were burned in the fire protection training pits through approximately 1955, then the base began disposal of the material through resale or reuse. Rinse water from the plating and painting operations were previously discharged to the storm sewer. Cyanide solutions from the plating facility were discharged to the sanitary sewer system.

Burning of ignitable and other chemical waste in the fire protection training pits was decreased about 1965 due to air quality considerations. An industrial waste treatment system became operational in 1964 and expanded in 1969. Treatment began of waste streams from facilities such as the Electroplating Shop and the Corrosion Control Shop which had previously discharged to the storm sewer or sanitary sewer. A sludge lagoon was also constructed in the mid-1960's to dispose of industrial waste treatment plant sludge. Many types of waste chemicals and chemical sludges were also disposed of in the sludge lagoon. Paint residue, thinners and paint skimmings were typically disposed of in the on-base landfills. Petroleum products were sold by DPDO beginning in approximately 1965.

In 1978, the on-base disposal of all hazardous solid wastes and most non-hazardous solid waste was discontinued. Solid wastes were disposed of off-base by contract disposal. New industrial waste treatment plant sludge disposal facilities were also completed and started up about this time.


Fire Protection Training

The Fire Department has operated four fire protection training areas since 1943. These areas were used for practice exercises where petroleum based fires are set and then extinguished. The following list gives specific designation for the areas and their approximate period of use (See Figure 4.1).

| <u>Fire Protection Training Area</u> | <u>Period of Operation</u> |
|--------------------------------------|----------------------------|
| No. 1 | 1943-mid 1950's |
| No. 2 | Mid 1950's-mid 1960's |
| No. 3 | Mid 1960's-1969 |
| No. 4 | 1969-present |

FIGURE 4.1

ROBINS AFB
FIRE PROTECTION TRAINING AREAS



NOTE: FIRE PROTECTION TRAINING AREA NO. 1 IS SITUATED IN THE AREA BETWEEN SECOND STREET AND THE SOUTHERN END OF THE MAIN RUNWAY

SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

In the past, the common mode of operation was for the Fire Department to dump drums of contaminated fuel, oil, solvents, and ignitable chemicals on previously water saturated ground. The area was repeatedly ignited and extinguished during each exercise until it would no longer burn. This was the standard procedure until air pollution control regulations became more stringent in the mid 60's. These regulations curtailed the number of exercises and required the use of only uncontaminated JP-4 (less than 10 percent contaminants).

High pressure water was used to extinguish fires at Robins AFB until the introduction of protein foam in 1950. The protein foam was replaced in 1972 by the AFFF as an extinguishing agent for fire fighting training exercises.

Fire Protection Training Area No. 1

Fire protection training area No. 1 was located in the general vicinity of landfills No. 1 & No. 2, near the POL bulk storage area, however, the exact location of fire protection training area No. 1 could not be determined. This area was an unlined pit surrounded with earthen dikes and was used twice a week from 1943 until the mid 1950's.

Fire Protection Training Area No. 2

Fire protection training area No. 2 was actually a number of sites in the general area of Lake Luna as shown in Figure 4.2. These sites were used from the mid 1950's until the early to mid 1960's. During this period the Fire Department did not use a pit but conducted training exercises on open sites. Operating procedures included saturating the ground with water and then burning various flammable materials or chemical wastes.

Fire Protection Training Area No. 3

Fire protection training area No. 3, was another diked, unlined pit. This area was located close to the present site (No. 4), as shown in Figure 4.3. The site was operated from the early 1960's until the construction of the present training area in 1969. As previously mentioned, air pollution regulations curtailing the number of exercises and requiring the use of only uncontaminated fuel became effective during this period.

FIGURE 4.2





FIGURE 4.3



Fire Protection Training Area No. 4

The current site, fire protection training area No. 4, is a concrete lined, diked pit located in the SAC area as shown in Figure 4.3. Permanent fuel tanks with gravity feed were also installed during construction. Training exercises are limited to twice per quarter using uncontaminated JP-4.

Pesticide Utilization

Pest control has been an on-going program since the inception of Robins AFB. The Entomology Shop initially administered the pest control program while the grounds and pavements shop was responsible for weed control. In 1967, the two programs were combined and the Entomology Shop became responsible for both programs. The Entomology Shop has always been located in building 295 and the chemical storage areas have been situated in the facilities neighboring the shop. Grounds and pavements has been located in the same compound as Entomology occupying facilities 294 and 286.

The pesticide program entails routine and specific job order spraying. Both truck-mounted and hand-held sprayers are utilized. A listing of the pest and weed control chemicals presently on hand is included in Appendix C. Standard procedures include mixing and using all pesticides immediately or storing any residual mixtures for use within 15 to 30 days. In 1966, a wash rack was constructed in an area adjacent to the Entomology Shop to rinse empty containers and spray equipment. Water collected in the wash rack is stored in an underground tank. The water is routinely pumped and used as make-up water for chemical mixing. Prior to the wash rack installation, Entomology Shop personnel interviewed stated that excess herbicides were usually sprayed on the adjacent lot. Empty pesticide containers are presently triple rinsed, punctured or crushed and disposed along with the base refuse.

It was indicated by several base personnel that a one time quantity of pesticide, approximately 40 tons, had been disposed in Landfill No. 2. It is suspected that the material was a mixture of clay or aggregate with 1.5 to 10 percent granular malathion used for aerial spraying to control mosquitoes and gnats. Further investigation revealed that the disposal operation would likely have occurred prior to 1964.

In October 1979, 55 gallons of DDT solution leaked from a drum stored in a gravel section of the chemical storage area adjacent to building 295, (Figure 4.4). The Bioenvironmental Engineering Services Division collected soil samples from the site and the drainage paths from the storage area to determine the extent and degree of migration of the DDT (SGB, 1980). Soil under the gravel was found to be primarily a sandy loam. The chemical analyses were conducted by USAF OEHL, Brooks AFB, TX and are summarized below:

| <u>Location</u> | <u>Concentration DDT in ppm</u> |
|---|---------------------------------|
| Surface of soil under pallet | 2144 |
| Crystalline material from pallet | 55 |
| Soil sample 6"-10" under surface | 7600 |
| Soil sample 18" under surface | 6760 |
| 10' west of pallet | 1124 |
| Surface - east runoff ditch | 135 |
| Drainage ditch at entrance to storm sewer | 3 |

The area at the leak site has since been covered with an asphalt pad incorporating a four inch high curb along the perimeter. This area continues to serve as the drummed chemical storage area for the entomology shop.

Fuel Management

The Robins AFB Fuels Management storage system consists of numerous under-ground and above-ground storage tanks in various locations throughout the base. A description of major fuel, oil and chemical bulk storage capacities is summarized in Table 4.2. These include JP-4, DF-2 (distillate fuel), MOGAS, AVGAS, solvents, oil and other chemicals. Bulk storage of fuels is located in the fenced POL tank area. The JP-4 tanks in the bulk storage area are supplied by a four inch diameter steel pipe running from the Standard Transmission Corporation tank farm located north of the base on Georgia Highway 247. An eight inch diameter steel line supplies JP-4 to the SAC area from the POL storage area. The POL storage area was paved with concrete some time between 1978 and 1979. Prior to this time the containment dikes were tarred and the rest of the ground surface was covered with gravel.

Fuel storage tanks have been cleaned every three years and 1 to 50 gallons of sludge per tank was removed during cleaning. Until 1975, the

FIGURE 4.4




TABLE 4.2

SUMMARY OF MAJOR FUEL, OIL AND CHEMICAL STORAGE CAPACITIES

Robins Air Force Base

| Item | No. of Tanks | Maximum Tank Volume (gals.) | Minimum Tank Volume (gals.) | Total Storage Volume (gals.) |
|-------------------|--------------|--------------------------------|--------------------------------|---------------------------------|
| JP-4 | 20 | 788,739 | 48,770 | 2,909,369 |
| MOGAS | 4 | 17,387 | 9,988 | 58,771 |
| Fuel Oil | 4 | 1,063,223 | 2,018 | 1,115,189 |
| AVGAS | 1 | 24,403 | 24,493 | 24,493 |
| JPTS | 1 | 24,963 | 24,963 | 24,963 |
| Aluminum Sulfate | 1 | 5,250 | 5,250 | 5,250 |
| Sodium Hydroxide | 1 | 16,000 | 16,000 | 16,000 |
| Sulfuric Acid | 1 | 16,000 | 16,000 | 16,000 |
| Oil, Phillips 220 | 1 | 30,000 | 30,000 | 30,000 |
| Solvents | 1 | 1,400 | 1,400 | 1,400 |
| Calibration Fluid | 1 | 5,000 | 5,000 | 5,000 |

Note: Information obtained from Robins AFB Oil and Hazardous Substances - Pollution Contingency Plan, 30 September 1981.

sludge was dumped next to the cleaned tank, the area was roped off and the sludge allowed to weather. Sludges removed from the tanks are now disposed of off-base by contractor service through DPDO.

Spent fuel filters were placed in buckets to allow the fuel to evaporate. After the fuel filter has sufficiently weathered it was discarded into a dumpster to be disposed of with the general refuse.

Interviews with base personnel indicated there have been three major fuel spills on the base. A leak of an undetermined amount of JP-4 occurred from the four inch diameter supply line about the mid 1960's. The leak was located north of the POL bulk storage area by landfill No. 1. After the pipeline was repaired the pipe trench was closed and no attempt was made to recover the JP-4 that was spilled. JP-4 has been found in pipe trenches and other excavations in this general area on a regular basis since the leak occurred.

A second major spill of JP-4 occurred in the early 1970's. An estimated 60,000 gallon of fuel overflowed a tank in the POL storage area. The containment dike valve was left open and the fuel flowed into the drainage ditches leading to Horse Creek. Only a small portion of the spilled JP-4 was recovered. Contaminated soil in the affected area of the sump was excavated and removed.

A third JP-4 spill occurred in May of 1978 when approximately 1,000 gallons of fuel overflowed a tank in the storage area. This spill was contained and recovered.

Numerous small leaks were mentioned in the interviews along the four inch diameter JP-4 supply line and the eight inch diameter SAC JP-4 supply line. These pipelines were originally installed without cathodic protection and were susceptible to corrosion. Most of the pipe has been replaced and protection has been installed during the replacement effort.

DESCRIPTION OF PAST ON-BASE DISPOSAL METHODS

Prior to 1977, many waste materials generated at Robins AFB were disposed of or treated on the base by landfilling, burning in the fire protection training pits, or discharged to the sludge lagoon or industrial wastewater treatment plant. The collection and on-base transportation of liquid waste solvents from a portion of the various base

organizations has been a contract service from 1974 to 1982. The contractor has been responsible for emptying and cleaning various degreasing vats, solution tanks and paint booths and containerizing the waste material. He was also responsible for transporting the waste from the on-base industrial facility to the on-base waste holding area. The waste holding area was located in the vicinity of industrial waste treatment plant No. 1 and Landfill No. 4 from approximately 1965 through 1979. From 1965 to 1974, base employees performed these services.

Since 1980, the Defense Property Disposal Office (DPDO) has been responsible for disposal of hazardous wastes. DPDO has awarded one year contracts that require the contractor to load and transport the materials for off-base reprocessing or disposal.

The on-site facilities which have been used for management and disposal of waste can be categorized as follows:

- o Landfills
- o Waste Dumps
- o Sludge Lagoon
- o Hazardous Waste Burial Sites
- o Low Level Radioactive Waste Sites
- o Industrial Wastewater Treatment Plant
- o Sanitary Wastewater Treatment Plant
- o Storm Sewers (Oil/Water Separators)
- o Refuse Incineration

The types of waste management facilities are discussed individually in the following subsections.

Landfills


On-base landfills have been used for disposal of non-hazardous and hazardous solid wastes at Robins Air Force Base. Landfills were operated at four locations on the base as shown in Figure 4.5. Table 4.3 contains a summary of pertinent information concerning each landfill disposal site. Since 1978, solid wastes have been hauled off-base and no landfills were operated on the base.

Landfill No. 1

Landfill No. 1 is located, as shown in Figure 4.6, near the south end of the runway, between the fuels management (POL) tank farm and Second Street. The site was operated from 1946 to 1951, encompassing an

FIGURE 4.5

ROBINS AFB LANDFILL LOCATIONS




SOURCE: ROGERS AFB INSTALLATION DOCUMENTS

TABLE 4.3

SUMMARY OF LANDFILL DISPOSAL SITES

| Landfill | Operation Period | Approximate Size (Acres) | Types of Wastes | Estimated Waste Quantity (cu.yd.) | Method of Operation | Closure Status | Surface Drainage | Comments |
|----------|------------------|--------------------------|--|-----------------------------------|---|---|--------------------------------------|---|
| Number 1 | 1946-1951 | 2 | "General Refuse "Probably some industrial wastes "Boiler bottom ash (daily cover) "Ash from refuse incinerator | 65,500 | Trench and daily bottom ash cover Filled in water table | Closed; cover of sandy loam and local grasses. Impact site located in area. | To Horse Creek and swamp | *Surface erosion on slope -landfilled material exposed "; leachate entering ditch -bright green color |
| Number 2 | 1951-1963 | 22 | "General Refuse "Probably some industrial wastes "Boiler bottom ash (daily cover) "Approx. 40 tons of granular insulation and aggregate | 580,000 | Trench and daily bottom ash cover Filled in water table. A wood burning face located on west | Closed; cover of sandy loam and local grasses, runway buffer area. Pounding on the surface. | To Horse Creek and swamp | *Water on surface of trench areas and drainage stream traverses the site |
| Number 3 | 1964 | 2 | "General Refuse | 65,500 | Surface dump in water table | Closed; cover of sandy loam. Used for a baseball field. | To Horse Creek and swamp | *Permeable soil "Close Proximity to Lake Luna |
| Number 4 | 1965-1978 | 45 | "General Refuse "Probably some industrial wastes | 484,000 | Surface dump and daily cover with west end-trench and daily cover. Filled in water table of swamp | Closed; cover of sandy loam. | To Horse Creek and surrounding swamp | *Reported G.W. contamination (from monitoring wells installed 1980) "Permeable soil cover "Erosion on edges of fill "Waste chemical drums once stored on top of fill |

FIGURE 4.6



area of approximately two acres. The landfill was a trench and fill operation with daily cover of bottom ash from the boiler. The area had been previously filled with a sandy loam. Trench depths of 20 feet penetrated the fill material and sometimes extended below the water table requiring pumping when equipment had to operate near the trench bottom. General refuse from the base and housing areas was the primary material landfilled. Disposal of chemicals in the landfill was not standard procedure, however, some industrial wastes may have been placed in this landfill. An impact test facility sled was constructed on the site after landfill was closed. During construction of the sled, JP-4 seeped into the excavation that had been dug in the landfill. The source of the fuel may have resulted from a previous leak in the 4-inch diameter fuel supply line. Apparently, portions of the landfill contained JP-4 from the leaking supply line. The landfill is closed and the area is covered with soil and has established grass. During visual inspection of the site a green colored leachate was noted flowing from an eroded section on the northwest slope of the landfill. The site is 800 feet from a drinking water well and 4500 feet from the base boundary.

Landfill No. 2

Landfill No. 2 is located, as shown in Figure 4.6, east of the first site, across Second Street. This fill encompasses approximately 22 acres and was in operation from 1951 to 1963. Operation of landfill No. 2 was similar to No. 1, and included trenching into a previously filled area with daily cover of boiler bottom ash. The trench depths of 20 feet also penetrated the water table. Landfill No. 2 had a burning face on the west side of the site for disposing of scrap lumber from the base. Disposal material in landfill No. 2 included general refuse and moderate quantities of industrial wastes. Information obtained from interviews with base personnel revealed that in the early 1960's, forty tons of off-specification pesticide was buried at this site (clay or aggregate and 1.5 to 0 percent granular malathion). The site is closed and is covered with soil and vegetation has been established. An inspection of landfill No. 2 revealed some ponding of rain water on the top of the site. A drainage stream is located in the southwest corner

of the site. Landfilling occurred on both sides of the drainage stream. This site is approximately 2200 feet from a drinking water well.

Landfill No. 3

Landfill No. 3 is located, as shown in Figure 4.7, in the south-eastern part of the Robins AFB property near Lake Luna. The site was operated in 1964, primarily to fill a swampy area. Total area of the fill is approximately 2 acres. General refuse was deposited followed by a daily cover of sandy loam. Fire protection training exercises were conducted around the landfill site. The landfill is closed and the area has an established vegetation cover and a baseball field is built over it.

Landfill No. 4

Landfill No. 4 is located, as shown in Figure 4.8, near landfill No. 2, southeast of the industrial waste treatment plant addition. The fill was operated from 1965 to 1978, encompassing approximately 45 acres. Landfill No. 4 was the last on-base disposal site for solid waste. General refuse was deposited into the swamp and covered daily with a sandy soil. Little or no boiler bottom ash was used as cover due to the conversion of the boiler system to natural gas in 1966. There was occasional dumping of industrial wastes in this landfill throughout its life. The site is now covered with a sandy soil loam and partially established vegetation. This site is approximately 2200 feet from a drinking water well and is located adjacent to drainage ditches which flow to Horse Creek. From 1976 to 1979, approximately 1500 drums of waste material were stored at the west end of the landfill. A ground-water monitoring study was conducted around Landfill No. 4 and the sludge lagoon (LETCO, 1980). The results of this monitoring program indicate the presence of contaminants in the shallow aquifer has occurred downgradient of the site.

Waste Dumps

Four sites on-base were used for general refuse and landscape trash. The general locations of the waste dumps are indicated on Figure 4.9. Waste dump No. 1 and 2 were operated from early 1942 through 1946. The exact method of operation of the waste dumps was not determined. It is speculated that refuse was surface dumped at these sites and burned when it began to accumulate. No daily cover was probably applied,

FIGURE 4.7




FIGURE 4.8





FIGURE 4.9

WASTE DUMP LOCATIONS

ROBINS AFB



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

however, both waste dump No. 1 and No. 2 have been given a final cover.

Waste dump No. 3 and No. 4 are currently active sites where primarily landscape refuse has been disposed. Portions of these areas are covered with soil. Small quantities of paint cans, construction material wastes, automotive filters and oil cans, tires, and empty fire extinguisher agent containers were observed during a visual inspection. No hazardous wastes were found at these sites.

Sludge Lagoon

A sludge lagoon was used for disposal of industrial wastewater treatment plant sludges from approximately 1962 until its closure in 1978. The lagoon encompassed approximately 1.5 acres located on the north end of Landfill No. 4 (Figure 4.8). The lagoon was an unlined, diked pit with the bottom excavated below the water table level.


Sludges (2-5 percent solids) from both industrial waste treatment plants were dumped into the lagoon. Sludge from industrial waste treatment plant No. 1 contained some phenols and oils. Industrial waste treatment plant No. 2 treated waste water from metal plating operations and the sludges contained cyanide, chrome, and other heavy metals. Other industrial wastes such as paint removers, solvents, hydraulic fluids, and oils were occasionally disposed of in the sludge lagoon.

The sludge lagoon was closed in 1978 when the sludge dewatering and disposal building was started up. The lagoon is now covered with sandy loam soil which also covers Landfill No. 4. The lagoon is approximately 2200 feet from a drinking water well and 5200 feet from the nearest base boundary. The ground-water monitoring program recently conducted indicated the presence of contaminants in the shallow aquifer downgradient of the sludge lagoon.

Hazardous Waste Burial Sites

In January 1976, approximately 240 aerosol cans of DDT with pyrethrin were disposed by burial on the south portion of the base (Figure 4.10). Several sections of 30 inch diameter reinforced concrete pipe 48 inch in length were used as containers. These sections were placed vertically in a trench then capped at the bottom end with concrete. The aerosol cans were placed in the pipe sections. Each pipe section was capped at the top end with concrete for a secure closure. The trench was filled and 24 inches of natural earth cover was placed over the pipe

FIGURE 4.10



sections. Similar procedures were used at this same location for disposal of two containers of mercury contaminated material and one container of a small amount of PCB material in April 1976. Approximately 15 gallons of wastes contaminated with mercury were disposed at this location in April 1977. The waste material was placed in plastic bags, then placed in metal containers. The containers were placed in additional plastic bags, then were encapsulated with six inches of concrete prior to final burial. No indication of further waste disposal at this site was determined from the base records and personnel interviews.

Laboratory chemicals which had exceeded their recommended shelf life were buried in two unlined pits in the southeastern end of the base sometime between 1962 and 1964. This was a one time disposal of old bottles, canisters and jars of a variety of laboratory chemicals from the base storage. The disposal site is believed to be in the vicinity of Luna Lake by the dog kennel, however, an exact location could not be determined.

Low Level Radioactive Waste Sites


Low level radioactive wastes have been generated on-base from instrument repair work and washdown of radioactive aircraft. The disposal sites for these wastes occurred in the locations shown in Figure 4.11 and are described below.

The radioactive waste (solid) disposal site, facility number 8315, is located, as shown in Figure 4.12, on the southeast corner of the base along Perimeter Road south of the firing range. It is comprised of a concrete vault buried approximately six feet below the ground surface. A locked chain-linked fence with two barbed wire strands surrounds the disposal area. Two signs are posted on the fence designating the area as a "Radiation Hazard Area". The site was used in the early 1950's for disposal of low-level solid radioactive wastes such as old radium dials, contaminated radioactive brushes, election tubes and spark gaps. Soil samples collected within and adjacent to the burial area have been analyzed annually. The 1980 soil analyses are presented in Table C.13 (Appendix C). The area was last surveyed with a beta/gamma radioactivity detector in September of 1981. Radiation levels did not exceed 0.03 mr/hr above a background of 0.01 mr/hr; indicating radioactive

FIGURE 4.11


RADIOACTIVE WASTE BURIAL SITE & AIRCRAFT WASH AREAS

ROBINS AFB



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

FIGURE 4.12



materials are present, but do not result in radioactivity levels hazardous to human health.

Two open radioactive aircraft wash areas were utilized at Robins AFB for decontamination caused by airborne fission products. Wash area No. 1 was located east of the SAC ordinance area. This area was used in 1956 to decontaminate one aircraft. The aircraft was positioned off of the taxiway onto a grass area for washdown. The area was restricted after washing until monitoring for levels of radioactivity indicated only background amounts.

Similar washdown operations occurred in area No. 2. Approximately four aircraft were decontaminated at this location during 1957. Similar area restrictions and monitoring were initiated until only background levels of radioactivity were detectable.

Two underground storage tanks (wash area No. 3) located adjacent to the east side of building 58, were designed to collect washdown from aircraft that also may have been contaminated by airborne fission products. The contents of these tanks were sampled in 1978 and found to contain water contaminated with zinc, iron, low level radiation and a surfactant. The east tank also contained a stratified upper layer mixture of a petroleum base solvent and a compound similar to methyl ethyl ketone. The solutions were probably generated around 1963 during a washdown operation. During interviews with the Bioenvironmental Engineering Services Division personnel, it was learned that these tanks were pumped out in 1978 and the water was discharged to the wastewater treatment plant at a predetermined, dilution ratio.

Industrial Waste Treatment Plants

The first industrial waste treatment at Robins AFB began in 1960 with batch treatment of cyanide wastes. The treated wastes were combined with treated sanitary sewer wastes and discharge to Horse Creek. Prior to this many aqueous industrial wastes may have been neutralized, diluted and discharged to the storm sewer system.

The first industrial waste treatment plant was built in 1964 primarily as an air flotation system for removal of oils and phenols. In 1971, the plant was upgraded to provide treatment for reduction of hexavalent chromium, neutralization, and coagulation/precipitation of heavy

metals. Industrial waste treatment plant No. 1 treats all the industrial waste from the base except the plating shops, and includes wastes from aircraft stripping operations and washdown. The wastewater contains oils, phenols, chrome, paint residues, solvents and alkaline based stripping materials. Sludge from the treatment plant was discharged into the sludge lagoon until its closure in 1978. Sludge has been de-watered and placed in the sludge disposal building since 1978. Effluent from industrial waste treatment plant No. 1 flows through a sanitary waste treatment facility for biological oxidation of residual phenols.

Industrial waste treatment plant No. 2 was built in 1969 to treat the base plating shops wastes. Influent is typical plating waste and includes high levels of chrome, cyanide and heavy metals. Sludge from the clarifier underflow of this facility was also disposed in the sludge lagoon until its closure in 1978. Since then the sludge has been de-watered and placed in the sludge disposal building.


The sludge dewatering and disposal facility was built in 1978 as part of the closure of the sludge lagoon. The disposal building is completely enclosed with a concrete floor. Decant from sludge dewatering (plate and frame pressure filter) is returned to industrial waste treatment plant No. 1. The sludge disposal building was designed for a total dry sludge storage volume of 9,323 cubic yards and an estimated life of 10 years at current sludge generation rates. The locations of the waste treatment facilities are shown in Figure 4.13.

Sanitary Wastewater Treatment Facilities

Domestic sewage has been treated on-base since 1942 by a single stage trickling filter system located in the area of industrial waste treatment plant No. 1. This sanitary treatment facility discharges treated effluent to a tributary of Horse Creek. The sludge generated from this treatment facility was applied to various land areas on-base. This system may have received wastewater streams containing phenolic and non-phenolic paint strippers from the mid 1940's to 1965. Also this system may have received batches of partially or completely treated cyanide baths from the electroplating operations on-base during the same period.

WASTEWATER TREATMENT FACILITIES

FIGURE 4.13



SOURCE: ROBINS AFB INSTALLATION DOCUMENTS

An additional sanitary wastewater treatment plant was operational from 1943 through approximately 1979. In 1973 this facility was upgraded from a primary to a secondary treatment facility. This facility is located off Hannah Road near Seventh Street. It is believed that this plant received little or no industrial waste streams. This facility is now used only as a pumping station. The locations of the waste treatment facilities are shown in Figure 4.13.

Storm Sewer Systems

The storm sewer systems on-base consist primarily of concrete conduits or open-channels which direct drainage towards tributaries of Horse Creek. The systems in the areas of aircraft maintenance functions received some discharges of wastes from maintenance activities from the mid 1940's through the early 1970's. In the mid 1970's, oil/water separators were installed in many of the systems. A list of these units is shown in Table 4.4.

Refuse Incineration

General refuse from the base was disposed of by incineration in the late 1940's. The incinerator was located west of landfill No. 4. Ash from the incinerator was buried in landfill No. 1. The operation was discontinued in the early 1950's and the refuse went directly to the landfill for disposal.

EVALUATION OF PAST DISPOSAL ACTIVITIES AND FACILITIES

The review of past operation and maintenance functions and past waste management practices at Robins AFB has resulted in the identification of 13 sites containing hazardous waste materials and having the potential for migration of contaminants. Other sites were reviewed and eliminated from further evaluation based on the logic presented in the decision tree shown in Figure 1.1.

The 13 sites have been assessed using a hazardous assessment rating methodology (HARM) which takes into account characteristics of potential receptors, waste characteristics, pathways for migration and specific characteristics of the site related to waste management practices. The details of the HARM procedures are presented in Appendix G and the results of the assessment are summarized in Table 4.5. The rating system is designed to indicate the relative need for follow-on action. The

TABLE 4.4
SUMMARY OF ON-BASE OIL/WATER SEPARATORS

| Separator Number | Date Installed | Building Location | Description |
|------------------|----------------|-------------------|--|
| 0-01 | 1972 | 23 | North Side |
| 0-02 | 1978 | 30 | Noise Suppressor N.E. Corner |
| 0-03 | 1969 | 33 | East of Pad |
| 0-04 | 1970 | 47 | West Side |
| 0-05 | 1967 | 48 | East Side |
| 0-06 | 1967 | 49 | East Entrance |
| 0-07 | 1954 | 628 | West Side ALC |
| 0-08 | 1976 | 656 | N.W. Side |
| 0-09 | 1975 | 959 | (Gray Eagle Unit) |
| 0-10 | 1979 | 979 | S.W. Side |
| 0-11 | 1977 | 377 | East Side (Fire Dept.) |
| 0-12 | 1952 | 318 | East Side (Land Fill) |
| 0-13 | 1956 | 194 | S.E. of Bldg. 153 on Parking Ramp |
| 0-14 | 1964 | 302 | East End of Washrack |
| 0-15 | 1960 | 67 | N.W. Side |
| 0-16 | 1960 | 67 | North Side |
| 0-17 | 1975 | 85 | North Side |
| 0-18 | 1960 | 76 | N.E. Corner |
| 0-19 | 1960 | 82 | North Side |
| 0-20 | 1962 | 52 | South Side |
| 0-21 | 1962 | 52 | North Side |
| 0-22 | 1963 | 190 | North Side |
| 0-23 | 1963 | 190 | N.E. Holding Tank |
| 0-24 | 1963 | 196 | North of Bldg. 192 (POL) |
| 0-25 | 1963 | 196 | Area near Bldg. 73 (POL) |
| 0-26 | 1960 | 79 | Adjacent to Washrack |
| 0-27 | 1979 | PB64 | Outside Flight Line Area along 1st St. |
| 0-28 | 1974 | 922 | BX Service Station |
| 0-29 | 1979 | 979 | Washrack |
| 0-30 | 1980 | 184 | Aero Club/Aircraft Parking Lot |
| 0-31 | 1967 | 985 | Base Hobby Shop |
| 0-32 | 1963 | 109 | Fire Department |
| 0-33 | 1951 | 93 | Paint Storage (inactive) |

SOURCE: Bioenvironmental Engineering Services Division Files, verified and updated by CES

TABLE 4.5
SUMMARY OF HARM SCORES FOR POTENTIAL CONTAMINATION SOURCES

| Rank | Site Name | Receptor Subscore | Pathways Subscore | Waste Characteristics Subscore | Waste Management Factor | Overall Total Score |
|------|---|-------------------|-------------------|--------------------------------|-------------------------|---------------------|
| 1 | Sludge Lagoon | 57 | 100 | 75 | 1.0 | 77 |
| 2 | Landfill No. 4 | 59 | 100 | 60 | 1.0 | 73 |
| 3 | DOT Spill (1979) | 51 | 100 | 60 | 1.0 | 70 |
| 4 | Fire Protection Training Area No. 2 | 46 | 55 | 90 | 1.0 | 64 |
| 5 | Landfill No. 1 | 46 | 80 | 50 | 1.0 | 59 |
| 6 | Landfill No. 2 | 42 | 80 | 53 | 1.0 | 58 |
| 7 | JP-4 Spill (1965) | 47 | 80 | 45 | 1.0 | 57 |
| 8 | Hazardous Waste Burial Site | 44 | 48 | 80 | 0.95 | 54 |
| 9 | Fire Protection Training Area No. 1 | 44 | 62 | 50 | 1.0 | 52 |
| 10 | Laboratory Chemical Burial Site | 42 | 80 | 30 | 1.0 | 51 |
| 11 | Landfill No. 3 | 46 | 56 | 40 | 1.0 | 47 |
| 12 | Fire Protection Training Area No. 3 | 40 | 56 | 40 | 1.0 | 45 |
| 13 | Radioactive Waste (Solid) Disposal Site | 44 | 41 | 14 | 0.95 | 31 |

information presented in Table 4.5 is intended as a guide for assigning priorities for further evaluation of the Robins AFB disposal areas (Chapter 5, Conclusions and Chapter 6, Recommendations). The rating forms for the individual waste disposal sites on Robins AFB are presented in Appendix H. Photographs of some of the key disposal sites are contained in Appendix E.

CHAPTER 5
CONCLUSIONS

CHAPTER 5

CONCLUSIONS

The goal of Phase I of the IRP is to identify the potential for environmental contamination from past waste disposal practices at Robins AFB and to assess the probability of contaminant migration. The conclusions given below are based on the assessment of the information collected from the project team's field inspection, review of records and files, interviews with base personnel, past employees and state and local government employees and review of the environmental setting.

Table 5.1 contains a summary of HARM scores for sites at Robins AFB.

- 1) The sludge lagoon has a high potential for migration of contaminants. This lagoon was used from approximately 1962 through 1978 to dispose of sludges from the industrial waste treatment plants. Sludges and industrial wastes from other industrial operations on-base were also disposed of in this lagoon. The results of a recently conducted ground-water monitoring program (LETCO, 1980), indicated contamination of the shallow aquifer down-gradient of the site. The lagoon is approximately 2,200 feet from a drinking water well and 5,200 feet from the base boundary. The lagoon was constructed in a former swamp area and the bottom extends below the water table. A stream flows adjacent to the lagoon site and standing water conditions commonly occur near the lagoon site. This site received a rating score of 77.
- 2) Landfill No. 4 has a high potential for migration of contaminants. This landfill was utilized from 1965 through 1978 for disposal of general refuse and significant quantities of industrial wastes. The results of a ground-water monitoring study (LETCO, 1980) indicate contamination of the shallow aquifer downgradient of the site. Landfill No. 4 is located approximately 2,000 feet from a drinking water well and 4,800 feet from the nearest base boundary. The bottom of the landfill is in the ground-water

TABLE 5.1
PRIORITY RANKING OF POTENTIAL CONTAMINATION SOURCES
ROBINS AFB

| Rank | Site Name | Date of Operation or Occurrence | Overall Total Score |
|------|---|---------------------------------|---------------------|
| 1 | Sludge Lagoon | 1963-1978 | 77 |
| 2 | Landfill No. 4 | 1965-1978 | 73 |
| 3 | DDT Spill (1979) | 1979 | 70 |
| 4 | Fire Protection Training Area No. 2 | mid 1950's to mid 1960's | 64 |
| 5 | Landfill No. 1 | 1943-1951 | 59 |
| 6 | Landfill No. 2 | 1951-1953 | 58 |
| 7 | JP-4 Spill (1965) | 1965 | 57 |
| 8 | Hazardous Waste Burial Site | 1976, 1977 | 54 |
| 9 | Fire Protection Training Area No. 1 | 1943-mid 1950's | 52 |
| 10 | Laboratory Chemical Disposal Site | early 1960's | 51 |
| 11 | Landfill No. 3 | 1964 | 47 |
| 12 | Fire Protection Training Area No. 3 | mid 1960's to 1969 | 45 |
| 13 | Low Level Radioactive Waste (Solid) Burial Site | 1940's to 1950's | 31 |

table. This site is presently closed and covered with sandy loam and has some vegetation established. Landfill No. 4 was given a HARM score of 73.

3) The DDT spill (1979) poses a high potential for contaminant migration. The spill involved a 55-gallon drum which leaked concentrated pesticide prior to discovery by base personnel. The immediate area around the spill received significant quantities of DDT as determined by soil samples taken by the Bioenvironmental Engineering Services Division office. The surface drainage pathway of the spilled material leading to Horse Creek was also sampled and contained lower levels of DDT. The remedial action taken consisted of covering the contaminated spill site with asphalt material. No removal of contaminated soil from the spill area or drainage pathway was reported. This site received a HARM score 70.

4) Fire Protection Training Area No. 2 poses a moderate potential for migration of contaminants. This area actually consists of several grade level open burning sites used from the mid 1950's through the mid 1960's. Significant amounts of chemical wastes, solvents, and paint wastes may have been routinely burned at this site in addition to the petroleum based materials used in each exercise. The estimated locations of the burn areas are within 1,200 feet to 600 feet of a drinking water well and are within 1,200 feet to 2,000 feet from the base boundary. The depth to ground water is estimated to be between 20 feet and 25 feet. This area received a HARM score of 64.

5) Landfill No. 1 poses a moderate potential for contaminant migration. Landfill No. 1 was operated from 1946 to 1957 and may have received small quantities of industrial wastes as well as general refuse. During a visual inspection of the site, a green colored leachate was noted flowing from an eroded section on the northwest slope of the landfill. The landfill may contain JP-4 as a result of a pipeline leak that occurred in the 1960's. This site is 800 feet from a drinking water well and 4,500 feet from the base boundary. Landfill No. 1 is now covered with soil and established vegetation. This landfill received a HARM score of 59.

- 6) Landfill No. 2 poses a moderate potential for migration of contaminants. Landfill No. 2 was used for disposal of general refuse and may have received moderate quantities of industrial wastes from 1951 to 1963. This site is approximately 2200 feet from a drinking water well and is located adjacent to drainage ditches which lead to Horse Creek. The distance from the bottom of the landfill to ground water is estimated to be 5 feet or less. This site is closed and covered with soil and vegetation is established. This landfill received a HARM score of 58.
- 7) The JP-4 leak (1965) poses a moderate potential for migration of contaminants. Several incidents of finding JP-4 seepage during excavations have been reported in the area of the old pipeline leak specifically around Landfill No. 1. It is believed that a moderate to large quantity of JP-4 may be floating on the ground water table down-gradient of the leak site. The quantity of fuel spilled and the quantity remaining on the ground-water table has not been determined. The JP-4 spill received a HARM score of 57.
- 8) The hazardous waste burial site poses a moderate potential for migration of contaminants. This site contains moderate amounts of hazardous wastes. Encapsulation of the wastes in concrete pipes was completed at the hazardous waste disposal site prior to burial of the material. The hazardous waste disposal site received a HARM score of 54.
- 9) Fire Protection Training Area No. 1 poses a moderate potential for contaminant migration. Hazardous materials have been burned in this area along with petroleum materials. The area was operated from 1943 through 1950. The precise location of Fire Protection Training Area No. 1 could not be determined, but it is believed to be located in or by Landfill No. 2. This site received a HARM score of 52.
- 10) The laboratory chemical disposal site is believed to pose a moderate potential for migration of contaminants. This site is located somewhere in the vicinity of Luna Lake and the dog kennel but the exact location could not be determined. Bottles, canisters and jars of outdated laboratory chemicals from the base storage

facility were buried at this site. The disposal site received a HARM score of 51.

11) Landfill No. 3 poses low potential for migration of contaminants. This site was operated in 1964 and is believed to have received primarily general refuse and little or no waste chemicals for disposal. The site is covered with vegetation and soil. Landfill No. 3 received a HARM score of 47.

12) Fire Protection Training Area No. 3 poses a low potential for contaminant migration. Fire training was conducted in this area from 1960 through 1969, only petroleum substances were known to be used in the training exercises. The site received a HARM score of 45.

13) The low level radioactive waste (solid) burial site poses a low potential for migration of contaminants. A concrete vault was used to dispose small quantities of low-level radiation materials in the late 1940's and early 1950's. The site is fenced securely and marked with warning signs. This site received the lowest HARM score, 31.

CHAPTER 6
RECOMMENDATIONS

CHAPTER 6

RECOMMENDATIONS

To aid in the comparison of the 13 sites on Robins AFB with those sites identified in the IRP at other Air Force Bases, a hazardous assessment rating methodology (HARM) was developed. Of primary concern at Robins AFB are those sites with a high potential for contaminant migration and with HARM scores greater than 65. These sites require further investigation in Phase II. Sites of secondary concern are those with moderate potential for contaminant migration and have HARM scores from 50 to 64. Further investigation at these sites is recommended. No further monitoring is recommended for those sites with low potential for migration of contaminants (scores from 0 to 49) unless data collected from other locations indicate a potential problem could exist at one of these sites.

The following recommendations are made to further assess the potential for contaminant migration from waste disposal areas at Robins AFB. The recommended monitoring program for Phase II is summarized in Table 6.1.

1) Landfill No. 4 is considered to have a high potential for migration of contaminants as demonstrated by the contamination of the shallow ground water down-gradient of the site. The recommended monitoring at this site is intended to define the extent of contamination and help determine remedial measures.

Geophysical survey techniques are recommended to help map the contaminant plume and further define site geology. The swamp area may restrict the performance of geophysical survey techniques.

A revised ground water monitoring program is recommended to determine plume configuration, depth of contamination, and concentration of contaminants. The monitoring program should consist of the following:

- o Evaluate the existing down-gradient monitoring wells along Hannah Road to determine their condition. The wells are

constructed of polyvinyl chloride (PVC) pipe and some of the organic contaminants such as methylene chloride will react with the PVC. Use these wells if no distortion or softening of the PVC is noted. If PVC deterioration is observed, then construct new monitoring wells with Teflon®, stainless steel, or other inert material.

- o Establish three wells in deeper zones above Hannah Road, to depths of 50, 75 and 100 feet, respectively. These wells can be used to evaluate vertical migration of contaminants. Monitor for the parameters in List A, Table 6.2. If contamination is found at 100 feet, then deeper wells should be constructed to define the depth of the plume. The material for well construction should be determined from the previous evaluation.
 - o Establish an up-gradient well west of Landfill No. 4 and other sources of contamination. The ground-water should be sampled at 25, 50, 75 and 100 feet. Monitor for the parameters in List A, Table 6.2. The existing up-gradient well is in an area down-gradient of another potential source of contamination (Landfill No. 2). Therefore this well is not representative of background conditions.
 - o Establish eight monitoring wells down-gradient at the landfill perimeter, capable of sampling to depths of 25, 50, 75 and 100 feet. These wells should be constructed of stainless steel or Teflon® since deterioration of the existing perimeter wells constructed of PVC has already been observed. Monitor for the parameters in List A, Table 6.2.
 - o Abandon and seal the existing up-gradient and perimeter monitoring wells in accordance with Section 391-3-2.13 of the Georgia Ground Water Use Act of 1974.
 - o Monitoring wells should be established to determine the furthest edge of the ground-water contaminant plume. This may be difficult to achieve in the swamp area. Samples should be analyzed for the parameters in List A, Table 6.2.
- 2) The sludge lagoon is also considered to have a high potential for migration of contaminants as demonstrated by the contamination of the shallow ground water down-gradient of the site. Landfill No. 4 and the

sludge lagoon are too close to each other to monitor separately, therefore, the program described for monitoring Landfill No. 4 will include the sludge lagoon.

- 3) The DDT spill (1979) site has a high potential for contaminant migration. Sampling has shown that the soil around the site is contaminated with DDT. The contaminated soil should be removed and replaced with fill material then the area paved to prevent infiltration. Sampling and analyses for DDT should be performed to verify clean up of the site.
- 4) The Fire Protection Training Area No. 2 is considered to have a moderate potential for migration of contaminants. The exact location of this site was not clearly defined by the records search project therefore part of the monitoring will be aimed at identifying the pit location. Collect soil borings in and around the suspected area of the old pits (100 ft. by 200 ft., 15 in the general pit area and 1 outside the area). The borings should be on a 50 foot grid, ten feet deep with soil samples taken at regular intervals and at any interface. Analyses should be performed on water extractions and then analyzed for the parameters in List B (Table 6.2).
- 5) Landfill No. 1 is considered to have a moderate potential for contaminant migration and monitoring is recommended. Geophysical survey techniques are recommended to identify any JP-4 in or around the site. If the geophysical survey is not affective, then install six monitoring wells (PVC) into the top of the water table down-gradient of the landfill and sample for floating oil. Samples of any leachate stream(s) should be collected and analyzed for the parameters in List A, Table 6.2.
- 6) Landfill No. 2 is considered to have a moderate potential for migration of contaminants and monitoring of this site is recommended. One upgradient and three downgradient monitoring wells (Schedule 40 PVC) should be constructed in the uppermost aquifer and the shallow ground water should be monitored for the parameters in List A, Table 6.2.
- 7) The area around the JP-4 leak (1965) is considered to have a moderate potential for migration of JP-4 and monitoring down-gradient of the site is recommended. Geophysical survey techniques may be effective

for defining JP-4 floating on top of the water table. If the geo-physical survey is not effective then install six monitoring wells (PVC) into the top of the water table down-gradient of the leak and sample for floating material. This monitoring should be done jointly with monitoring for Landfill No. 1.

8) The hazardous waste burial site has a moderate potential for contaminant migration. One up-gradient and two down-gradient monitoring wells are recommended at this site. The wells should be constructed of Schedule 40 PVC and the ground water should be sampled and analyzed for the parameters in List B, Table 6.2.

9) The Fire Protection Training Area No. 1 has a moderate potential for contaminant migration. Since this site is believed to be located in or around Landfill No. 2, it will be included as part of the monitoring of Landfill No. 2.

10) The laboratory chemical disposal site is considered to have a moderate potential for contaminant migration. The exact location of this site could not be determined by the records search project. Since some of the materials were disposed of in metal containers, geophysical surveys techniques may be effective in identifying the location. The waste were reported buried on the south side of Luna Lake near the dog kennels. If the site is identified, collect soil borings as described for fire protection area No. 2.

11) Conduct a one-time water sampling program for water supply wells Nos. 3, 6, 8 and 12. Analyze each sample for he parameters shown in List A of Table 6.2.

12) Sample water and sediments of the drainage courses around landfill No. 4 to determine if leachate from the landfill and sludge lagoon are entering the drainage ditch. Set up eight sample stations and analyze for the parameters in List B, Table 6.2.

TABLE 6.1

RECOMMENDED MONITORING PROGRAM FOR PHASE II - ROBINS AIR FORCE BASE

| Site | HANM Score | Recommended Monitoring | Comments |
|----------------|------------|---|--|
| Landfill No. 4 | 73 | <p>a. Utilize geophysical survey techniques to map contaminant plume, if site geology permits.</p> <p>b. Establish a revised groundwater monitoring program to determine configuration, depth of contamination, and concentrations of contaminants. Monitoring program should consist of:</p> <ul style="list-style-type: none"> - Evaluate existing down-gradient monitoring wells along Hannah Road to determine condition. Continue use if well condition is adequate. - Abandon and seal (per Section 391-3-2.13 of the Ground Water Use Act of 1974) upgradient well and landfill perimeter wells. - Establish new upgradient well, west of Landfill No. 4, at depths of 25, 50, 75 and 100 feet. Monitor for parameters in List A, Table 6.2. - Establish eight monitoring wells down-gradient at landfill perimeter capable of sampling to depths of 25, 50, 75 and 100 feet. Construct wells of stainless or Teflon®. Monitor for parameters in List A (Table 6.2). - If condition permits, use LETCO Hannah Road wells to monitor shallow ground-water quality. If well condition is poor, replace wells with stainless steel or Teflon®. Monitor for parameters in List A, Table 6.2. - Establish wells in deeper zones along Hannah Road, to depths of 50, 75 and 100 feet. Analyze for parameters in List A, Table 6.2. - If possible, establish a line of monitoring wells along edge of farthest plume extent. Construct and monitor for parameters in List A, Table 6.2. <p>- If contamination is determined to exist at depths of 100 feet, increase monitoring depth in order to determine maximum depth of contamination. Monitor for parameters specified in List A, Table 6.2.</p> | <p>Geophysical survey performance may be degraded by site geology and wetland environment.</p> <p>Contamination of the shallow aquifer downgradient of this site has been documented by previous ground-water monitoring (LETCO, 1980).</p> <p>This recommended monitoring program is more extensive than confirming if contamination exists. It is intended to define the extent of contamination and help determine remedial action.</p> |

Sludge Lagoon

77

Monitoring program described under Landfill No. 4 will include the sludge lagoon.

Landfill No. 4 and the sludge lagoon are too close to monitor separately.

TABLE 6.1 (Continued)

| Site | HAN4 Score | Recommended Monitoring | Comments |
|-------------------------------------|------------|---|---|
| DUR Spill 1 (1979) | 70 | Monitor soil samples for DPP to verify clean up of the site. | Preliminary monitoring has indicated DPP contamination. The soil in the spill area should be removed and replaced with fill material then pave over the site. |
| Fire Protection Area No. 2 | 64 | Collect soil borings in and around the suspected area of the old pits (100 ft. by 200 ft., 15 in the pit area and 1 outside the area). The borings should be on 50 foot grid, tan feet deep and soil samples taken at regular intervals and at any interface. Analyses should be performed on water extractions and then analyzed for the parameters in List B (Table 6.2). | |
| Landfill No. 1 | 59 | <p>a. Conduct geophysical survey in the area in and around the landfill (approximately 15 to 20 acres). If geophysical survey techniques do not work then install six monitoring wells into the top of the water table down-gradient of the site (about 10 to 20 feet deep). Sample for floating material.</p> <p>b. Collect surface water samples of leachate stream(s). Analyze for parameters in List A (Table 6.2).</p> | JP-4 spill (1965) occurred around Landfill No. 1. Therefore monitoring of these sites should be performed jointly. |
| Landfill No. 2 | 58 | Establish shallow ground-water quality monitoring system in uppermost aquifer, consisting of one upgradient and three downgradient wells. Construct wells of PVC (Schedule 40) and monitor for parameters in List A (Table 6.2). | |
| JP-4 Spill 1 (1965) | 57 | Conduct monitoring as described under Landfill No. 1. | Should monitor with Landfill No. 1 since they are in the same area. |
| Hazardous Waste Burial Site | 54 | Establish shallow ground-water quality monitoring system in uppermost aquifer consisting of one upgradient and two down-gradient wells. Construct wells of PVC (Schedule 40) Pipe and monitor for parameters in List B (Table 6.2). | |
| Fire Protection Training Area No. 1 | 52 | Monitoring will be included as part of monitoring program at Landfill No. 2. | |
| Laboratory Chemical Disposal Site | 51 | Utilize geophysical survey techniques to locate site. If site is identified, collect soil boring as described for Fire Protection Area No. 2. | Unable to determine location of this site. Geophysical survey may be able to detect metal containers. |

TABLE 6.1 (Continued)

| Site | HARM Score | Recommended Monitoring | Comments |
|--------------------------|------------|---|----------|
| Water Supply Wells | - | Conduct a water sample collection and analyses program for water supply wells Nos. 3, 6, 8 and 12. The parameters shown in List A of Table 6.2 should be used for analyses of each sample. | / |
| Surface Water Monitoring | - | Sample water and sediments of the drainage courses from Landfill No. 4 to the base boundary. Set up approximately 8 sampling stations and analyze for the parameters in List A (Table 6.2). | |

TABLE 6.2
RECOMMENDED LIST OF ANALYTICAL PARAMETERS

List A

Samples from:

Ground-water monitoring wells
Leachate
Base water supply wells
Stream sediment samples
Stream water samples

Analyses to include:

GC/MS scan
Total organic carbon
pH
Nickel
Phenol
Cyanide
Copper
Zinc
Manganese
Total dissolved solids
Interim Primary Drinking Water Standards (selected list)

| | | | |
|----------|----------|--------------|-----------------|
| Arsenic | Lead | Endrin | 2,4,5-TP Silvex |
| Barium | Mercury | Lindane | Radium |
| Cadmium | Nitrate | Methoxychlor | Gross alpha |
| Chromium | Selenium | Toxaphene | Gross Beta |
| Fluoride | Silver | 2,4-D | |

List B

Samples from:

Ground-water monitoring wells
Water extract of soil borings

Analyses to include:

Interim Primary Drinking Water Standards (see above list)
pH
Total organic carbon
Nickel
Phenol
Cyanide
Copper
Zinc
Manganese
Total Dissolved Solids

APPENDICES

APPENDIX A

BIOGRAPHICAL DATA

**G. M. Gibbons
R. M. Reynolds, P.E.
E. J. Schroeder, P.E.
M. I. Spiegel
R. E. Zimmermann, C.P.G.**

Biographical Data
GREGORY M. GIBBONS
Sanitary Engineer

[PII Redacted]



Education

B.S. in Civil Engineering, 1978, University of Notre Dame
M.S. in Sanitary Engineering, 1980, University of Michigan,
Ann Arbor.

Professional Affiliations

Engineering-in-Training (Indiana)
American Society of Civil Engineers
Water Pollution Control Federation

Experience Record

1977-Date Engineering-Science. Technical Specialist (1977).
Responsible for reviewing shop drawings and performing
general office duties.

Assistant Engineer (1978). Prepared designs, wrote
specifications, and reviewed shop drawings.

Engineer (1979). Responsible for design preparation,
pilot plant operation, and data analysis. Also in-
volved in contract administration.

Sanitary Engineer (1980-Date). Responsible for indus-
trial waste survey, characterization and treatability
studies, including field surveys, analyses, interviewing
and report preparation. Responsible for field inves-
tigation and report preparation for sludge land
application EIS at Des Moines, Iowa. Assisted in air
pollution source tests and compliance determinations
at various industrial facilities. Assisted in EIS
preparation for wastewater treatment plant in Hanover
County, Virginia. Responsible for design of components
of 100-mgd Division Avenue Water Treatment Plant (Cleveland,
Ohio). Lead responsibility in process design for elec-
troplating waste treatment system. Project Manager for
resource recovery assessment of newsprint for the
Commonwealth of Virginia.


1978-1979 University of Michigan, Ann Arbor, Michigan. Laboratory
Aide (1978). Teaching Assistant (1979). Responsible
for instructing laboratory classes in water quality
analysis.

Biographical Data

Randal M. Reynolds

Senior Engineer

[PII Redacted]



Education

BChE (Chemical Engineering), 1973, Georgia Institute of Technology,
Atlanta, Georgia

Professional Affiliations

Registered Professional Engineer, Georgia #13023
Air Pollution Control Association
American Institute of Chemical Engineers (Chapter Secretary)

Experience Record

- | | |
|-----------|--|
| 1973-1975 | U.S. Environmental Protection Agency, Water Enforcement Branch, Atlanta, Georgia. Chemical Engineer. Responsible for developing draft NPDES limitations for industrial discharges, issuing public notices and final NPDES permits and participating in public hearings concerning NPDES permits. |
| 1975-1981 | Gold Kist Inc., Corporate Engineering, Atlanta, Georgia. Environmental Process Engineer. Responsible for reviewing and implementing new air quality, NPDES, RCRA and TSCA regulations. Supervised preparation and submittal of air quality, water quality and hazardous waste permit applications. Kept management informed of impact of regulations on existing and future projects. Served as staff engineer responsible for preparing preliminary designs for air pollution control systems and detailed cost estimates for air system capital projects. Major projects included the preliminary selection of alternatives for a particulate emission control system for a 60,000 lbs/hr industrial steam boiler (peanut hull/wood fired). |
| 1981-Date | Engineering-Science, Inc., Atlanta, Georgia. Senior Engineer. Responsibility for developing environmental studies and alternative evaluations for clients. |

Randal M. Reynolds, Continued

Project Engineer for Phase I Installation Restoration Program projects for the Department of Defense.

Developed hazardous chemical usage, waste generation and waste disposal practice timelines for industrial operations at several Air Force bases. Identified industrial operation disposal practices which could result in migration of contaminants and recommended priority disposal practices requiring further investigation.

Project Engineer assisting in a comprehensive study of the solid waste management program for the City of Roswell, Georgia. Developed conceptual cost estimates for a city operated sanitary landfill and incinerator disposal alternatives.

Project Manager for development of a Spill Prevention Control and Countermeasures (SPCC) Plan for an industrial facility. Coordinated the design of spill containment structures and recommended structure modifications. Recommended essential spill control and clean-up equipment.

Publications and Presentations

R. M. Reynolds, "Practical Tips - Bagging Sludge?", Pollution Engineering, Vol. 12, No. 7, July 1980, pg. 28.

R. M. Reynolds, "Pulse-Type Fabric Filters in a Soybean Processing Facility," Operation and Maintenance of Air Particulate Control Equipment, R. A. Young, F. L. Cross, Jr., editors, Ann Arbor Science Publishers, Inc., Ann Arbor, Michigan, July 1980, pp. 121-123.

"Operation, Maintenance and Design of Fabric Filters for a Soybean Processing Facility," a slide presentation for the EPA technology transfer seminar, "Operation and Maintenance of Air Pollution Equipment for Particulate Control," April 12, 1979, Atlanta, Georgia.

Biographical Data

ERNEST J. SCHROEDER

Environmental Engineer
Manager, Solid and Hazardous Waste

Education

B.S. in Civil Engineering, 1966, University of Arkansas,
Fayetteville, Arkansas
M.S. in Sanitary Engineering, 1967, University of Arkansas,
Fayetteville, Arkansas

Professional Affiliations

Registered Professional Engineer (Arkansas No. 3259, Georgia
No. 10618, Texas No. 33556 and Florida No. 0029175)
Water Pollution Control Federation

Honorary Affiliations

Chi Epsilon

Experience Record

1967-1976 Union Carbide Technical Center, Engineering Department,
South Charleston, West Virginia (1967-1968). Project
Engineer. Responsible for environmental protection
engineering projects for various organic chemicals and
plastics plants. Conducted industrial waste surveys,
landfill design, and planning for plant environmental
protection programs; evaluated air pollution discharges
from new sources; reviewed a wastewater treatment plant
design; and participated on a project team to design a
new chemical unit.

Union Carbide Corporation, Environmental Protection
Department, Texas City, Texas (1969-1975). Project
Engineer and Engineering Supervisor. Responsible for
various aspects of plant pollution abatement programs,
including preparation of state and federal permits for
wastewater treatment activities.

Operations Representative on \$8 million regional waste-
water treatment project and member of design team which
made the initial site selection and process evaluation

ERNEST J. SCHROEDER (Continued)

and recommendation. Participated in contract negotiations, process and detailed engineering design, construction of the facilities, preparation of start-up manuals, operator training, and the start-up activities. Designated as Project Engineer after start-up on expansion to original waste treatment unit.

Engineering Supervisor responsible for operation of wastewater treatment facilities including collection system, sampling and monitoring programs, spill control and clean-up, primary waste treatment, wastewater transfer system, biological waste treatment, and waste treatment pilot plants. Developed odor control program which successfully reduced odor emissions and represented Union Carbide at a public hearing on community odor problems.

Led special projects such as an excess loss control program to reduce water pollution losses; sewer segregation program involving coordination and reporting of 38 projects for the separation of contaminated and non-contaminated water; and sludge disposal program to develop long-term sludge disposal alternatives and recover land in present sludge landfill area. Developed improved methods of sampling and continuous monitoring of wastewater.

Union Carbide Corporation, Environmental Protection Project Engineer, Toronto, Ontario, Canada (1975-1976). Responsible for the overall environmental permitting, engineering design, construction and start-up of waste treatment systems associated with a new refinery.

- | | |
|-----------|--|
| 1976-Date | Engineering-Science, Inc., Project Manager (1976-1978). Responsible for several industrial wastewater projects including the following: wastewater investigation to characterize sources of waste streams in a chemical plant and to develop methods to reduce the wastes, sludge settling studies to evaluate settling characteristics of activated sludge at a chemical plant, development of a process document for the design and operation of a wastewater treatment facility at a petrochemical complex, wastewater treatment evaluation which included characterization of wastewater, unit process evaluation, inhibition studies, design review, operations review, preparation of operations manual, operator training and providing operating assistance for waste treatment facilities, various biological treatability studies and bench-scale and pilot-scale evaluation of advanced waste treatment technologies such as granular carbon adsorption, multi-media filtration, powdered activated carbon treatment, ion exchange and ozonation. |
|-----------|--|

ERNEST J. SCHROEDER (Continued)

Project Manager for hazardous waste disposal projects involving waste characterization, development of criteria for disposal of hazardous waste, site investigation, preparation of permits, detailed design, construction of facilities and spill clean-up activities.

Deputy Project Manager for industry-wide pilot plant study of advanced waste treatment in the textile industry. Technologies evaluated included coagulation/clarification, multi-media filtration, granular carbon adsorption, powdered activated carbon treatment, ozonation and dissolved air flotation.

Engineering-Science, Inc., Manager of the Industrial Waste Group in the Atlanta, Georgia office (1978-1980). Responsible for the supervision of industrial waste project managers and project engineers and the management of industrial waste studies conducted in the office. Also directly involved in project management consulting with clients on environmental studies and environment assessment projects, e.g., project manager for several spill control and wastewater treatability projects and for a third-party EIS for a new phosphate mine in Florida.

Engineering-Science, Inc., Manager of Solid and Hazardous Waste Group in the Atlanta, Georgia office (1980-date). Responsible for the supervision of solid and hazardous waste project managers and project engineers and the management of solid and hazardous waste projects in the office. Project activities have included permit and regulatory assistance, environmental audits, waste management program development, ground water monitoring, landfill evaluations, landfill closure design, hazardous waste management, waste inventory, waste recovery/recycle evaluation, waste disposal alternative evaluation, transportation evaluation, and spill control and counter-measure planning.

Project Manager for several Phase I Installation Restoration Program projects for the U.S. Air Force. The objective of this program is to audit past hazardous waste disposal practices that could result in migration of contaminants and recommend priority sites requiring further investigation. Also conducted environmental audits (air, water and solid waste) at several Gulf Oil Company facilities.

ERNEST J. SCHROEDER (Continued)

Publications and Presentations

Schroeder, E. J., "Filamentous Activated Sludge Treatment of Nitrogen Deficient Waste," research paper submitted in partial fulfillment of the requirements for MSCE degree, 1967.

Schroeder, E. J., and Loven, A.W., "Activated Carbon Adsorption for Textile Wastewater Pollution Control," Symposium Proceedings: Textile Industry Technology, December 1978, Williamsburg, VA.

Schroeder, E. J., "Summary Report of the BATEA Guidelines (1974) Study for the Textile Industry," North Carolina Section of AWWA/WPCA, Pinehurst, North Carolina, November 1979.

Mayfield, R. E., Sargent, T. N. and Schroeder, E. J., "Evaluation of BATEA Guidelines (1974) Textiles," U.S. EPA Report, Grant No. R-804329, February 1980.

Storey, W. A., and Schroeder, E. J., "Pilot Plant Evaluation of the 1974 BATEA Guidelines for the Textile Industry," Proceedings of the 35th Industrial Waste Conference, Purdue University, May 1980.

Pope, R. L., and Schroeder, E. J., "Treatment of Textile Wastewaters Using Activated Sludge With Powdered Activated Carbon," U.S. EPA Report, Grant No. R-804329, December 1980.

Schroeder, E. J., "Industrial Solid Waste Management Program to Comply with RCRA," Engineering Short Course Instructor, Auburn University, October 1980.

Schroeder, E. J., "Technical and Economic Impact of RCRA on Industrial Solid Waste Management, Florida Section, American Chemical Society, May 1981.

Biographical Data

MARK I. SPIEGEL

[PII Redacted]

Environmental Scientist



Education

B.S. in Environmental Health Science (Magna cum laude), 1976,
University of Georgia, Athens, Georgia
Limnology and Environmental Biology, University of Florida,
Gainesville, Florida
Business Administration, Georgia State University

Professional Affiliations

American Water Resources Association
Technical Association of the Pulp and Paper Industry

Experience Record

- 1974-1976 U.S. Environmental Protection Agency, Surveillance and Analysis Division. Cooperative Student. On assignment to Air Surveillance Branch, participated in ambient air study in Natchez, Mississippi, and operated unleaded fuel sampling program for Southeast National Air Surveillance Network. For Engineering Branch, participated in NPDES compliance monitoring of industrial facilities throughout the southeast; operation and maintenance studies of municipal waste treatment facilities; and post-impoundment study of West Point Reservoir, West Point, Georgia. Participated in industrial bioassay studies for the Ecological Branch.
- 1977-Date Engineering-Science. Environmental Scientist. Responsible for the conduct of water and wastewater sampling programs and analyses, quality control, laboratory process evaluations, and evaluation of other environmental assessment data. Conducted leachate extraction studies of sludges produced at a large organic chemicals plant to define nature of sludges according to the Resource Recovery and Conservation Act guidelines. Involved in laboratory quality assurance program for the analysis of water samples used in a stream modeling project. Conducted water quality modeling study for Amerada Hess Corporation to determine the assimilative capacity of a stream receiving effluent from a southern Mississippi refinery.

Mark I. Spiegel (Continued)

Participated in bench-scale industrial treatability studies conducted for the American Textile Manufacturers Institute and Eli Lilly Pharmaceuticals in Mayaguez, Puerto Rico, and in carbon adsorption studies for an American Cyanamid chemical plant and Union Carbide Agricultural Products Division.

Involved in various aspects of several industrial environmental impact assessments including preliminary planning for a comprehensive study for St. Regis Paper Company on a major pulp and paper mill expansion project. Assisted in preparation of third-party EIS for EPA and Mobil Chemical Company concerning a proposed 16,000-acre phosphate mining and beneficiation facility. Developed an EIA prior to construction of a pulp and paper complex by the Weyerhaeuser Company in Columbus, Mississippi, which included preparation of a separate document for the Interstate Commerce Commission concerning the construction of a railroad spur to serve the complex. Also involved in formulating the water quality, water resource and socio-economic aspects of an environmental impact assessment for International Paper Company. Participated in large scale site evaluation to determine the suitability and environmental permitting requirements of a site for an east coast brewery for the Adolph Coors Company. Assisted in development of a peat mining and restoration plan for a private concern in coastal North Carolina.

Project Manager. Conducted comprehensive process evaluation of an 80 mgd wastewater treatment system for Weyerhaeuser Company. Responsible for a study to determine the leaching characteristics of sludges for a paint manufacturing facility for RCRA compliance. Also managed study for development of a solid waste management plan for a ceramic pottery manufacturer in northern Alabama which included evaluating surface and groundwater contamination potential from the existing disposal site and assisting manufacturer in developing a disposal program acceptable to state agencies.


Participated as project team member for Phase I Installation Restoration Program projects for the Department of Defense. Studies were conducted at five Air Force bases to identify past hazardous waste disposal practices that could result in migration of contaminants and recommend priority sites requiring further investigation.

Biographical Data

ROBERT E. ZIMMERMANN

Geologist

[PII Redacted]



Education

B.S. in Geology, 1978, University of Akron, Akron, Ohio
Post baccalaureate Studies - University of Akron - Geology, 1979
M.S. - Environmental Geology, University of Akron - Presently
working towards degree
Cartographic Certification - 1981 - University of Akron

Professional Affiliations

American Institute of Professional Geologists
National Water Well Association
Geological Society of America
American Society of Photogrammetry

Experience Record

1978 - 1981 Ohio Environmental Protection Agency, Twinsburg, Ohio
Geologist

- ...Performed RCRA Site inspections of Hazardous Waste Facilities as part of permit process
- ...Performed site investigations and evaluations for the disposal of hazardous and solid waste materials.
- ...Hydrogeologic studies of ambient groundwater quality in various aquifers in Northeast Ohio.
- ...Performed groundwater contamination studies due to various pollution sources (landfills, chemical disposal sites, salt storage, road salting, brine disposal, etc.)
- ...Hydrogeologic evaluation for injection well sites.
- ...Conducted Surface Impoundment Assessment in Northeast Ohio as required by the Safe Drinking Water Act and completed groundwater pollution potential reports on selected impoundments.
- ...Responsible for the compiling and drafting of final copies of groundwater aquifer maps for State of Ohio.
- ...Worked with general public on water quality and well problems.

Robert E. Zimmermann (Continued)

Additional Responsibilities

- ...Worked very closely with various consultants on groundwater contamination problems and approval of new or expanding landfill sites;
- ...Compiled and drafted soil capability maps, groundwater quality maps, aquifer maps, etc.;
- ...Collected and interpreted geochemical analyses of groundwater samples;
- ...Provided input for Ohio's proposed Groundwater Protection Strategy;
- ...Provided geologic information as needed by Ohio EPA staff and general public

1981 - Date Engineering-Science, Inc., Cleveland, Ohio.
Geologist. Responsible for setting up groundwater monitoring programs for industry; supervising drilling and well construction of monitoring wells; assessing impact of contaminants on groundwater quality; determining flow rates, directions, etc., of groundwater at industrial disposal sites; locate and determine new sites suitable for solid and hazardous waste disposal, monitoring groundwater at solid waste facilities; determination of subsurface geology at various locations; hydrogeologic studies at various solid and hazardous waste disposal facilities.

Special Skills

Certified Cartographer, drafting abilities, calligrapher

APPENDIX B

INSTALLATION HISTORY, ORGANIZATION AND MISSIONS

APPENDIX B
INSTALLATION HISTORY, ORGANIZATION AND MISSIONS

HISTORY

This information was obtained from Robins AFB records.

Robins Air Force Base began in 1941 with the announcement by Congressman Carl Vinson of plans to establish a maintenance and supply depot in the southeast. The original tract of 3,000 acres of land was donated by the City of Macon and Bibb County. Subsequent acquisitions by the Federal Government increased the size of the installation to its present 8,855 acres.

The names "Robins" for the Base and "Warner Robins" for the ALC and the City honor the memory of Brigadier General Augustine Warner Robins, Chief of the Air Corps, Material Division, Army Air Corps, 1935-1939, and Commandant of Randolph Field at the time of his death in 1940.

Officially activated on 1 March 1942 and declared a permanent military installation in 1952, the base today is a multi-mission facility. The original intent was to establish a maintenance and supply depot but the installation also became a training center. Original facilities were both temporary and permanent. After World War II, Robins ceased to be a training center but continued as an Air Material Area of AMC (now AFLC).

A second growth spurt began in 1949 when the Fourteenth Air Force Headquarters moved to Robins where it remained until deactivated in 1960. Headquarters Continental Air Command moved to Robins in 1961. Other factors contributing to the expansion were the Korean Conflict in 1950 and the decentralization of prime responsibility by the Air Materiel Command to its Air Material Areas.

The largest construction program commenced in 1958 with contracts exceeding 26 million dollars to prepare facilities for the 19th Bombardment Wing as a tenant organization. Runway enlargement and Capehart Family Housing were two of the numerous items of this program. In 1962,

the runways were further rehabilitated to better accommodate the heavy B-52 and KC-135 aircraft.

Today, Robins AFB, an Air Force Logistics Command installation, is a huge, sprawling military complex of closely related units with diversified missions. The Warner Robins Air Logistic Center is one of five similar organizations in the Air Force. These Centers provide logistics support to the entire Air Force, and it is their mission to keep the United States Air Force Weapons Systems at constant state of readiness.

The Warner Robins ALC determines the parts, supplies, and equipment needed to support the weapon systems for which it is responsible.

The ALC budgets for these items, buys them, stores them, distributes them, repairs and maintains them, and finally disposes of them when they have outlived their usefulness.

In short, the Warner Robins ALC is system manager for 41 aircraft, missile and support systems. In addition, the ALC has 10 program management assignments. The ALC's support mission includes management of 167,000 items in virtually all commodity areas.

The commodity range is from simple hardware items to the free world's most sophisticated aerospace communications and electronic equipment.

The entire Air Force fleet of bombers, fighter-interceptors, reconnaissance, cargo aircraft, and helicopters depends on Warner Robins logistics expertise to fulfill vital logistical needs.

In 1973, the ALC was designed as the Technology Repair Center for airborne electronics, gyros and life support systems. Airborne electronics is one of the largest and most sophisticated repair loads of the new assignments.

The Warner Robins Air Logistics Center has command jurisdiction over the installation with the 2853rd Air Base Group providing the housekeeping functions vital to operation of the installation.

Throughout its 41 years, the relationship of Robins AFB with its neighboring communities has been outstanding. The Base depends upon the local area for many community services and its most important resource people. In turn, Robins AFB is an integral part of the Middle Georgia economy. There is recognition of this dependence as the base and the

communities work together for a solution of mutual problems and the further strengthening of the ties that bind the two.

ORGANIZATIONS AND MISSIONS

This information was obtained from the Robins Air Force Base Tab A-1 Environmental Narrative and the Warner Robins-Air Logistics Center Information Handbook, Fiscal Year 1981, prepared by Management and Cost Analysis, Comptroller.

Warner Robins-Air Logistics Center

The Warner Robins Air Logistics Center (WR-ALC) is one of five organizations that provide logistics support to the entire U. S. Air Force. As a worldwide logistics manager, it is one of the vital parts of the Air Force Logistics Command (AFLC) which supports the aerospace forces.

The Center determines the spare parts, supplies and equipment needed to support the weapon systems for which it is responsible. It budgets for these, buys them, stores them, distributes them, and finally disposes of them when they have outlived their usefulness.

Warner Robins ALC currently serves as System Manager - that is, the overall Air Force focal point - for five transport aircraft, seven utility aircraft, five helicopters, eight air-to-air and air-to-ground missiles, seven drones, the F-15 Fighter and B-57 reconnaissance bomber. The latest system management responsibility assignment is the H-60 Helicopter.

Warner Robins ALC's support mission includes management of nearly 200,000 items ranging from single hardware items to the most sophisticated communications and electronic equipment. The entire fleets of Air Force bombers, fighter-interceptors, reconnaissance, cargo aircraft, and helicopters depend on the Warner Robins ALC to fulfill their logistics needs. Other item management responsibilities include bombing-navigation systems, fire control systems, target acquisition systems, airborne radar, airborne electronic warfare systems, propellers, bearings, general purpose automatic data processing equipment, satellite communication equipment, guns and vehicles.

The largest group of people in the ALC are engaged in repairing, modifying, and overhauling aircraft and equipment. In the aircraft area, this involves depot level repair of the C-141, C-130 and the F-15.

The WR-ALC is also the technology repair center for aircraft propellers, life support equipment, instruments, gyros, and airborne electronics. As Avionics Center of the Air Force, we use some of the most sophisticated equipment and skills anywhere in the world.

The Center has the geographic area logistics support responsibility for most Air Force bases along the eastern coast as well as the Atlantic Missile Test Range, Newfoundland, Labrador, Greenland, Iceland, Bermuda and the Azores.

Tenant Organizations

Robins AFB is the host to many tenants and provides services, facilities, and other support to these organizations. The following list shows the tenant units located on Robins Air Force Base. In addition, Robins AFB supports some 63 off base organizations ranging from high school ROTC detachments to American units in 11 foreign countries.

Robins Air Force Base Exchange (AAFES)

The mission of the Army & Air Force Exchange Service is to:
(1) provide merchandise and services of necessity and convenience which are not furnished from appropriated funds to authorized patrons at uniformly low prices.

Robins Air Force Base Commissary (AFCOMS)

The Air Force Commissary Service (AFCOMS) is a centralized commissary system which manages and operates the worldwide Air Force Commissary function.

1926th Communications Squadron (AFCC)

The mission of the 1926 Communications Squadron is to manage, operate, and maintain communications-electronics-meteorological (C-E-M) services and the air traffic control (ATC) services/facilities in support of Robins AFB.

Detachment 5, Air Force Communications Command (AFCC)

The mission of DET 5, AFCC, is to provide communications-electronics (C-E) and air traffic control (ATC) staff support to Headquarters Air Force Reserve (AFRES).

5th Combat Communications Group (AFCC)

The mission of 5th Combat Communications Group is to provide mobile and transportable communications, aids to navigation, and air traffic control services for use in any area of the world, but primarily in support of the Tactical Air Command.

1839th Engineering Installation Group, Operating Location C (AFCC)

The mission of the 1839th Engineering Installation Group, Operating Location C, Robins Air Force Base, Georgia, is to fabricate AN/TSC-107 (Quick Reaction Package), test, furnish emergency and depot level maintenance of these systems in the field.

Headquarters Air Force Reserve (AFRES)

The United States Air Force Reserve develops, maintains, and provides operationally ready units and trained individuals needed to augment the Air Force in time of war, national emergency or when required to maintain national security.

94th Aerial Port Squadron (AFRES)

The primary peacetime mission of the 94th Aerial Port Squadron is to attain and maintain through training a state of operational readiness that will permit the 94th Aerial Port Squadron to fulfill its mobilization and/or contingency responsibilities.

402d Combat Logistics Support Squadron (AFRES)

The primary mission of the 402d Combat Logistics Support Squadron is to provide highly trained worldwide deployable military teams to accomplish rapid aircraft battle damaged repair and combat packaging and supply operations.

Detachment 6, 3025th Management Engineering Team (AFLC)

The Management Engineering Team (MET) provides manpower, organization, management engineering and management advisory services to all AFLC activities.

Detachment 8, 2762d Logistics Squadron (Special) (AFLC)

Det 8 insures equipment, skills, and techniques capable of performing and supporting the system's operational role are compositely

programmed, managed, and furnished in keeping with overall program objectives.

NCO Academy/Leadership School (AFLC)

The mission of the NCO Academy and NCO Leadership School is to insure that selected NCOs are prepared to assume supervisory positions, more advanced leadership and management responsibilities, and are able to fulfill their role in the Air Force.

321st Field Training Detachment (ATC)

FTD 321 is an off-campus unit of the U.S. Air Force School of Applied Aerospace Sciences, Sheppard AFB, Texas.

3503d USAF Recruiting Group (ATC)

The Group is responsible for all active duty Air Force recruiting programs in 12 states and Puerto Rico.

14th Flying Training Wing (ATC)

The detachment trains the co-pilots of the 19th Bomb wing.

Office of the Placement Coordinator Zone 2

and Atlantic Theatre (DOD)

The DOD Placement Coordinator, Zone 2/Atlantic Theatre, acts for the Assistance Secretary of Defense (Manpower, Reserve Affairs and Logistics) in implementing and administering various DOD-wide personnel programs in the geographic area of the Southeast and Southwest Civil Service Regions and the Atlantic Theatre.

DCAS Quality Assurance Section (DLA)

DCAS Quality Assurance Section is a management area of Defense Contracts Administration Region Atlanta located in Marietta, Georgia.

Defense Property Disposal Office (DLA)

The Defense Property Disposal Office mission is to receive, segregate, inspect, classify, and store excess surplus and scrap property turned in by all host installation organizations and other generators in the geographical area. Dispose of property through reutilization, transfer, donation, sale and destruction.

Federal Aviation Administration

Radar Approach Control (FAA)

The mission of the FAA Radar Approach Control is to provide for the

management of civil and military air traffic operating within the geographical boundaries of the facility's allocated navigable airspace.

Air Force Audit Agency Area Office

Detachment 960 (AFAA)

The mission of Det 960, Air Force Audit Agency (AFAA) Area Audit Office is to provide all levels of Air Force management with independent, objective, and constructive evaluations of the economy, effectiveness, and efficiency with which managerial responsibilities (including financial, operational, and support activities) are carried out.

Detachment 712, Air Force Office of

Special Investigations (AFOSI)

AFOSI Detachment 712 is a field extension of AFOSI District 7, Patrick AFB, FL. AFOSI investigates fraudulent activities, major administrative irregularities and violations of public trust involving Air Force procurement, disposal, pay and allowance matters, and nonappropriated fund activities.

Area Defense Counsel (USAF)

The Area Defense Counsel's mission is to perform legal defense functions.

Detachment 13, 15th Weather Squadron (MAC)

The mission of Det 13, 15 Weather Squadron is to provide or arrange for the environmental services needed to support the exercise, contingency, and wartime requirements of the Warner Robins Logistics Center and the 19th Bombardment Wing.

Headquarters 19th Bombardment Wing (SAC)

The mission of the 19th Bombardment Wing, Heavy, (BMW) is to develop and maintain operational capability to permit the conduct of strategic warfare according to the emergency war order (EWO) plans as directed by proper command authority.

Procurement Center Representative (SBA)

The Procurement Center Representatives (PCRs) represent the Small Business Administration to the commanding officer of the installation on any procurement or technical matter pertaining to policy or operation SBAs programs or the small business community.

4400th Mobility Support Flight (TAC)

The mission is to acquire, store, and maintain the Harvest Eagle Air Transportable Housekeeping Package in a serviceable condition for deployments in support of wartime commitments, contingencies, and exercises.

Detachment 3, 2d Aircraft Delivery Group (TAC)

Responsible for the movement of aircraft from the Southern United States and Central and South America.

RAF - Royal Air Force C-130 Liaison Team

This team serves as liaison for the C-130 program between the Royal Air Force and Robins AFB.

RCAF - Canadian Forces Logistics Unit

The first Canadian Forces Logistics Liaison Detachment is to serve as liaison agency between logistics functions at Robins AFB and the Royal Canadian Air Force.

RAAF - Royal Australian AF Liaison Office

The Royal Australian AF Liaison Office is to serve as liaison agency between logistics functions at Robins AFB and the Royal Australian Air Force.

U. S. Army Corps of Engineers

This U. S. Army unit is known as the U. S. Army Corps of Engineers, Savannah District. It administers and supervises Air Force and Army construction contracts at Robins and the surrounding areas. It coordinates contract sales of government real estate properties and facilities.

General Accounting Office (USGAO)

The U. S. General Accounting Office is an independent, nonpolitical agency in the legislative branch of the government. It provides the Congress, its committees and members with information, analyses and recommendations concerning operations of the government, primarily the executive branch.

GAO is concerned that the federal departments and agencies through their programs and activities, carry out the mandate or intent of legislation enacted by the Congress.

APPENDIX C
SUPPLEMENTAL ENVIRONMENTAL SETTING INFORMATION

APPENDIX C

SUPPLEMENTAL ENVIRONMENTAL SETTING INFORMATION

BIOLOGICAL RESOURCES

The following information regarding the Robins AFB biological resources was obtained from the Tab A-1, Environmental Narrative, 1976. The information pertaining to threatened and endangered vertebrate species was verified and updated by the Georgia Game and Fish Division (GA Game and Fish Div., 1982).

Robins AFB encompasses natural forests totaling 1,964 acres (60% wetlands) and grasslands with low bush totaling 4,197 acres. The wet ecosystem of the wetlands promotes the growth of hardwoods such as oak and hinders the growth of softwoods such as pine. Floating, submerged and emergent types of aquatic plants are present in the wetlands.

The natural forests and grasslands on-base provide habitat areas for a wide variety of animal life. Large and small game animals and a variety of predatory bird exist on-base. Numerous species of fish and waterfowl inhabit the lakes and wetlands on-base. Several of the animal species are included as threatened or endangered as shown in Table C.1.

SUMMARY OF SURFACE WATER QUALITY DATA

A summary of NPDES water quality sampling data is shown in Table C.2. A summary surface water quality sampling data conducted by the Base Bioenvironmental Engineering Office is shown in Tables C.3 through C.10. The EPA interim primary and proposed secondary drinking water standards are shown in Table C.11.

INVENTORY OF PESTICIDES

A summary of the current inventory of pesticides on-base is shown in Table C.12.

GROUND-WATER MONITORING - LANDFILL NO. 4

In October 1979 Law Engineering Testing Company (LETCO) was subcontracted to perform a hydrogeologic and ground-water quality study at Landfill No. 4. The objectives of the study were to determine if any ground or surface water contamination was occurring from Landfill No. 4 or the sludge lagoon, determine the magnitude of contamination if demonstrated to exist, and provide other relevant landfill closure information.

The study consisted of an exploratory drilling program, the installation of a monitoring well system and ground and surface water sampling, summarized in a formal report. The study confirmed the presence of several metals and numerous priority pollutants hydraulically down stream and down-gradient of Landfill No. 4 (LETCO, 1980). Recommendations for further studies were included in the formal report. The Phase I IRP report is a follow-on project to the earlier study and supplements the information collected in the previous work.

TABLE C.1
 THREATENED OR ENDANGERED VERTEBRATE SPECIES
 POTENTIALLY FOUND WITHIN
 ROBINS AIR FORCE BASE

| Common Name | Status | Habitat |
|---------------------------------------|------------|---|
| <u>Fish</u> | | |
| Suwannee Bass | Threatened | Unpolluted springs & rivers |
| Trispot Darter | Threatened | Unpolluted streams |
| <u>Reptiles and Amphibians</u> | | |
| American Alligator | Endangered | Coastal plain swamps & bayous |
| Pine Barrens Tree Frog | Threatened | Pine barren swamps |
| <u>Birds</u> | | |
| Southern Bald Eagle | Endangered | Estuarine shores, rivers |
| Florida Sandhill Crane | Threatened | Wet prairies and fields |
| Ivory-Billed Woodpecker | Endangered | Bottom land hardwood stands |
| Red-Cockaded Woodpecker | Endangered | Old-age pine woodlands |
| Bachman's Warbler | Endangered | River swamp forest |
| <u>Mammals</u> | | |
| Florida Panther | Endangered | Large, unmolested swamp, deer available |

Source: Robins AFB TAB A-2, Updated 1976
 Verified and updated by Georgia Game and Fish Division, 1982

TABLE C.2
1981 NPDES DATA SUMMARY

| Station/Parameter | Unit | Permit Requirement | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV |
|--|------|--------------------|------|------|-----|-----|-----|-----|------|------|-------|-----|-----|
| <u>Station 001 (Runoff Ditch by Missile Storage)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 10.0 | 5.8 | 4.7 | 2.5 | 2.4 | 1.6 | 1.5 | 2.6 | 5.1 | 4.3 | 2.3 | 2.5 |
| Oil/Grease | mg/l | 15.0 | 3.1 | 0.6 | 1.5 | 1.0 | 1.3 | 5.4 | 2.3 | 10.3 | 3.1 | 2.7 | 4.8 |
| Suspended Solids | mg/l | 50.0 | -- | 6.0 | 4.5 | 1.3 | 1.2 | -- | 1.6 | 3.2 | 2.4 | 1.0 | 2.7 |
| pH | unit | 6.0-8.5 | 6.7 | 6.9 | 6.2 | 6.8 | 7.3 | 7.7 | 7.1 | 6.9 | 7.2 | 6.7 | 6.7 |
| <u>Station 002 (Runoff Ditch by Ammo Storage Area)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 15.0 | 8.0 | 6.3 | 6.9 | 3.8 | 3.0 | 1.9 | 1.4 | 4.1 | 3.5 | 2.7 | 2.2 |
| Oil/Grease | mg/l | 15.0 | 4.6 | 0.6 | 1.2 | 1.9 | 2.9 | 3.9 | 4.1 | 9.1 | 5.4 | 3.8 | 4.2 |
| pH | unit | 6.0-8.5 | 6.6 | 6.9 | 8.5 | 7.3 | 7.2 | 7.4 | 7.4 | 7.0 | 6.8 | 7.4 | 6.6 |
| <u>Station 003 (Runoff Ditch North SAC Alert)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 15.0 | 7.0 | 4.3 | 3.2 | 2.5 | 3.0 | 1.3 | 2.0 | 4.1 | 2.5 | 2.6 | 1.8 |
| Oil/Grease | mg/l | 15.0 | 3.0 | 0.8 | 2.1 | 1.3 | 1.7 | 2.1 | 1.7 | 11.0 | 2.6 | 3.1 | 8.4 |
| pH | unit | 6.0-8.5 | 6.7 | 10.3 | 7.2 | 6.5 | 7.3 | 7.2 | 7.6 | 7.3 | 8.0 | 6.9 | 6.7 |
| <u>Station 004 (Hannah Rand Runoff Ditch)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 15.0 | 5.1 | 2.4 | 3.7 | 2.3 | 1.8 | 2.0 | 1.6 | 1.6 | 2.5 | 1.3 | 2.0 |
| Oil/Grease | mg/l | 15.0 | 1.8 | 0.3 | 1.3 | 1.5 | 3.4 | 1.2 | 2.9 | 2.9 | 6.2 | 4.7 | 4.6 |
| pH | unit | 6.0-8.5 | 6.5 | 7.1 | 7.1 | 6.9 | 7.1 | 7.1 | 7.1 | 6.9 | 6.7 | 6.9 | 6.5 |
| NH ₃ -N | mg/l | 2.0 | 0.56 | 0.28 | 0.8 | 0.3 | 0.5 | 1.4 | 0.56 | 1.8 | 0.001 | 2.4 | 0.3 |

TABLE C.2
 (Continued)
 1981 NPDES DATA SUMMARY

| Station/Parameter | Unit | Permit Requirement | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV |
|---|------|--------------------|------|------|------|------|------|------|------|------|-------|------|------|
| <u>Station 005 (Ditch at End of San. Treat. Plant No. 2 Pipe)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 15.0 | 3.5 | 3.5 | 3.7 | 3.4 | 2.7 | 2.4 | 2.4 | 4.9 | 3.0 | 2.9 | 2.5 |
| Oil/Grease | mg/l | 15.0 | 1.8 | 0.1 | 1.6 | 2.5 | 2.1 | 1.6 | 4.8 | 3.7 | 4.1 | 4.4 | 3.2 |
| pH | unit | 6.0-8.5 | 6.9 | 6.7 | 6.7 | 7.1 | 7.2 | 7.2 | 6.9 | 7.0 | 7.1 | 7.1 | 6.6 |
| NH ₃ -N | mg/l | 2.0 | 0.42 | 1.12 | 0.56 | 0.2 | 0.92 | 0.56 | 0.56 | 0.84 | 0.001 | 0.28 | 0.2 |
| <u>Station 006 (Ditch by Dependent Pool)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 15.0 | 4.7 | 3.9 | 3.6 | 2.9 | 2.4 | 1.8 | 1.4 | 4.6 | 1.4 | 2.8 | 1.7 |
| Oil/Grease | mg/l | 15.0 | 2.3 | 0.4 | 1.4 | 1.0 | 4.3 | 1.5 | 1.3 | 2.7 | 5.2 | 6.8 | 3.1 |
| pH | unit | 6.0-8.5 | 7.3 | 6.4 | 6.8 | 6.9 | 7.4 | 7.2 | 7.9 | 7.4 | 7.3 | 6.9 | 7.0 |
| <u>Station 008 (Industrial Waste Treatment Plant #2)</u> | | | | | | | | | | | | | |
| BOD | mg/l | 30.0 | 2.1 | 2.3 | 3.2 | 1.3 | 3.3 | 1.7 | 6.8 | 3.7 | 3.1 | 3.1 | 2.9 |
| Suspended Solids | mg/l | 30.0 | 13.0 | 18.0 | 7.9 | 6.0 | 5.8 | 9.9 | 5.8 | 8.4 | 10.0 | 7.6 | 6.8 |
| COD | mg/l | 150.0 | 40.0 | 50.0 | 38.0 | 20.0 | 48.0 | 60.0 | 61.0 | 60.2 | 55.0 | 60.0 | 40.0 |
| Oil/Grease | mg/l | 15.0 | 1.1 | 1.8 | 9.4 | 4.1 | 6.3 | 9.0 | 4.4 | 6.4 | 3.1 | 8.0 | 6.1 |
| Phenol | mg/l | 0.2 | 0.02 | 0.2 | 0.19 | 0.2 | 0.1 | 0.2 | 0.1 | 0.1 | 0.001 | 0.01 | 0.01 |
| Cyanide | mg/l | 0.35 | 0.04 | 0.04 | 0.05 | 0.06 | 0.05 | 0.1 | 0.04 | 0.05 | 0.03 | 0.04 | 0.05 |
| Cadmium | mg/l | 0.15 | 0.02 | 0.02 | 0.03 | 0.02 | 0.08 | 0.05 | 0.02 | 0.13 | 0.02 | 0.02 | 0.01 |
| Chromium (total) | mg/l | 0.45 | 0.08 | 0.01 | 0.01 | 0.13 | 0.07 | 0.13 | 0.20 | 0.10 | 0.01 | 0.08 | |
| Zinc | mg/l | 0.45 | 0.08 | 0.05 | 0.06 | 0.01 | 0.10 | 0.11 | 0.07 | 0.10 | 0.18 | 0.12 | 0.1 |
| Nickel | mg/l | 0.75 | 0.01 | 0.01 | 0.01 | 0.12 | 0.12 | 0.07 | 0.1 | 0.17 | 0.34 | 0.06 | 0.04 |
| Lead | mg/l | 0.15 | 0.01 | 0.01 | 0.01 | 0.01 | 0.02 | 0.05 | 0.01 | 0.01 | 0.10 | 0.08 | 0.1 |
| Copper | mg/l | 0.30 | 0.02 | 0.04 | 0.2 | 0.02 | 0.18 | 0.10 | 0.07 | 0.3 | 0.04 | 0.07 | 0.08 |
| pH | unit | 6.0-9.0 | 8.8 | 8.3 | 8.9 | 8.6 | 8.8 | 9.0 | 9.0 | 9.0 | 9.0 | 9.0 | 8.1 |

TABLE C.2
 (Continued)
 1981 NPDES DATA SUMMARY

| Station/Parameter | Unit | Permit Requirement | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV |
|--|----------|--------------------|------|-------|--------|------|------|-------|------|------|-------|------|------|
| <u>Station 009 (Industrial Waste Treatment Plant #1)</u> | | | | | | | | | | | | | |
| BOD | mg/l | Not Listed | 16.0 | 20.0 | 23.0 | 21.0 | 25.0 | 19.0 | 18.0 | 15.0 | 8.0 | 8.0 | 8.0 |
| COD | mg/l | " | 39.0 | 50.0 | 44.0 | 10.0 | 32.0 | 20.0 | 50.0 | 31.0 | 31.4 | 20.0 | 20.0 |
| Suspended Solids | mg/l | " | 15.0 | 13.0 | 25.0 | 11.0 | 17.0 | 18.0 | 14.0 | 13.0 | 15.0 | 4.0 | 4.0 |
| Phenol | mg/l | 0.20 | 0.10 | 0.02 | 0.02 | 0.2 | 0.2 | 0.2 | 0.2 | 0.1 | 0.1 | 0.02 | 0.01 |
| Oil/Grease | mg/l | 15.0 | 0.90 | 0.2 | 1.1 | 2.0 | 1.6 | 1.5 | 4.7 | 2.3 | 2.1 | 2.1 | 3.0 |
| NH ₃ -N | mg/l | 2.0 | 0.28 | 0.56 | 0.77 | 1.1 | 0.6 | 1.6 | 0.28 | 1.8 | 0.001 | 0.56 | 0.2 |
| Fecal Coliform | N/100 ml | 400.0 | 1.0 | 200.0 | 131.00 | 1000 | TNTC | 219.0 | 1000 | 3500 | 5000 | 4.0 | 1.0 |
| pH | Unit | 6.0-9.0 | 7.5 | 7.9 | 7.3 | 7.3 | 7.0 | 7.4 | 7.4 | 7.3 | 7.2 | 7.3 | 7.2 |

TNTC = too numerous to count

TABLE C.3
SUMMARY OF WATER SAMPLE RESULTS
FROM MONITORING STATION NO. 001
(Missile Storage Area)
March 1979

| Day | COD (mg/l) | TOC (mg/l) | Oil & Grease (mg/l) | Fe (μ g/l) | K (mg/l) | Na (mg/l) | CN (mg/l) |
|-----|---------------|---------------|---------------------------|--------------------|-------------|--------------|--------------|
| 13 | 20 | 7 | 0.6 | 2,300 | 1.3 | 5.9 | 0.2 |
| 14 | 20 | 8 | 0.3 | 1,600 | 1.1 | 4.5 | 0.1 |
| 15 | 20 | 5 | (a) | 1,000 | 1.1 | 4.5 | (b) |
| 16 | 15 | 7 | (a) | 280 | 1.1 | 4.5 | (b) |
| 17 | 15 | 9 | (a) | 2,900 | 1.0 | 6.0 | (b) |
| 18 | 14 | 7 | (a) | 3,400 | 0.7 | 6.0 | 2.1 |

(a) Less than detectable limits of 0.3 mg/l.

(b) Less than detectable limits of 0.1 mg/l.

(c) Results for the following parameters were less than the detectable limits shown:

NH_3 (0.2 mg/l), PO_4^{+3} (0.2 mg/l), $\text{Cd}(10 \mu\text{g/l})$, $\text{Cr}^{+3}(50 \mu\text{g/l})$,

$\text{Cr}^{+6}(50 \mu\text{g/l})$, $\text{Cu}(20 \mu\text{g/l})$, $\text{Pb}(50 \mu\text{g/l})$, $\text{Hg}(5 \mu\text{g/l})$, $\text{Ni}(50 \mu\text{g/l})$
and $\text{Zn}(50 \mu\text{g/l})$.

TABLE C-4
SUMMARY OF WATER SAMPLE RESULTS FROM
MONITORING STATION NO. 002 (SAC DITCH), NOVEMBER 1978

| Day | COD mg/l | TOC mg/l | Oil & Grease mg/l | Cd µg/l | Cr ⁺³ µg/l | Cu µg/l | Ag mg/l | Na mg/l | K mg/l | Zn µg/l | Temp. °F | pH S.U. | D.O. mg/l | NH ₃ mg/l | Cl ⁻ mg/l |
|-----|-------------|-------------|-------------------------|------------|--------------------------|------------|------------|------------|-----------|------------|-------------|------------|--------------|-------------------------|-------------------------|
| 15 | 11 | 1 | (b) | 31 | 100 | 38 | 28 | 1.6 | 100 | 68.9 | 7.2 | 8.0 | 0 | 0 | |
| 16 | 6 | (a) | (b) | 15 | (c) | 30 | (d) | 54.3 | 1.3 | 140 | 68.9 | 6.8 | 7.0 | 0 | 0 |
| 17 | 5 | (a) | (b) | 19 | 58 | 27 | (d) | 16 | 0.4 | 84 | 68.9 | 7.2 | 6.5 | 0 | 0 |
| 18 | 11 | (a) | (b) | 25 | (c) | 29 | (d) | .31 | 2.0 | 100 | 68 | 7.2 | 7.5 | 0 | 0 |
| 19 | 6 | (a) | 0.4 | 11 | (c) | 29 | (d) | 14.1 | 0.8 | 70 | 59 | 7.2 | 7.0 | 0 | 0 |
| 20 | 6 | (a) | 0.4 | <10 | (c) | 40 | (d) | 2.2 | 0.5 | 70 | 62.6 | 7.0 | 7.5 | 0 | 0 |
| 21 | 6 | 1 | (b) | 41 | (c) | 35 | (a) | 65.5 | 1.3 | 95 | 66.2 | 7.0 | 7.0 | 0 | 0 |

(a) Less than detectable limits of 1.0 mg/l

(b) Less than detectable limits of 0.3 mg/l

(c) Less than detectable limits of 50 µg/l

(d) Less than detectable limits of 10 µg/l

(e) Results for the following parameters were less than the detectable limits shown:
CN (0.1 mg/l), Phenol (0.1 mg/l), Cr⁺⁶ (50 µg/l), Pb (50 µg/l), Ni (50 µg/l),
Surfactants (0.1 mg/l).

TABLE C.5

SUMMARY OF WATER SAMPLE RESULTS FROM
MONITORING STATION NO. 004
(Hannah Rd.,) February 1979

| Sample No. | Oil & Grease (mg/l) | TDS (mg/l) | Hg (mg/l) | Mn (mg/l) | PO ₄ ³⁻ (mg/l) | Cd (µg/l) | Cr ⁶⁺ (µg/l) | Cr ³⁺ (µg/l) | Cu (µg/l) | Fe ³⁺ (µg/l) | Hg (µg/l) | Ni (µg/l) | Ag (µg/l) | Zn (µg/l) | Ca (µg/l) | Na (µg/l) | Cl ⁻ (µg/l) | SO ₄ ²⁻ (µg/l) | HCO ₃ (µg/l) | Pheno (µg/l) | CNS (µg/l) | | | |
|------------|------------------------|---------------|--------------|--------------|---|--------------|----------------------------|----------------------------|--------------|----------------------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------------------|---|----------------------------|-----------------|---------------|----------|---------|---|
| | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | 130 | 35 | (a) | 6.9 (b) | 0.5 | 0.5 | (d) | (e) | 81 | 2.3 | 170 | (e) | (e) | (d) | 91 | 2.3 | 3 | 4 | 16 | 100 | 0.3 | 0.55 (c) | 0 | |
| 8 | 95 | 23 | (a) | 8.6 (b) | 0.5 | 0.5 | (d) | (e) | 36 | 2.0 | 150 | (d) | (e) | (d) | 69 | 22.5 | 3 | 5 | 20 | 95 | 0.4 | 1.1 (c) | 0 | |
| 9 | 20 | 5 | 0.4 | 4.1 (b) | 0.5 | 0.4 | (d) | (e) | 30 | 2.2 | 140 | (d) | (e) | (d) | 140 | 17 | 2 | 3 | 19 | 46 | 0.1 | 0.45 (c) | 0 | |
| 10 | 35 | 11 | 0.8 | 7.5 (b) | 0.4 | 0.4 | (d) | (e) | 32 | 2.2 | 150 | (e) | 50 | (d) | 89 | 20 | 2 | 4 | 32 | 24 | 6.3 | 0.2 | 0.05 | 0 |
| 11 | 1 | 5 | 4.0 (b) | 4.0 (b) | 0.4 | 0.4 | (d) | (e) | 32 | 1.6 | 130 | (e) | (e) | (d) | 14 | 2 | 2 | 15 | 28 | 13 | 0.1 | 0.52 | 0 | |
| 12 | 35 | 10 | 1.4 | 7.5 (b) | 0.5 | 1.5 | (d) | (e) | 57 | 39 | 1.6 | 57 | (a) | (d) | (e) | 18 | 1.1 | 4 | 32 | 16 | 78 | 0.2 | 0.17 | 0 |
| 13 | 50 | 12 | 1.0 | 8.0 (b) | 0.4 | 0.5 | (d) | (e) | 57 | 110 | 2.4 | 180 | (e) | (d) | 130 | 17 | 2 | 4 | 37 | 16 | 65 | 0.4 | 1.5 (c) | 0 |

(a) Less than detectable limits of 0.3 µg/l

(b) Exceeds MNRIS permit limits of 2.0 µg/l

(c) Exceeds MNRIS permit limits of 0.2 µg/l

(d) Less than detectable limits of 10 µg/l

(e) Less than detectable limits of 50 µg/l.

TABLE C.6

SUMMARY OF WATER SAMPLE RESULTS FROM MONITORING STATION NO. 005
 (Golf Course Lake), March 1979

| Day | COD mg/l | TOC mg/l | Oil & Grease mg/l | PO ₄ mg/l | Cu µg/l | Fe µg/l | Hg µg/l | Zn µg/l | K µg/l | Na mg/l | Ca mg/l | CN mg/l |
|-----|-------------|-------------|-------------------------|-------------------------|------------|------------|------------|------------|-----------|------------|------------|------------|
| 20 | 10 | (a) | (b) | 0.3 | - | 1,400 | 20 | - | 0.5 | 1.4 | 12.2 | - |
| 21 | 10 | (a) | (b) | 0.2 | 36 | 1,800 | (d) | (e) | 0.5 | 2.7 | - | 2.3 |
| 22 | 6 | 1 | (b) | 0.4 | 65 | 1,600 | (d) | 50 | 0.5 | 2.3 | - | - |
| 23 | 6 | (a) | (b) | (c) | 40 | 1,400 | (d) | (e) | 0.5 | 2.3 | - | - |
| 24 | 6 | (a) | (b) | (c) | 35 | 570 | (d) | (e) | 1.5 | 0.8 | - | - |
| 25 | 6 | 1 | (b) | (c) | 30 | 800 | (d) | (e) | 1.2 | 1.1 | - | - |
| 26 | <5 | (a) | 5 | (c) | <20 | 1,200 | (d) | 170 | 1.5 | 1.9 | - | - |

(a) Less than detectable limits of 1.0 mg/l

(b) Less than detectable limits of 0.3 mg/l

(c) Less than detectable limits of 0.2 mg/l

(d) Less than detectable limits of 5 µg/l

(e) Less than detectable limits of 50 µg/l

(f) Results for the following parameters were less than the detectable limits shown:
 NH₃ (0.2 mg/l), Cd (10 µg/l), Cr⁺³ (50 µg/l), Cr⁺⁶ (50 µg/l), Pb (50 µg/l),
 and Ni (50 µg/l).

TABLE C.7
SUMMARY OF WATER SAMPLE RESULTS FROM
HORSE CREEK (HC) AND THE STABLE AREA (006)
APRIL 1979

| Day | COD (mg/l) | TOC (mg/l) | Oil & Grease (mg/l) |
|--------------------|---------------|---------------|---------------------------|
| <u>Stable Area</u> | | | |
| 2 | 15 | 5 | (a) |
| 3 | (a) | 4 | (a) |
| 4 | (a) | 4 | (a) |
| 5 | 10 | 4 | (a) |
| 6 | 6 | 3 | (a) |
| 7 | 6 | (a) | (a) |
| 8 | 6 | 3 | (a) |
| <u>Horse Creek</u> | | | |
| 9 | 15 | 0.7 | (a) |
| 10 | 10 | 3 | (a) |
| 11 | 15 | 4 | (a) |
| 12 | 5 | 4 | (a) |
| 13 | 5 | 5 | (a) |
| 14 | 10 | 5 | (a) |
| 15 | 5 | 3 | (a) |

(a) Less than detectable limits of 0.3 mg/l.

(b) Results for the following parameters were less than the detectable limits shown:

NH_3 (0.2 mg/l), PO_4 (0.2 mg/l) and surfactants (0.1 mg/l).

TABLE C.8
SUMMARY OF WATER SAMPLE RESULTS FROM
INDUSTRIAL WASTE TREATMENT PLANT ADDITION

| Day | COD (mg/l) | TOC (mg/l) | NH ₃ (mg/l) | NO ₃ (mg/l) | PO ₄ (mg/l) | Surfac- tants (mg/l) | Phenol (mg/l) | CN (mg/l) | pH |
|-----|---------------|---------------|---------------------------|---------------------------|---------------------------|----------------------------|------------------|--------------|-----|
| 1 | 30 | 13 | 7.2 | 0.5 | 3.1 | 0.2 | 0 | 0 | 7.2 |
| 2 | 10 | 2 | 3.2 | 1.9 | 3.5 | 0.1 | 0 | 0 | 7.4 |
| 3 | 30 | 13 | 8.0 | 0.3 | 4.1 | 0.1 | 0 | 0 | 7.2 |
| 4 | 28 | 13 | 4.0 | 0.8 | 3.5 | 0.1 | 0 | 0 | 7.4 |
| 5 | 28 | 11 | 3.5 | 1.0 | 2.8 | 0.2 | 0 | 0 | 7.2 |
| 6 | 15 | 10 | 2.5 | 1.2 | 2.5 | 0.1 | 0 | 0 | 7.4 |
| 7 | 30 | 13 | 4.0 | 0.9 | 2.0 | 0.2 | 0 | 0 | 7.2 |

- (a) Results for oil and greese were less than the detectable limit of 0.3 mg/l.
- (b) No sample results were given for the following parameters: Cd, Cr⁺³, Cr⁺⁶, Cu, Fe, Mn, Hg, Ni, Ag, Zn, Ca, Mg, K, Na, Cl⁻, SO₄

TABLE C.9

SUMMARY OF WATER SAMPLE RESULTS FROM MAJOR BASE LAKES,
August 8 to October 13, 1978

| | DUCK LAKE | | | LIMA LAKE | | | SCOUT LAKE | | | | |
|------------------------------------|----------------|------|------|-----------|----------------|------|------------|----------------|------|------|------|
| | No. of Samples | Min. | Max. | Mean | No. of Samples | Min. | Max. | No. of Samples | Min. | Max. | Mean |
| Cu, $\mu\text{g/l}$ | 11 | 0 | 0 | - | 4 | 0 | 0 | - | 4 | 0 | 0 |
| Cr ⁺⁶ , $\mu\text{g/l}$ | 11 | 0 | 0 | - | 4 | 0 | - | - | 4 | 0 | 0 |
| Cr ⁺³ , $\mu\text{g/l}$ | 11 | 0 | 0 | - | 4 | 0 | - | - | 4 | 0 | 0 |
| NH ₃ , mg/l | 11 | 0 | 0 | - | 4 | 0 | 0 | - | 4 | 0 | 0 |
| NO ₃ , mg/l | 11 | 0 | 0 | - | 4 | 0 | 0 | - | 4 | 0 | 0 |
| NO ₂ , mg/l | 11 | 0 | 0 | - | 4 | 0 | 0 | - | 4 | 0 | 0 |
| PO ₄ , mg/l | 11 | 0 | 0.4 | 0.12 | 4 | 0 | 0.18 | 0.05 | 4 | 0 | 0 |
| Fe, $\mu\text{g/l}$ | 10 | 100 | 300 | 160 | 4 | 0 | 100 | 40 | 4 | 0 | 100 |
| SO ₄ , mg/l | 10 | 0 | 0 | - | 4 | 0 | 0 | - | 4 | 0 | 0 |
| Ca, mg/l | 1 | 10 | 10 | 10 | 1 | 5 | 5 | 5 | 1 | 5 | 5 |
| Cl ⁻ , mg/l | 1 | 2.5 | 2.5 | 2.5 | 1 | 2.5 | 2.5 | 2.5 | 1 | 2.5 | - |
| Pb, $\mu\text{g/l}$ | 10 | 6.8 | 8.0 | 7.1 | 1 | 5.5 | 5.5 | 5.5 | 1 | - | - |

TABLE C.10

SUMMARY OF WATER SAMPLE RESULTS FROM THE WASTE TREATMENT PLANTS

August 8 - December 13, 1978

| Station 009 (Ind. Waste Treat. Plt #1) | | Station 005 (End of San. Treat. Plt. No. 2 Pipe) | | Station 004 (Hannah Road Ditch) | | |
|---|------|---|------|------------------------------------|------|------|
| No. of Samples | Min. | No. of Samples | Min. | No. of Samples | Min. | |
| Cu, $\mu\text{g}/\text{l}$ | 13 | 0 | 13 | 0 | 13 | 0 |
| Cr ⁺⁶ , $\mu\text{g}/\text{l}$ | 13 | 0 | 13 | 0 | 13 | 0 |
| Cr ⁺³ , $\mu\text{g}/\text{l}$ | 13 | 0 | 13 | 0 | 13 | 0 |
| NH ₃ , mg/l | 13 | 3 | 12.7 | 7.4 | 13 | 0 |
| NO ₃ , mg/l | 9 | 0.1 | 5.1 | 2.5 | 6 | 1 |
| NO ₂ , mg/l | 9 | 0.01 | 1.0 | 0.5 | 7 | 0.03 |
| PO ₄ , mg/l | 10 | 1.8 | 4.0 | 2.8 | 10 | 5 |
| Fe, $\mu\text{g}/\text{l}$ | 12 | 200 | 500 | 370 | 13 | 50 |
| SO ₄ , mg/l | 6 | 40 | 80 | 65 | 7 | 15 |
| Ca, mg/l | 6 | 50 | 60 | 52.5 | 7 | 40 |
| Cl, mg/l | 7 | 18 | 30 | 22.3 | 7 | 20 |
| Pb, $\mu\text{g}/\text{l}$ | 7 | 6.8 | 7.4 | 7.2 | 7 | 7.4 |

TABLE C.11
EPA INTERIM PRIMARY AND PROPOSED SECONDARY
DRINKING WATER STANDARDS

| PARAMETER | MAXIMUM LEVEL |
|---------------------------|-------------------------|
| <u>A. Interim Primary</u> | |
| Arsenic | 0.05 |
| Barium | 1.0 |
| Cadmium | 0.01 |
| Chromium (VI) | 0.05 |
| Fluoride | 1.4 to 2.4 |
| Lead | 0.05 |
| Mercury | 0.002 |
| Nitrate (as N) | 10 |
| Selenium | 0.01 |
| Silver | 0.05 |
| Endrin | 0.002 |
| Lindane | 0.004 |
| Methoxychlor | 0.1 |
| Toxaphene | 0.005 |
| 2,4-D | 0.01 |
| 2,4,5-TP Silvex | 0.01 |
| Radium | 5 pCi/l |
| Gross Alpha | 15 pCi/l |
| Gross Beta | 4 millirem/yr |
| Turbidity | 1 TU |
| Coliform Bacteria | 1/100 ml |
| <u>B. Secondary</u> | |
| Chloride | 250 |
| Copper | 1 |
| Foaming Agents | 0.5 |
| Hydrogen Sulfide | 0.05 |
| Iron | 0.3 |
| Manganese | 0.05 |
| Sulfate | 250 |
| Total Dissolved Solids | 500 |
| Zinc | 5 |
| Color | 15 Color Units |
| Corrosivity | Non-corrosive |
| Odor | 3 threshold Odor Number |
| pH | 6.5 to 8.5 |

TABLE C.12
ROBINS AIR FORCE BASE
CURRENT PESTICIDES USED

| Insecticides | Herbicides | Rodenticides |
|----------------|------------|---------------------|
| Avitral | Ansar | Zinc Phosphide Bait |
| Amdro | Borocil | Pinalyl Bait |
| Baygon | Diquat | Diphacinone Bait |
| Chlordane | Maintain | Strychnine Bait |
| Cyanogas | Retard | |
| Cygon | Round-Up | |
| Dursban | Spike | |
| Dibrom (Naled) | Velpar | |
| Diazinon | 2,4-D | |
| Ficam | | |
| Lindane | | |
| Malathion | | |
| Naptha | | |
| DDVP | | |
| Sevin | | |
| D-Phenothrin | | |

Source: Robins AFB Bioenvironmental Engineering Files

TABLE C.13

ANALYSIS OF SOIL SAMPLES COLLECTED FROM THE RADIOACTIVE
WASTE DISPOSAL AREA

| Parameters | Units | Approximate Sample Location | | |
|--------------|-------|---------------------------------|----------------|---|
| | | 100' from Site (Bottom of Hill) | Center of Site | 20' from Site (Up Hill) 50' from Site (Down Grade) |
| Gross Alpha | pCi/g | 20 | 26 | 20 20 |
| Gross Beta | pCi/g | 17 | 27 | 20 24 |
| Potassium 40 | pCi/g | .17 | 1.82 | .97 1.24 |
| Cesium 137 | pCi/g | .084 | 1.59 | .77 .30 |
| Uranium 238 | pCi/g | 1.07 | 1.03 | 1.88 1.87 |
| Radium 226 | pCi/g | .91 | 1.26 | 1.35 1.66 |
| Thorium 232 | pCi/g | 1.45 | 1.34 | 2.00 2.40 |
| Cobalt 60 | pCi/g | | .070 | |

SOURCE: Base reports

APPENDIX D
MASTER LIST
INDUSTRIAL SHOPS

APPENDIX D

MASTER LIST

INDUSTRIAL SHOPS

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| DIRECTORATE OF DISTRIBUTION (DS*) | | | |
| Supply & Equip. Shed | 28 | | |
| Supply & Equip. Shed | 29 | | |
| LOX Storage | 32 | | |
| Hydrogen Fluoride Bldg. | 38 | | |
| Liq. Fluoride Pump Station | 39 | | |
| LOX Storage | 50 | | |
| Supply & Equipment Warehouse | 59 | | |
| Liq. Fuel Pump Station | 70 | | |
| Liq. Fuel Pump Station | 72 | | |
| Liq. Fuel Pump Station | 73 | | |
| Terminal Air Freight | 127 | | |
| Supply & Issue Shipping | 153 | | |
| (Name not listed)** | 193 | | |
| POL Operations/Qual. Control | 194 | X | |
| Liq. Fuel Pump Station | 195 | | |
| POL Operations/Qual. Control | 196 | X | |
| (Name not listed) | 209 | | |

* Office symbols used by the Air Force.

** Indicates no name for the facility was listed in the BEE records.

X Indicates presence of hazardous materials or generation of hazardous waste.

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| Directorate of Distribution (Continued) | | | |
| (Name not listed) | 211 | | |
| Supply & Equipment Warehouse | 232 | | |
| Shop Shelter | (241-closed) | | |
| Depot MAT Process | 247 | | |
| Shop Shelter | 248 | | |
| Logistics Facility Depot | 300 | | |
| Warehouse Supply & Equip. Depot | 301 | | |
| Vehicle Fueling Station | 303 | | |
| Mag Storage | 306 | | |
| Supply & Equipment Warehouse | 309 | | |
| Supply & Equipment Warehouse | 310 | | |
| Storage Igloo | 311 | | |
| Storage Igloo | 312 | | |
| Segregated Mag Storage | 313 | | |
| Supply & Equip. Shed | 320 | | |
| Supply & Equip. Shed | 322 | | |
| Chemical Storage | 327 | X | X |
| Chemical Storage | 328 | X | X |
| Bottled Gas Storage | 329 | | |
| Bottled Gas Storage | 330 | | |
| Bottled Gas Storage | 331 | | |
| Supply & Equip. Shed | 334 | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| Directorate of Distribution (Continued) | | | |
| Supply & Equip. Shed | 334 | | |
| Supply & Equip. Shed | 335 | | |
| Supply & Equip. Shed | 336 | | |
| Supply & Equip. Shed | 337 | | |
| Supply & Equip. Shed | 338 | | |
| Supply & Equip. Shed | 339 | | |
| Supply & Equip. Shed | 350 | | |
| Material Process. Depot | 351 | | |
| Material Process. Depot | 354 | X | X |
| (Name not listed) | 357 | | |
| Material Process. Depot | 364 | | |
| Material Process. Depot | 365 | | |
| Supply & Equipment Warehouse | 366 | | |
| Supply & Equipment Warehouse | 367 | | |
| Lumber Shed | 372 | | |
| Material Process. Depot | 376 | | |
| Supply & Equipment Warehouse | 380 | | |
| Supply & Equipment Warehouse | 385 | | |
| Supply & Equipment Warehouse | 602 | | |
| Material Process. Depot | 606 | | |
| Supply & Equipment Warehouse | 641 | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| Directorate of Distribution (Continued) | | | |
| Supply & Equipment Warehouse | 660 | | |
| (Name not listed) | 10091 | | |
| (Name not listed) | 10094 | | |
| (Name not listed) | 10187 | | |
| (Name not listed) | 10188 | | |
| DIRECTORATE OF MAINTENANCE (MA) | | | |
| Aircraft Division (MAB) | | | |
| Hydrogen Fluoride Bldg. | 23 | X | |
| Functional Testing | 40 | X | X |
| Nose Dock | 44 | X | X |
| Nose Dock | 47 | X | |
| Nose Dock | 48 | X | |
| Nose Dock | 49 | X | |
| Compress Air Bldg. | 53 | | |
| Corrosion Control | 54 | X | X |
| Nose Dock | 55 | X | X |
| Paint Shop | 89 | X | X |
| Hazardous Storage | 93 | X | |
| (Old Corrosion Control) | (110) | (X) | (X) |
| Hazardous Storage | 112 | X | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| Aircraft Division (Continued) | | | |
| (Name not listed) | 115 | | |
| Aircraft Training Facility | 120 | | |
| Non-Destructive Inspect. | 125 | X | |
| Welding | 125 | | |
| C-141 | 125 | | |
| C-130 | 125 | | |
| F-15 | 125 | | |
| Radio Repair | 125 | | |
| Engine Repair | 125 | X | X |
| Landing Gear | 125 | X | X |
| Tire Shop | 125 | | |
| Sealant Shop | 125 | X | |
| (Name not listed) | 145 | | |
| F-15 Maintenance | 149 | X | X |
| Hazardous Storage | 151 | | |
| AIRBORNE ELECTRONICS DIVISION (MAI) | | | |
| Surveillance & Inst. Shop | 635 | | |
| Bomb Navigation | 640 | X | X |
| Radar Navigation | 640 | X | X |
| Weapons | 640 | X | X |
| Communications Shop | 645 | X | X |
| Fire Control Shop | 645 | X | X |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| Airborne Electronics Division (Continued) | | | |
| Electronic Warfare | 645 | X | |
| Air Cond. & Engr. Shop | 647 | | |
| Boresight Shop | 675 | | |
| INDUSTRIAL PRODUCTS DIVISION (MAN) | | | |
| Paint Shop | 125 | X | X |
| Life Support | 128 | | |
| Hazardous Storage | 132 | X | |
| Pylon Shop | 140 | | |
| Tubing & Cable | 140 | | |
| F-15 Shop | 140 | | |
| Parachute Shop | 140 | | |
| Turret Shop | 140 | X | X |
| Electric Shop | 140 | | |
| F-15 Pylon | 140 | | |
| Pneudraulics | 140 | X | |
| Propeller Cleaning | 140 | X | X |
| Propeller Shop | 140 | X | X |
| Machine Shop | 140 | | |
| Heat Treat Shop | 140 | | |
| Electroplating Shop | 142 | | X |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|---|---------------------------------|-----------------------------|----------------------------|
| <hr/> | | | |
| Industrial Products Division (Continued) | | | |
| Hydrostatic Testing | 150 | X | X |
| Battery Shop | 150 | X | X |
| (Name not listed) | 154 | | |
| Physical Lab | 165 | X | |
| Chemical Lab | 165 | X | |
| Tubing & Cable | 169 | | |
| Small Motor Repair | 169 | | |
| Cleaning Shop | 169 | X | X |
| Metal Bond | 169 | X | |
| Forms and Patterns | 169 | | |
| Small Motor Mfg. | 169 | | |
| Plant Services | 173 | X | |
| Industrial X-ray | 181 | X | X |
| Fabric Shop | 181 | | |
| Parachute Shop | 181 | | |
| Paint Shop | 605 | X | X |
| Plastics Shop | 670 | X | X |
| Radome Strip | 680 | X | X |
| <hr/> | | | |
| DIRECTORATE OF CONTRACTING AND MANUFACTURING (PM) | | | |
| Maintenance Dock | 67 | | |
| Aircraft Engine Shipping | 148 | X | |
| Precision Measurement Equip. Lab | 162 | X | X |
| <hr/> | | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| USAF HOSPITAL | | | |
| X-ray Lab | 700 | X | |
| Dental Lab | 700 | X | |
| 5 COMBAT COMMUNICATIONS GROUP (CCG) | | | |
| (Name not listed) | 600 | | |
| (Name not listed) | 611 | | |
| Generator Shop | 615 | | |
| Supply & Equipment Warehouse | 651 | | |
| Vehicle Maintenance | 655 | | |
| Chemical Storage | 656 | | |
| Supply & Equipment Warehouse | 658 | | |
| Supply & Equipment Warehouse | 659 | | |
| Maintenance Facility | 925 | | |
| (Name not listed) | 948 | | |
| (Name not listed) | 949 | | |
| (Name not listed) | 950 | | |
| (Name not listed) | 951 | | |
| Communications Shipping | 962 | | |
| (Name not listed) | 10000 | | |
| (Name not listed) | 10023 | | |
| (Name not listed) | 10070 | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| 5 Combat Communications Group (Continued) | | | |
| (Name not listed) | 10085 | | |
| (Name not listed) | 10098 | | |
| (Name not listed) | 10205 | | |
| (Name not listed) | 10207 | | |
| (Name not listed) | 10212-10218 | | |
| 19 BOMBARDMENT WING (BW) | | | |
| (Name not listed) | 1 | | |
| Traffic Check House | 6 | | |
| Ordnance Control Point | 8 | | |
| (Name not listed) | 9 | | |
| (Name not listed) | 10 | | |
| Readiness Crew | 12 | | |
| Traffic Check House | 16 | | |
| Aircraft Maintenance Shipping | 22 | | |
| Engine Test Cell | 31 | X | X |
| Fuel Cell Repair | 59 | | X |
| Nose Dock | 66 | | |
| Nose Dock | 67 | | |
| (Name not listed) | 69 | | |
| (Name not listed) | 74 | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| 19 Bombardment Wing (Continued) | | | |
| Weapons Shop | 75 | X | |
| Propulsion Shop | 76 | X | |
| Environmental Systems | 76 | | |
| Munitions Shop | 76 | | |
| Multi-Maintenance Shops | 79 | X | |
| Corrosion Control | 80 | X | X |
| Tire Shop | 81 | X | |
| Aerospace Ground Equipment (AGE) | 82 | X | X |
| (Name not listed) | 85 | X | |
| Equipment Maintenance | 86 | X | |
| Munitions Shop | 94 | | |
| SRAM Missile Shop | 100 | | |
| (Name not listed) | 10001 | | |
| (Name not listed) | 10004 | | |
| (Name not listed) | 10006 | | |
| (Name not listed) | 10007 | | |
| (Name not listed) | 10079 | | |
| (Name not listed) | 10080 | | |
| (Name not listed) | 10082 | | |
| (Name not listed) | 10102 | | |
| (Name not listed) | 10120 | | |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|---|------------------------------------|-----------------------------------|----------------------------------|
| 1926 COMMUNICATIONS INSTALLATION GROUP (CIG) | | | |
| (Name not listed) | 10148-10154 | | |
| (Name not listed) | 3 | | |
| (Name not listed) | 19 | | |
| (Name not listed) | 26 | X | |
| Aircraft Maintenance | 46 | | |
| Facility Depot | 56 | | |
| Communications Center | 161 | | |
| Base Communications | 225 | | |
| (Name not Listed) | 608 | | |
| Vehicle Maintenance | 978 | | |
| Instrument Repair | 1684 | X | |
| 2853 AIR BASE GROUP (ABG) | | | |
| Graphics Services | 321 | X | |
| Photo Lab | 321 | X | X |
| BX Gas Station | 922 | X | X |
| Auto Hobby Shop | 985 | X | X |
| Fuel Vehicle Repair | 190 | X | X |
| Vehicle Maintenance | 302 | X | X |
| Paint & Body Shop | 304 | X | X |
| Auto Maintenance Shop | 307 | X | X |

APPENDIX D (CONTINUED)

| Name | Present Location (Bldg. No.) | Handles Hazardous Materials | Generates Hazardous Wastes |
|--|---------------------------------|-----------------------------|----------------------------|
| 2853 CIVIL ENGINEERING SQUADRON (CES) | | | |
| Tire Shop | 308 | X | |
| Fire Training | 5 | X | |
| Fire Training | 7 | X | |
| Fuel Tank Repair | 63 | X | |
| Steam Facility | 83 | | |
| Fire Station | 109 | X | |
| Indus. Waste Treat. Plant (IWTP) | 141 | X | X |
| IWTP | 147 | | |
| Steam Plant | 177 | | |
| Metal Maintenance Shop | 270 | | |
| Paint Shop | 272 | X | X |
| Plumbing Shop | 272 | | |
| Refrig. Shop | 272 | | |
| Structural Shop | 272 | | |
| Electric Shop | 273 | | |
| Paint Shop | 275 | X | X |
| Generator Shop | 286 | | |
| Entomology Unit | 295, 296 | X | |
| Sludge Dewatering | 352 | X | X |
| Grounds Shop | 591, 593 | X | X |

APPENDIX E
PHOTOGRAPHS

**Impact
Sied
Testing
Facility**

**Bulk
Fuel
Storage
Tanks**

**Landfill
No. 1**



LANDFILL No. 1

**Landfill
No. 2**

**Sludge
Lagoon**

**Landfill
No. 4**



**LANDFILLS No. 2 & No. 4
and SLUDGE LAGOON**



Sludge
Lagoon

Landfill
No. 4

SLUDGE LAGOON




Location
of
Disposal
Trench

HAZARDOUS WASTE BURIAL SITE



HAZARDOUS WASTE BURIAL SITE




FIRE PROTECTION TRAINING AREA NO. 4

**Estimated Location of
Fire Protection Training Area No. 2**



**FIRE PROTECTION
TRAINING AREA No. 2**



LANDFILL No. 3

APPENDIX F
WATER SUPPLY WELL LOGS

- City of Warner Robins
- Robins AFB

ENVIRONMENTAL PROTECTION DIVISION
WATER SUPPLY SECTION
270 WASHINGTON STREET, S.W.
ATLANTA, GEORGIA 30334

WELL DATA SHEET FOR PUBLIC WATER SYSTEM
(TO BE COMPLETED BY WATER WELL CONTRACTOR)

OF WATER SYSTEM: Warner Robins, Ga - Well No. 1-A COUNTY: Houston
LOCATED AT No. 1 Water plant TYPE WATER SYSTEM: COMMUNITY NON-COMMUNITY
OWNER CITY OF Warner Robins, GA DRILLER Rowe Drilling Co., Inc.
ADDRESS P.O. Box 1468, Warner Robins, Ga 31093 ADDRESS P.O. Box 1363, Tallahassee, Fl 32302
PHONE (904) 576-1271 LIC. NO.: 72

WELL DESCRIPTION

DATE DRILLED: 6/8/81

TOTAL DEPTH: 540 FT.

TYPE DRILLING (INDICATE):

HOTARY PERCUSSION OTHER

HOLE DIAMETER

SIZE .22 IN. FROM 0 FT. TO 120 FT.

SIZE .25 IN. FROM 120 FT. TO 540 FT.

SIZE ... IN. FROM ... FT. TO ... FT.

(USE ADDITIONAL SHEETS IF NECESSARY)

CASING RECORD

TYPE MATERIAL: Black Steel

WALL THICKNESS: .375

WEIGHT/FOOT

SIZE 26 IN. FROM 0 FT. TO 120 FT.

SIZE 16 IN. FROM 0 FT. TO 255 FT.

SIZE 12 IN. FROM 255 FT. TO 540 FT.

(USE ADDITIONAL SHEETS IF NECESSARY)

WELL SCREEN

TYPE MATERIAL: 304 Stainless Steel

SIZE 12 IN. FROM 240 FT. TO 350 FT.

SIZE 12 IN. FROM 320 FT. TO 380 FT.

SIZE 12 IN. FROM 420 FT. TO 430 FT.

SIZE 12 IN. FROM 440 FT. TO 460 FT.

SIZE 12 IN. FROM 510 FT. TO 530 FT

WAS SLOT SIZE DETERMINED BY SIEVE ANALYSIS:
YES NO

GROUTING

TYPE GROUT: Neat Portland

APPLIED BY PRESSURE: YES NO

FROM 120 FT. TO 0 FT

FROM FT. TO FT.

STATIC WATER LEVEL 129 FT.

PUMPING WATER LEVEL: 149 FT. AT 1557 GPM

TEST PUMP DATA

DATE TESTED: June 8 & 9, 1981

PUMPED BAILED ESTIMATED

PUMP RATED: 4000 GPM 217 HP

TOTAL CONTINUOUS HRS. TESTED: 24

DID WATER LEVEL STABILIZE: YES NO

HRS. RUN BEFORE STABILIZATION: 1

YIELD 1557 GPM AFTER 24 HRS. OF CONTINUOUS
PUMPING

DISCHARGE PRESSURE: 0 PSI

WATER LEVEL BEFORE TEST: 129 FT.

TOTAL DRAWDOWN: 16 FT
(ATTACH COPY OF DRAWDOWN MEASUREMENTS)

SPECIFIC CAPACITY 62.5 GPM/FT.

NO MINUTES FOR WELL TO RECOVER:

WAS WELL DEVELOPED AND DISINFECTED: YES NO

WERE UNTREATED WATER SAMPLES COLLECTED

FOR BACTI: YES NO

FOR CHEMICAL: YES NO

PERMANENT PUMP DATA (BY CONTRACTOR OR
OWNER)

PUMP TYPE: Pumpless OUTLET SIZE: 10 IN.

POWERED BY: 150 HP

RATE: 1500 GPM

TOTAL DYNAMIC HEAD: 216 FT.

PUMP SET AT: 200 FT. w/30 Ft. Tail Pipe

PUMP DISINFECTED: YES NO

DEEP WELL AIR LINE, TYPE MATERIAL: Galv.

LENGTH 200 FT.

ACCESS PORT, DIA: 2 IN.

COMPLETE WELL LOG ON REVERSE SIDE

WF #521

WELL LOG

1-A

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|--------------|------------|-------------------------------|---------|---------------------------------|
| 0 | 20 | red clay | | |
| 20 | 33 | coarse sand, red | | |
| 33 | 45 | brown coarse sand | | |
| 45 | 62 | clay coarse sand | | |
| 62 | 89 | | | |
| 89 | 110 | fine & coarse sand | | |
| 110 | 122 | clay | | |
| 122 | 164 | coarse sand | | |
| 164 | 190 | red coarse sand | | |
| 190 | 205 | brown coarse sand & clay | | |
| 205 | 208 | clay | | |
| 208 | 286 | coarse sand | | |
| 286 | 294 | clay | | |
| 294 | 307 | coarse sand, little red clay | | |
| 307 | 317 | clay | | |
| 317 | 372 | coarse sand | | |
| 372 | 437 | sand | | |
| 437 | 470 | coarse sand | | |
| 470 | 480 | coarse sand, little clay | | |
| 480 | 523 | sand | | |
| 523 | 538 | coarse sand, little clay | | |
| 538 | 540 | clay | | |
| 540 | 566 | coarse sand, little clay | | |
| 566 | 588 | coarse sand, very little clay | | |
| 588 | 605 | coarse sand, very little clay | | |
| | | | | |

(If More Space Is Required, Use Additional Sheet)

THIS WELL WAS DRILLED ACCORDING TO THE RULES FOR SAFE DRINKING WATER
 (CHAPTER 391-3-5) OF THE GEORGIA DEPARTMENT OF NATURAL RESOURCES AND
 THE INFORMATION ON THIS FORM IS TRUE AND CORRECT TO THE BEST OF MY
 KNOWLEDGE

SIGNED _____
 WATER WELL CONTRACTOR'S SIGNATURE
 DATE 6/9/81

LIC. NO.: 72

FORM COMPLETED
URN TO:

2A

GEORGIA DEPARTMENT OF NATURAL RESOURCES
ENVIRONMENTAL PROTECTION DIVISION
WATER SUPPLY SECTION
270 WASHINGTON STREET, S.W.
ATLANTA, GEORGIA 30334

WELL DATA SHEET FOR PUBLIC WATER SYSTEM
(TO BE COMPLETED BY WATER WELL CONTRACTOR)

EPD Project No.
79-E-WS-14

NAME OF WATER SYSTEM: City of Warner Robins, Georgia COUNTY: Houston
LOCATED AT: Warner Robins TYPE WATER SYSTEM: COMMUNITY NON-COMMUNITY
OWNER: City of Warner Robins DRILLER: Layne Atlantic Company
ADDRESS: ADDRESS: Post Office Box 669, Albany, Georgia
PHONE: 912/435-8338 LIC. NO.: 14

"City Well No. 2-A - South Pleasant at City Maintenance Yard"

WELL DESCRIPTION

DATE DRILLED: May 7, 1979

STATIC WATER LEVEL: 132 FT.

TOTAL DEPTH: 580 FT.

PUMPING WATER LEVEL: 235 FT. AT 1,613 GPM

TYPE DRILLING (INDICATE):

ROTARY PERCUSSION OTHER

HOLE DIAMETER

SIZE: .32 IN. FROM 0 FT. TO 125 FT.

TEST PUMP DATA

SIZE: .25 IN. FROM 125 FT. TO 510 FT.

DATE TESTED: June 13, 1979

SIZE: .25 IN. FROM 0 FT. TO FT.

PUMPED BAILED ESTIMATED

USE ADDITIONAL SHEETS IF NECESSARY

PUMP RATED: 1613 GPM 150 HP

ASING RECORD

TOTAL CONTINUOUS HRS. TESTED: 24

TYPE MATERIAL: Black Steel pipe

DID WATER LEVEL STABILIZE: YES NO

WALL THICKNESS: 0.375 Sch. 40

HRS. RUN BEFORE STABILIZATION 10

WEIGHT/FOOT: Schedule 40 P.E.

YIELD 1,613 GPM AFTER 24 HRS. OF CONTINUOUS
PUMPING

SIZE: .26 IN. FROM 0 FT. TO 125 FT.

DISCHARGE PRESSURE: 0 PSI

SIZE: .16 IN. FROM 0 FT. TO 250 FT.

WATER LEVEL BEFORE TEST: 132 FT.

SIZE: .12 IN. FROM 250 FT. TO 510 FT.

TOTAL DRAWDOWN: 103 FT.
(ATTACH COPY OF DRAWDOWN MEASUREMENTS)

USE ADDITIONAL SHEETS IF NECESSARY

SPECIFIC CAPACITY: 15.66 GPM/FT.

WELL SCREEN

NO. MINUTES FOR WELL TO RECOVER: 2-hrs

TYPE MATERIAL: Stainless Steel Type 304

WAS WELL DEVELOPED AND DISINFECTED: YES NO

SIZE: .12 IN. FROM 274 FT. TO 284 FT.

WERE UNTREATED WATER SAMPLES COLLECTED

SIZE: .12 IN. FROM 300 FT. TO 310 FT.

FOR BACTI: YES NO

SIZE: .12 IN. FROM 400 FT. TO 440 FT.

FOR CHEMICAL: YES NO

SIZE: .12 IN. FROM 478 FT. TO 488 FT.

PERMANENT PUMP DATA (BY CONTRACTOR OR
OWNER)

SIZE: .12 IN. FROM 495 FT. TO 500 FT.

PUMP TYPE: Layne OUTLET SIZE 8 IN.

WAS SLOT SIZE DETERMINED BY SIEVE ANALYSIS:
YES NO

POWERED BY: 40 HP

ROUTING

RATE: 600+ GPM

TYPE GROUT: Cement

TOTAL DYNAMIC HEAD: 202 FT.

APPLIED BY PRESSURE YES NO

PUMP SET AT: 160 FT.

FROM 0 FT. TO 125 FT.

PUMP DISINFECTED: YES NO

FROM 0 FT. TO FT.

DEEP WELL AIR LINE, TYPE MATERIAL: 4" Galv.

WELL LOG

2A

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|-----------|---------|--------------------------------------|---------|------------------------------|
| 0 | 15 | Red Clay | | |
| 15 | 45 | Red Clay & White Clay | | |
| 45 | 60 | White Clay & fine sand | | |
| 60 | .75 | Coarse white sand & clay | | |
| 75 | 94 | Coarse white sand & little clay | | |
| 94 | 109 | Coarse sand | | |
| 109 | 123 | White & red clay - slow | | |
| 123 | 168 | Coarse white sand | | |
| 168 | 228 | White coarse sand | | |
| 228 | 241 | Coarse sand with little clay streaks | | |
| 241 | 256 | Coarse sand and little white clay | | |
| 256 | 270 | Fine pepper sand - slow | | |
| 270 | 285 | Fine sand and red clay | | |
| 285 | 300 | Fine sand & little clay streaks | | |
| 300 | 315 | Coarse sand with little clay streaks | | |
| 315 | 328 | Sand with little clay streaks | | |
| 328 | 343 | Coarse sand & clay streaks | | |
| 343 | 359 | Sand - little clay streaks - slow | | |
| 359 | 372 | Sand with little clay streaks | | |
| 372 | 386 | Coarse sand with little clay streaks | | |
| 386 | 400 | White sand little clay streaks | | |
| 400 | 415 | Sand little white clay | | |

(If More Space is Required, Use Additional Sheet)

THIS WELL WAS DRILLED ACCORDING TO THE RULES FOR SAFE DRINKING WATER
 (CHAPTER 301-3.5) OF THE GEORGIA DEPARTMENT OF NATURAL RESOURCES AND
 THE INFORMATION ON THIS FORM IS TRUE AND CORRECT TO THE BEST OF MY
 KNOWLEDGE.

SIGNED *John Lott* Dated May 2 LIC. NO. 14
 WATER WELL CONTRACTOR'S SIGNATURE
 DATE *5/20/02*

LAYNE ATLANTIC COMPANY
 P. O. BOX 669
 ALBANY, GEORGIA 31702

WELL LOG

24

If More Space is Required, Use Additional Sheet(s)

THIS WELL WAS DRILLED ACCORDING TO THE RULES FOR SAFE DRINKING WATER
(CHAPTER 391-3-51) OF THE GEORGIA DEPARTMENT OF NATURAL RESOURCES AND
THE INFORMATION ON THIS FORM IS TRUE AND CORRECT TO THE BEST OF MY
KNOWLEDGE.

SIGNED: John J. Hart Dist. 122, Inc. LIC NO: 14
WATER WELL CONTRACTOR'S SIGNATURE

DATE 3/26/55

LAYNE ATLANTIC COMPANY
P. O. BOX 669
ALBANY, GEORGIA 31702

DEPARTMENT OF NATURAL RESOURCES
STATE OF GEORGIA
APPLICATION FOR A PERMIT TO USE GROUNDWATER
PART B - WELL DATA

Submit one (1) Form for Each Well

(Print or Type all Information)

APPLICANT CITY OF WARNER ROBINS

WELL NO. 3 (Key to Attached Location Map) Ground Elevation _____ ft.
Latitude 32°36'43" N Longitude 83°36'46" W (if available)

WELL CONSTRUCTION DESCRIPTION EXISTING PROPOSED

Name of Aquifer(s) being or to be Utilized Tuscaloosa Group

TYPE DRILLING (Indicate)

Rotary

Percussion Total Depth 415 ft.
 Bored Static Water
Level 105 Ft.

Date Drilled March 1961

Date to be Drilled

Driller Layne-Atlantic Co.

DRILL HOLE DIAMETER

From 0 ft., to 97 ft., 26 in.
From 0 ft., to 415 ft., 25 in.
From ft., to ft., in.
From ft., to ft., in.
From ft., to ft., in.

GROUTING: Yes No

Type Pressure (cement)

From 97 ft., to 0 ft.

From ft., to ft.

From ft., to ft.

CASING RECORD

Type Material Steel
Wall Thickness 0.312, 0.375, 0.365 in.
Weight/Foot 65.71, 49.56, 40.48 lb.
Size 20 in. from 0 ft., to 97 ft.
Size 12 in. from 0 ft., to 200 ft.
Size 10 in. from 200 ft., to 415 ft.
Size in. from ft., to ft.
Size in. from ft., to ft.

TEST PUMP DATA

Pumped Test Bailed

Estimated Actual Test

Date Tested Feb. 24, 1961

Pump Rated 1000/1500 GPM 75 HP

Test Yield GPM After 5 & 5

hrs. of pumping

Water Level before Test 105 ft.

Drawdown 33/53 ft.

Specific Capacity 30.3 / 28.3 GPM/ft.

PERMANENT PUMP DATA (if available)

Pump Type Deep Well Turbine

Outlet Size 8"

Powered by Electric Motor

Horsepower 75

Rate 1000 GPM

Pumping Level 138/158 Ft.

Average Hours Pumped Per Day

NOTE: Detailed well construction specifications of a proposed well may be required by the Division upon review of the submitted application.

Complete WELL LOG on reverse side, if available.

| TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|------------|------------------------------------|---------|---------------------------------|
| 1 | Top Soil | | |
| 5 | Yellow Sandy Clay | | |
| 14 | Red Clay | | |
| 22 | Med. Coarse Sand | | |
| 32 | White Clay W/Sand - Slow | | |
| 49 | White Clay - Slow | | |
| 58 | Coarse Sand - Thin Stks White Clay | | |
| 72 | Coarse Sand | | |
| 96 | Clay W/Stks Sand | | |
| 102 | Clay - Slow | | |
| 108 | Clay W/ Stks Sand | | |
| 114 | Clay - Slow | | |
| 146 | Coarse White Sand - Soft | | |
| 149 | Clay | | |
| 158 | Coarse White Sand - Soft | | |
| 161 | Yellow Clay | | |
| 194 | Coarse Sand W/Thin Stks of Clay | | |
| 198 | Yellow Clay - Slow Drilling | | |
| 218 | Med. Coarse Sand - Soft | | |
| 220 | Streaks of Clay | | |
| 238 | Med. Coarse Sand - Soft | | |
| 240 | Streaks of Clay | | |

(If More Space Is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____
 Date _____

No. 3

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ **Title** _____

Date _____

DEPARTMENT OF NATURAL RESOURCES
STATE OF GEORGIA
APPLICATION FOR A PERMIT TO USE GROUNDWATER
PART B - WELL DATA

Submit one (1) Form for Each Well (Print or Type all Information)

APPLICANT CITY OF WARNER ROBINS

WELL NO. 4 (Key to Attached Location Map) Ground Elevation _____ ft.
 Latitude 32°36'29"N Longitude 83°36'55"W (if available)

WELL CONSTRUCTION DESCRIPTION EXISTING PROPOSED

Name of Aquifer(s) being or to be Utilized Tuscaloosa Group

TYPE DRILLING (Indicate)

Rotary

Percussion Total Depth 390 ft.
 Boxed Static Water
 Level 122 Ft.

Date Drilled February 1960

Date to be Drilled

Driller Layne-Atlantic Co.

GROUTING: Yes No
 Type Pressure (Cement)

From 60 ft., to 0 ft.

From ft., to ft.

From ft., to ft.

TEST PUMP DATA

Pumped Test Bailed

Estimated Actual Test

Date Tested Feb 20 1960

Pump Rated 1500 GPM 100 HP

Test Yield 1559 GPM After 12 hrs. of pumping

Water Level before Test 122 ft.

Drawdown 60 ft.

Specific Capacity 25 GPM/ft.

PERMANENT PUMP DATA (if available)

Pump Type Deep Well Turbine

Outlet Size 10 In.

Powered by Electric Motor

Horsepower 100

Rate 1500 GPM

Pumping Level 182 Ft.

Averag. Hours Pumped Per Day

NOTE: Detailed well construction specifications of a proposed well may be required by the Division upon review of the submitted application.

Complete WELL LOG on reverse side, if available.

WELL LOG

4

| FROM FT | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|------------|------------|--|---------|---------------------------------|
| 0 | 3 | Fill Dirt | | |
| 3 | 23 | Sandy Red Clay | | |
| 23 | 42 | Sand w/stks of Clay | | |
| 42 | 47 | Clay - Slow | | |
| 47 | 56 | Sand - Soft | | |
| 56 | 73 | Clay - Slow | | |
| 73 | 97 | Coarse Sand - Soft | | |
| 97 | 106 | Clay - Medium | | |
| 106 | 124 | Clay w/stks of Sand - Soft | | |
| 124 | 154 | Coarse White Sand - Soft | | |
| 154 | 178 | Coarse White Sand w/thin stks of Clay - Soft | | |
| 178 | 201 | Coarse Reddish Sand - Soft | | |
| 201 | 211 | Clay - Medium Drilling | | |
| 211 | 232 | Coarse Reddish Sand - Soft | | |
| 232 | 236 | Clay - Soft | | |
| 236 | 261 | Medium Coarse Reddish Sand - Soft | | |
| 261 | 264 | Clay - Medium | | |
| 264 | 275 | Med. Coarse Sand - Soft - Cut Rough | | |
| 275 | 292 | Med. Coarse Sand - Soft | | |
| 292 | 301 | Clay - Slow Drilling | | |
| 301 | 316 | Med. Coarse Sand - Soft | | |
| 316 | 318 | Clay - Med. Drilling | | |

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____

Date _____

No. 4

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Name _____ Title _____
Date _____

ENVIRONMENTAL PROTECTION DIVISION
DEPARTMENT OF NATURAL RESOURCES
STATE OF GEORGIA
APPLICATION FOR A PERMIT TO USE GROUNDWATER
PART B - WELL DATA

116

Submit one (1) Form for Each Well (Print or Type all Information)

APPLICANT CITY OF WARNER ROBINS

WELL NO. 5 (Key to Attached Location Map) Ground Elevation 431 ft.
Latitude 32° 35' 44"N Longitude 83° 38' 42"W (if available)

WELL CONSTRUCTION DESCRIPTION EXISTING PROPOSED

Name of Aquifer(s) being or to be Utilized Tuscaloosa Group

TYPE DRILLING (Indicate)

Rotary

Percussion Total Depth 422 ft.
 Bored Static Water
Level 132 Ft.

DRILL HOLE DIAMETER

From 0 ft., to 94 ft., 26 in.
From 0 ft., to 422 ft., 25 in.
From ft., to ft., in.
From ft., to ft., in.
From ft., to ft., in.

CASING RECORD

Type Material Steel
Wall Thickness 0.312, 0.375 In.
Weight/Foot 65.71, 49.56 Lb.
Size 20 in. from 0 ft., to 94 ft.
Size 12 in. from 0 ft., to 422 ft.
Size in. from ft., to ft.
Size in. from ft., to ft.
Size in. from ft., to ft.

WELL SCREEN

Type Material Stainless Steel
Size 12 in. from 235 ft., to 245 ft.
Size 12 in. from 270 ft., to 280 ft.
Size 12 in. from 349 ft., to 354 ft.
Size 12 in. from 366 ft., to 371 ft.
Size 12 in. from 392 ft., to 412 ft.

Date Drilled November 1962

Date to be Drilled

Driller Layne-Atlantic Co.

GROUTING: Yes No

Type Pressure (Cement)

From 94 ft., to 0 ft.

From ft., to ft.

From ft., to ft.

TEST PUMP DATA

Pumped Test Bailed

Estimated Actual Test

Date Tested November 27, 1962

Pump Rated 1100 GPM 75 HP

Test Yield GPM After 24 hrs. of pumping

Water Level before Test 132 ft.

Drawdown 24 ft.

Specific Capacity 45.8 GPM/ft.

PERMANENT PUMP DATA (if available)

Pump Type Deep Well Turbine

Outlet Size 8"

Powered by Electric Motor

Horsepower 75

Rate 1000 GPM

Pumping Level 156 Ft.

Average Hours Pumped Per Day

NOTE: Detailed well construction specifications of a proposed well may be required by the Division upon review of the submitted application.

Complete WELL LOC on reverse side, if available.

WELL LOG

5

| DEPT. FT. | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|--------------|------------|-------------------------------------|---------|---------------------------------|
| 0 | 1 | Top Soil | | |
| 1 | 10 | Red Clay | | |
| 10 | 20 | Red Sandy Clay | | |
| 20 | 30 | Dark Red Clay | | |
| 30 | 35 | Coarse Red Sandy Clay | | |
| 35 | 44 | Red Clay | | |
| 44 | 51 | Fine Red Sandy Clay | | |
| 51 | 59 | Fine Sand w/Stks of White Clay | | |
| 59 | 74 | Fine Sand w/Heavy Stks of Clay | | |
| 74 | 84 | Med Coarse Sand | | |
| 84 | 94 | Pink & White Clay (Med. - Slow) | | |
| 9 | 105 | Red Clay (Med.-Slow) | | |
| 105 | 139 | White Clay | | |
| 139 | 148 | Sand | | |
| 148 | 155 | Coarse Sand w/White Clay | | |
| 155 | 185 | Coarse Sand w/Stks of Clay | | |
| 185 | 216 | Coarse Sand w/Stks of White Clay | | |
| 216 | 258 | Med. Coarse Sand w/Very Little Clay | | |
| 258 | 298 | Coarse Sand w/Iron Granules | | |
| 298 | 308 | White Clay - Slow | | |
| 308 | 321 | Red & White Clay - Slow | | |
| 321 | 332 | White Clay - Slow | | |

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____
 Date _____

1104

WELL LOG

5

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____
Date _____

ENVIRONMENTAL PROTECTION DIVISION
DEPARTMENT OF NATURAL RESOURCES
STATE OF GEORGIA
APPLICATION FOR A PERMIT TO USE GROUNDWATER
PART B - WELL DATA

No. 6

Submit one (1) Form for Each Well

(Print or Type all Information)

APPLICANT CITY OF WARNER ROBINS

WELL NO. 6 (Key to Attached Location Map) Ground Elevation 393 + ft.
Latitude 32°37'58"N Longitude 83°37'42"W (if available)

WELL CONSTRUCTION DESCRIPTION EXISTING PROPOSED

Name of Aquifer(s) being or to be Utilized Tuscaloosa Group

TYPE DRILLING (Indicate)

Rotary

Percussion Total Depth 435 ft.

Bored

Static Water

Level 116 Ft.

Date Drilled July 1968

Date to be Drilled

Driller Layne-Atlantic

GROUTING: Yes No

Type Pressure (Cement)

From 70 ft., to 0 ft.

From ft., to ft.

From ft., to ft.

TEST PUMP DATA

Pumped Test Bailed

Estimated 1050 GPM

Date Tested July 16, 1968

Pump Rated 1040 GPM 100 HP

Test Yield GPM After 24

hrs. of pumping

Water Level before Test 116 ft.

Drawdown 15 ft.

Specific Capacity 69.3 GPM/ft.

PERMANENT PUMP DATA (if available)

Pump Type Deep Well Turbine

Outlet Size 8"

Powered by Electric Motor

Horsepower 100

Rate 1100 GPM

Pumping Level 131 Ft.

Average Hours Pumped Per Day

NOTE: Detailed well construction specifications of a proposed well may be required by the Division upon review of the submitted application.

Complete WELL LOG on reverse side, if available.

WELL LOG

6

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|-----------|---------|--|---------|------------------------------|
| 0 | 1 | Top Soil | | |
| 1 | 18 | Sand Clay | | |
| 18 | 32 | White Clay | | |
| 32 | 47 | White Clay & Sand | | |
| 47 | 64 | Red Clay W/Little Sand | | |
| 64 | 74 | Clay | | |
| 74 | 122 | Coarse Sand | | |
| 122 | 130 | Clay - White | | |
| 130 | 155 | Coarse Sand W/ Stks Clay | | |
| 155 | 180 | Med. Coarse Sand | | |
| 180 | 185 | White Clay | | |
| 185 | 215 | Med. Coarse Sand | | |
| 215 | 224 | Clay | | |
| 224 | 281 | Med. Coarse Sand | | |
| 281 | 296 | Sand & Clay | | |
| 296 | 341 | Med. Coarse Sand W/Little Stks of White Clay | | |
| 341 | 357 | Med. Coarse Sand W/Some White Clay | | |
| 357 | 369 | Coarse Sand | | |
| 369 | 385 | Med. Coarse Sand | | |
| 385 | 393 | Sand W/Lots of Clay - Clay Washes Out | | |
| 393 | 435 | Coarse Sand - Little Clay | | |
| 435 | 464 | Coarse Sand W/ Stks of White Clay | | |

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____
 Date _____

Georgia Department of Public Health
Water Supply Service
47 Trinity Avenue, S. W.
Atlanta, Georgia 30334

| | |
|--------------|--|
| DO NOT WRITE | |
| CLASS II | |
| CLASS III | |
| INDIVIDUAL | |

WELL DATA SHEET

For

PUBLIC OR COMMUNITY WATER SUPPLY SYSTEMS OR INDIVIDUAL WATER SUPPLY

INSTRUCTIONS:

Well No. 7 (Water Plant No. 3)

Name of Water System: Warner Robins, Georgia Location Arizona Street County Houston
 Type: Municipal Subdivision _____ No of Lots _____ Mobile Homes _____ or Trailer Parks _____
 No of Lots _____ Industrial _____ Commercial _____ Individual _____ Other _____
 Owner City of Warner Robins Driller Singer-Leyne Atlantic Company
 Address _____ Address Albany, Georgia
 Date Drilling Started January 1972 Date Completed February 1972

WELL DESCRIPTION

TYPE DRILLING (Check)

Rotary
 Percussion _____
 Bored _____
 Total depth of Well 410 Ft
 Depth to water (SWL) 105 Ft

GROUTING

Type Grout Cement
 Applied by pressure Z Other _____
 From C Ft To 140 Ft
 From _____ Ft To _____ Ft
 From _____ Ft To _____ Ft

HOLE DIAMETER:

From 0 Ft To 140 Ft 32 in.
 From 0 Ft To 140 Ft 25 in.
 From _____ Ft To _____ Ft _____ in.
 From _____ Ft To _____ Ft _____ in.
 From _____ Ft To _____ Ft _____ in.

TEST PUMP DATA:

Pumped Test Bailed _____
 Estimated Actual Test
 Date Test February 8, 1972
 Pump rated 1641 GPM HP Test Engine
 Yield 1641 GPM after 24 hrs
 of stabilization
 Water Level before Test 105 Ft
 Drawdown 42 Ft
 Specific Capacity 39.0 GPM per ft

CASING RECORD:

Type Material Steel
 Size .6 in. From 0 Ft To 240 Ft
 Size 16 in. From 0 Ft To 200 Ft
 Size 22 in. From 0 Ft To 240 Ft
 Size 22 in. From _____ Ft To _____ Ft
 Size 22 in. From _____ Ft To _____ Ft
.12" x .16" steel sleeve

Well developed and Disinfecting:

Yes No

PERMANENT PUMP DATA (If Available)

Pump Type Singer-Leyne & Bowler
 Outer size 8"
 Powered by 150 Electric Motor
 Horse power 150
 Rate 1500 GPM
 Pumping Level 144
 Pump Disinfecting 1 Yes No

FOR WELL LOG, USE REVERSE SIDE

| Total Thickness each in feet | TO FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|---------------------------------------|------------|--|---------|---------------------------------|
| 1 | 1 | Top Soil | | |
| 18 | 17 | Sand Clay | | |
| 32 | 17 | White Clay | | |
| 47 | 15 | White Clay & Sand | | |
| 64 | 17 | Red Clay w/Little Sand | | |
| 74 | 10 | Clay | | |
| 122 | 48 | Coarse sand | | |
| 130 | 8 | Clay - white | | |
| 135 | 24 | Coarse sand w/Some Clay | | |
| 180 | 30 | Med. Coarse Sand | | |
| 186 | 5 | White Clay | | |
| 215 | 30 | Med. Coarse Sand | | |
| 224 | 9 | Clay | | |
| 281 | 57 | Med. Coarse Sand | | |
| 286 | 15 | Sand & Clay | | |
| 341 | 45 | Med. Coarse Sand w/Little atka. of white clay | | |
| 357 | 16 | Med. Coarse Sand w/Some White Clay | | |
| 362 | 39 | Coarse Sand | | |
| 385 | 16 | Med. Coarse Sand | | |
| 393 | 8 | Sand w/lots of Clay. Clay washes out | | |
| 435 | 42 | Coarse Sand Little Clay | | |
| 464 | 29 | Coarse Sand w/Stems of White Clay | | |
| 488 | 24 | Med. Sand w/Little Clay | | |
| 495 | 7 | Med. Sand w/Little Clay | | |
| 520 | 8 | Red Clay w/Little Sand | | |
| | | | | |
| | | | | |

(// More Space is Required, Use Additional Sheet)

This well was drilled according to the Rules and Regulations of the Georgia Department of Public Health
and the above information is true and correct to the best of my knowledge.

Signed _____ Title _____
 Date John W. Flatt District Manager
June 15, 1972

NO 8

ENVIRONMENTAL PROTECTION DIVISION
DEPARTMENT OF NATURAL RESOURCES
STATE OF GEORGIA
APPLICATION FOR A PERMIT TO USE GROUNDWATER
PART B - WELL DATA

Submit one (1) Form for Each Well (Print or Type all Information)

APPLICANT CITY OF WARNER ROBINS

WELL NO. 8 (Key to Attached Location Map) Ground Elevation 396 + ft.
Latitude 32° 35' 44" N Longitude 83° 38' 57" W (if available)

WELL CONSTRUCTION DESCRIPTION EXISTING PROPOSED

Name of Aquifer(s) being or to be Utilized Tuscaloosa Group

TYPE DRILLING (Indicate) Rotary

Percussion Total Depth 430 ft.

Bored Static Water

Level 101 Ft.

Date Drilled August 1970

Date to be Drilled

Driller Singer-Layne-Atlantic Co.

GROUTING: Yes No

Type Pressure (Cement)

From 100 ft., to 0 ft.

From ft., to ft.

From ft., to ft.

TEST PUMP DATA

Pumped Test Bailed

Estimated 1500 GPM

Date Tested August 13/ 1970

Pump Rated 1641 GPM 150 HP

Test Yield 1641 GPM After 24

hrs. of pumping

Water Level before Test 101 ft.

Drawdown 27 ft.

Specific Capacity 60.8 GPM/ft.

PERMANENT PUMP DATA (if available)

Pump Type Deep Well Turbine

Outlet Size 8 in.

Powered by Electric Motor

Horsepower 150

Rate 1500 GPM

Pumping Level 128 Ft.

Average Hours Pumped Per Day

NOTE: Detailed well construction specifications of a proposed well may be required by the Division upon review of the submitted application.

Complete WELL LOG on reverse side, if available.

WELL LOG

8

(If More Space is Required, Use Additional Sheet)

The above information is true and correct to the best of my knowledge.

Signed _____ Title _____
Date _____

Georgia Department of Public Health
 Water Supply Service
 47 Trinity Avenue, S.W.
 Atlanta, Georgia 30334

| |
|--------------|
| DO NOT WRITE |
| CLASS II |
| CLASS III |
| INDIVIDUAL |

WELL DATA SHEET
 For
 PUBLIC OR COMMUNITY WATER SUPPLY SYSTEMS OR INDIVIDUAL WATER SUPPLY

Well No. 9 (Water Plant No. 2)

INSTRUCTIONS:

Name of Water System: Warner Robins Location Arrowhead Trail County Houston
 Type: Municipal Subdivision _____ No of Lots _____ Mobile Homes _____ or Trailer Parks _____
 No of Lots _____ Industrial _____ Commercial _____ Individual _____ Other _____
 Owner City of Warner Robins Driller Singer-Laynes Atlantic Company
 Address _____ Address Albany, Georgia
 Date Drilling Started September 1971 Date Completed October 1971

WELL DESCRIPTION

TYPE DRILLING (Check) GROUTING

Rotary
 Percussion _____
 Bored _____
 Total depth of Well 490 Ft.
 Depth to water (SWL) 101 Ft.

Type Grout Cement
 Applied by pressure Other _____
 From 0 Ft. To 110 Ft.
 From _____ Ft. To _____ Ft.
 From _____ Ft. To _____ Ft.

HOLE DIAMETER:

From 0 Ft. To 110 Ft. .32 In.
 From 0 Ft. To 490 Ft. .25 In.
 From _____ Ft. To _____ Ft. _____ In.
 From _____ Ft. To _____ Ft. _____ In.
 From _____ Ft. To _____ Ft. _____ In.

TEST PUMP DATA:

Pumped Test Settled _____
 Estimated Actual Test _____
 Date Tested October 5, 1971
 Pump rated 1613 GPM HP Test Engin
 Yield 1613 GPM after _____ hr.
 of stabilization
 Water Level before Test 101 Ft.
 Drawdown .22-.32 Ft.
 Specific Capacity .52 GPM per ft.

CASING RECORD:

Type Material Steel
 Size 26 in. From 0 Ft. To 110 Ft.
 Size 16 in. From 0 Ft. To 250 Ft.
 * Size 12 in. From 250 Ft. To 490 Ft.
 Size _____ in. From _____ Ft. To _____ Ft.
 Size _____ in. From _____ Ft. To _____ Ft.

*Steel Sump 12"x16"

Well developed and Disinfected:
 Yes No

PERMANENT PUMP DATA (If Available)

| | |
|------------------|---|
| Pump Type | <u>Singer-Laynes & Bowler</u> |
| Outlet Size | <u>.8"</u> |
| Powered by | <u>Electric Motor</u> |
| Horse power | <u>150</u> |
| Rate | <u>1500</u> GPM |
| Pumping Level | <u>130'</u> |
| Pump Disinfected | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |

WELL SCREEN:

Type Material Layne Stainless Steel Shutter
 Size 12 in. From 330 Ft. To 340 Ft.
 Size 12 in. From 360 Ft. To 380 Ft.
 Size 12 in. From 405 Ft. To 415 Ft.
 Size 12 in. From 460 Ft. To 480 Ft.
 Size _____ in. From _____ Ft. To _____ Ft.

FOR WELL LOG, USE REVERSE SIDE

EW 4-80

Thickness
each
Stratum

WELL LOG

1

| STATION | DEPTH FEET | TYPE MATERIAL ENCOUNTERED | REMARKS | INDICATE WATER BEARING ZONES |
|---------|---------------|---------------------------------------|---------|------------------------------|
| 7 | 7 | Sand | | |
| 20 | 13 | Sand & White Clay | | |
| 36 | 16 | Sand W/Little Stks. of White Clay | | |
| 50 | 14 | Coarse Sand & White Clay-Slow | | |
| 80 | 30 | Coarse Sand | | |
| 127 | 47 | Coarse Sand W/Stks. of White Clay | | |
| 189 | 62 | Med. Coarse Sand | | |
| 221 | 32 | Med. Coarse Sand W/Stks of Clay | | |
| 231 | 10 | Med. Coarse Sand-Soft | | |
| 253 | 22 | Med. Coarse Sand & Stks. of Clay-Soft | | |
| 270 | 23 | Med. Sand & Red Clay-Slow | | |
| 295 | 25 | Sand & Red Clay-Very Slow | | |
| 314 | 19 | Coarse Sand-Very Slow | | |
| 314 | 30 | Med. Coarse Sand-Soft | | |
| 366 | 42 | Med. Coarse Sand W/Little Clay-Soft | | |
| 396 | 10 | Red Sand Clay-Slow | | |
| 437 | 21 | Med. Coarse Sand-Soft | | |
| 437 | 20 | Coarse Sand Wome Clay-Slow | | |
| 450 | 13 | Sand Clay-Slow | | |
| 467 | 17 | Med. Coarse Sand-Soft | | |
| 497 | 30 | Med. Coarse Sand W/Little Clay-Soft | | |
| 528 | 31 | Sand W/Little Clay-Soft. | | |

(If More Space is Required, Use Additional Sheet)


This well was drilled according to the Rules and Regulations of the Georgia Department of Public Health and the above information is true and correct to the best of my knowledge.

Signed John W. Flatt Title District Manager
Date June 15, 1972

No. 10

ALL MEASUREMENTS TAKEN FROM GROUND (TOP OF FOUNDATION) (TOP OF CASING) (TOP BASE PLATE)

DRAWING OF THE WELL



STARTED WELL 10 COMPLETED 10
 TOTAL DEPTH 480 ELEVATION 10 STATIC WATER LEVEL
 LENGTH SURFACE CASING 121 SIZE 26 THICKNESS
 CEMENTED WITH BACKUP CEMENT TYPE PACKER
 LENGTH WELL CASING 121 SIZE 26 WEIGHT SCH 40
 CEMENTED WITH WELL CEMENT SIZE 26 WEIGHT SCH 40
 INNER CASING 16x12 SIZE 195x285 WEIGHT SCH 40
 WITH AS SHOWN
 RIG SEAL NO GUIDE
 WELL STRAINER Layne SIZE 12 LENGTH 75 OPENING 7/8"
 TYPE MATERIAL S.S. CONNECTIONS
 SIZE HOLE DRILLED FOR SURFACE CASING 32 WITH Tri-Cone
 SIZE HOLE DRILLED FOR WELL CASING 26 WITH Tri-Cone
 WELL HOLE DRAINED NO SIZE 26 WITH Tri-Cone
 VARUS OF GRAVEL PACK NO PLACED
 HOW WAS WELL SET NO
 NOTES
 RIG USED Gardner Denver DRILLER Sylvester Yawn
 SERIAL NUMBER MAKER FOUNDATION 10
 LENGTH COLUMN SIZE TYPE 20 LENGTHS
 BOWL SIZE TYPE STAGES MATERIAL IMPELLER
 MATERIAL BOWL WITH PORTS AND SHAFT
 SUCTION SIZE WITH LENGTH SUCTION STRAINER
 IS PUMP SEALED HOW WHERE WITH WHAT
 LUBRICATOR TYPE SIZE VOLTAGE
 LENGTH OF AIRLINE SIZE TYPE MATERIAL
 AIR RELEASE VALVE TYPE SIZE
 SIZE SURFACE DISCHARGE TYPE DAYTON COUPLING
 PRESSURE GAUGE SIZE SPEED
 NOTES
 RIG USED TO SET PUMP INSTALLED
 DATE PUMP INSTALLED 10 DATE IN OPERATION 10
 MAKE HP NAME PHASE CYCLE VOLT 220/440
 SPEED MODEL SERIAL NUMBER
 TOP BEARING TYPE BEARING RATCHET
 STARTER PRESSURE SWITCH FLOAT
 MAKE MODEL SIZE RATIO NO
 SIZE PULLEY TYPE MOTOR FRAME
 MAKE MODEL HP SERIAL NUMBER
 SPEED SIZE MM/EV FOUNDATION
 TYPE FUEL TANK MAKE MAG NO
 MAKE STARTER TYPE FUEL
 MAKE FLEXIBLE SHAFT SIZE LENGTH BELT LENGTH
 PURPOSE FOR WHICH THIS WATER IS USED
 TEMPERATURE IS WATER CLEAR CAPACITY
 HARDNESS HARDNESS PH IRON NaCl
 TYPE TREATMENT USED
 IS THERE A DERRICK OVER THE WELL HEIGHT TYPE
 CAN TRUCK ON YES/NO YARD TO WELL
 PUMP HEAD SIZE HATCH
 CONTRACT NO. AL-0150

OUR WELL NO. 10 IN WELL NO. 10 IN TEST HOLE NO. 10

LOCATION OF THE WELL Tabor Drive

INSTALLED ON CITY OF Warner Robins

COUNTY Elbert STATE Georgia

Contractor: Arthur Pew Construction Co. YEAR 1976
 Engineer: Flood & Associates

WELL NO. 10
CITY OF WARNER ROBINS
CONTRACT NO. AL-0150
FORMATION LOG OF THE WELL OR TEST HOLE

STARTED TEST HOLE Dec. 13 1976 FINISHED Dec. 14 1976 TEST HOLE NUMBER _____
LOCATION City of Warner Robins SEC _____ TO _____ RANGE _____ ELEVATION _____
Tabor Drive

No. 1.1

ALL MEASUREMENTS TAKEN FROM (GROUND) (TOP OF FOUNDATION) (TOP OF CASING) (TOP BASE PLATE)

| | | | |
|---|--|--|--|
| DRAWING OF THE WELL | | STARTED WELL Oct. 25, 1976 AND COMPLETED Dec. 7, 1976 TOTAL DEPTH 440 ELEVATION STATIC WATER LEVEL LENGTH SURFACE CASING SIZE THICKNESS CEMENTED WITH BACKS CEMENT TYPE PACKER LENGTH WELL CASING 180' SIZE 16 WEIGHT 111 1/2 CEMENTED WITH BACKS CEMENT TYPE PACKER INNER CASING LENGTH 16x12 SIZE 180'x260' WEIGHT 520 1/2 WITH X GUIDES LOCATED DOWN TYPE BACKOFF LEAD SEAL BACKPRESSURE VALVE GUIDE WELL STRAINER MAKE Layne SIZE 14 LENGTH 15 OPENING 2' TYPE MATERIAL S.S. WITH Welded CONNECTIONS SIZE HOLE DRILLED FOR SURFACE CASING 22 WITH Tri-Cone SIZE HOLE DRILLED FOR WELL CASING 26 WITH Tri-Cone SIZE HOLE DRILLED FOR STRAINER 26 WITH Tri-Cone YARDS OF GRAVEL USED HOW PLACED HOW WAS WELL DEVELOPED NOTES | |
| | | RIG USED Gardner Denver DRILLER Sylvester Yawn | |
| | | SERIAL NUMBER 82863 MAKE Layne FOUNDATION Concrete LENGTH COLUMN 100 SIZE 10x14x21 TYPE Oil @ 20 LENGTHS BOWL SIZE 12 TYPE PTC STAGES 6 MATERIAL IMPELLER MATERIAL BOWL C.I. WITH Open PORTS AND S.S. SHAFT SUCTION SIZE 10 LENGTH 30 SUCTION STRAINER Galy Cone IS PUMP SEALED HOW Yes WHERE Foundation WITH WHAT Concrete LUBRICATOR TYPE Oil SIZE 4 Bts. VOLTAGE 460 LENGTH OF AIRLINE 100 SIZE 1/4 TYPE MATERIAL Galy AIR RELEASE VALVE TYPE Crispen SIZE 2" SIZE SURFACE DISCHARGE 10 TYPE DAYTON COUPLING PRESSURE GAUGE 0-100 SPEED 1800 NOTES | |
| | | RIG USED TO SET PUMP Crane INSTALLER B. Castleberry DATE PUMP INSTALLED 3-2-77 DATE IN OPERATION 11-1-77 | |
| | | MOTOR MAKE GE HP 100 FRAME B44/LTP PHASE 3 CYCLE 60 VOLT. 208 SPEED 1800 MODEL 5K6277 X H2A SERIAL NUMBER M11013153 TOP BEARING BOTTOM BEARING RATCHET NBR STARTER PRESSURE SWITCH FLOAT | |
| | | GEAR MAKE Johnson MODEL CH200 SIZE 200 HP RATIO 1:1 NO. SIZE PULLEY TYPE MOTOR FRAME Combination | |
| | | ENGINE MAKE Waukesha MODEL F-1197GU HP 253 SERIAL NUMBER 365649 SPEED 1800 SIZE PULLEY FOUNDATION Concrete TYPE FUEL TANK MAKE MAG NO MAKE STARTER NO TYPE FUEL Natural Gas MAKE FLEXIBLE SHAFT SIZE LENGTH BELT LENGTH Willard Twiflex 1246-1-14.900 | |
| | | GENERAL PURPOSE FOR WHICH THIS WATER IS USED Municipal TEMPERATURE IS WATER CLEAR YES CAPACITY 1500 SAND No HARDNESS 6 PH 5.6 IRON 0.01 NaCl TYPE TREATMENT USED | |
| | | IS THERE A DERRICK OVER THE WELL No HEIGHT TYPE CAN TRUCK OR RIG EASILY GET TO WELL No In House PUMP HOUSE YES SIZE HATCH 4'x4' | |
| CONTRACT NO. AI-0150 | | | |
| OUR WELL NO. 11 THEIR WELL NO. 11 IN TEST HOLE NO. | | | |
| LOCATION OF THE WELL Taber Street | | | |
| INSTALLED FOR City of Warner Robins | | | |
| ADDRESS CITY Warner Robins COUNTY Houston STATE Georgia | | | |
| Prime Contractor: Arthur Peay Construction Co. Engineer : Flood & Associates | | | |
| YEAR 1976 | | | |

No. 11

WELL NO. 11
CORPAC NO. AL-0150
FORMATION LOG OF THE WELL OR TEST HOLE

STARTED TEST HOLE 10-26 FINISHED November 3, 1976 TEST HOLE NUMBER _____
LOCATION: Elder Street, Huron, Indiana SEC. ____ TS ____ RANGE ____ ELEVATION _____

| TOTAL DEPTH | THICKNESS EACH STRATUM | FORMATION | TOTAL DEPTH | THICKNESS EACH STRATUM | FORMATION |
|-------------|------------------------|---|-------------|------------------------|-----------------------------|
| 2 | 8 | Red Sand Clay | 559 | 50 | Red Sand & Clay. Very Slow. |
| 21 | 4 | Red Clay | | | |
| 25 | 8 | Red Sand Clay | | | |
| 31 | 5 | Red & White Sandy Clay | | | |
| 36 | 5 | Yellow Sand & Clay | | | |
| 39 | 9 | Coarse Gravel. Circulation Problems. | | | |
| 48 | 11 | Coarse Sand & Little White Clay | | | |
| 55 | 27 | Coarse Sand & Stks. of White Clay. Soft. | | | |
| 106 | 41 | Sand & White Clay. Soft. | | | |
| 155 | 29 | Med. Coarse Sand & White Clay. Soft. | | | |
| 182 | 28 | Coarse Sand with Stks. of White Clay. Soft. | | | |
| 198 | 15 | Med. Coarse Sand with Little White Clay. Soft. | | | |
| 226 | 22 | Coarse Sand with Stks. of White Clay. Soft. | | | |
| 244 | 5 | White Clay (No Sample) Slow. | | | |
| 276 | 15 | Coarse Sand & Little White Clay. Soft. | | | |
| 314 | 15 | Med. Coarse Sand. Little Clay. Medium Drilling. | | | |
| 331 | 12 | Red & White Clay. Very Slow. | | | |
| 347 | 21 | Coarse Sand & Little Clay. Soft. | | | |
| 374 | 58 | Coarse Sand with Stks. of White Clay. Soft. | | | |
| 413 | 29 | Coarse Sand & little Clay. Soft. | | | |
| 441 | 11 | Sand & Little Stks. of Red Clay | | | |
| 458 | 10 | Sand & Red Clay. Slow. | | | |
| 479 | 1 | Iron Sand with Little Clay. Slow. | | | |
| 480 | 15 | Sand & Stks. of Red Clay. | | | |

MUD PIT SIZE FT. X FT. X FT. DEEP
 TYPE BIT USED TO CUT SAND
 SIZE OF TEST HOLE THROUGH SAND
 TYPE OF BIT USED TO CUT UPPER FORMATIONS SIZE
 TYPE MUD PUMP USED
 DRILLING PRESSURE IN SAND
 TYPE OF MUD USED
 NOTES:

TEST DATA

| PRELIMINARY TEST | FINAL TEST |
|-------------------------------|------------|
| STATIC WATER LEVEL 47' | |
| PUMPED G. P. M. 1613 | |
| PRESSURE. POUNDS | |
| DRAWDOWN 25 | |
| G. P. F. D. 64.52 | |
| GUARANTEED G. P. M. 1600 | |
| GUARANTEED PRESSURE | |
| DATE OF TEST December 2, 1976 | |

REMARKS

DRILLER Sylvester Yawn
 FIELD SUPT. Jess Henderson

No. 1

LAYNE ATLANTIC COMPANY

NORFOLK, VA.

E. H. Smith

LOG OF WELL For Robins Field (Georgia Air Depot)

located at Wellton in Georgia (near Macon, Ga.) County, State

Date Drilling Started September 2, 1941 Date Started August 21, 1941

Finished Drilling September 18, 1941 Finished October 26, 1941

FORMATION AND DEPTH OF WELL

DIMENSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | DIMENSIONS OF CASING AND SCREEN | | | |
|------------------------------------|-----------------------------|--|--|--|-----------------------------------|-----------------------------------|
| | | | TOTAL LENGTH OF ALL SCREENS IN CASING | LENGTH OF EACH SEC. OF SCREEN IN CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN ON CASING |
| FT. IN. | FT. IN. | Well #1 | FT. IN. | FT. IN. | IN. | GAUGE (inches) mm |
| 20 | 20 | Brown sand | 76 | 76 | Casing | 20 5/16 |
| 40 | 20 | Yellow sand | | | 12" | casing commences at 60' |
| 48 | 8 | Yellowish white sand | 60 | 60 | Casing | 12 50% |
| 70 | 22 | Coarse white sand | 70 | 20 | Screen | 12 6 |
| 76 | 6 | Very coarse sand | 190 | 120 | Casing | 12 50% |
| 86 | 10 | Coarse white sand | 210 | 20 | Screen | 12 6 |
| 96 | 9 | Coarse sand, some chalk | | | | |
| 122 | 27 | Coarse white sand and fine gravel Signs of chalk 95 to 100 1 ft. very hard streak at 109 | | | | |
| 132 | 10 | Soft coarse white sand | | | | |
| 136 | 4 | Hard chalk and gravel | | | | |
| 152 | 16 | Chalk and gravel | | | | |
| 157 | 5 | Soft coarse white sand | | | | |
| 162 | 5 | Soft chalk and coarse gravel | | | | |
| 167 | 5 | Medium hard coarse gravel - used 1/2 pit of water | | | | |
| 172 | 6 | Coarse white sand | | | | |
| 177 | 5 | Chalk and gravel | | | | |
| 182 | 25 | Soft coarse sand | | | | |
| 207 | 18 | Hard clay and gravel | | | | |
| 236 | 36 | Coarse white sand | | | | |
| 237 | 36 | Hard streak (?). No sample | | | | |
| 263 | 16 | Fine white sand | | | | |
| 270 | 17 | Coarse sand - used water | | | | |
| 274 | 4 | Very hard gravel | | | | |
| 290 | 16 | Very hard chalk | | | | |
| 315 | 26 | Coarse sand | | | | |
| 318 | 3 | Coarse sand and little clay | | | | |
| 326 | 10 | Coarse sand | | | | |
| 332 | 4 | Coarse and fine white sand with white clay | | | | |
| 337 | 6 | Fine sand | | | | |
| 344 | 7 | Coarse sand, soft | | | | |
| 367 | 13 | Coarse and fine sand - little chalk | | | | |
| 362 | 5 | Very coarse sand - soft † - used pit of water 301 to 308 | | | | |

WELL DATA:

Preliminary Test
 Date Tested 9-20 1941 Static Level
 Production 1400 GPM Pumping Level
 73' drawdown Permanent Test
 Date Tested 9-22 1941 Static Level 40'
 Production 835 GPM Active St. Level
 Drawdown 35' Pumping Level -/
 Remarks: 36 hour test

PUMP DATA:

| | |
|----------------|-----------------|
| Shop No. | Type Lube. |
| Type Head | Size Section |
| Depth Setting | (BP to MB) |
| Size Column | Length Suction |
| Type Bowl | Length Air Line |
| No. Stages | Discharge- |
| Cap'y and Head | Pressure |

MOTOR DATA:

| | |
|------------|-----------|
| Horsepower | Voltage |
| RPM | Phase |
| Type | Cycles |
| Make | Frame No. |

No. 1

| | | | | | | | | |
|---|---|---|-------------------------------------|-------------|---|--|---------------------|--------------------|
| WELL DATA | | | INSTALLATION Robins AFB, Georgia | | | | WELL NO. #1 | |
| ELEVATION (FT) | | LOCATION Bldg # 186 | | | | DATE CONSTN FINISHD 28 October 1941 | | |
| W E L L | TYPE Drilled Well (Underreamed Gravel - Packed Well) | | | | | | | |
| | DEPTH 265 ft. | | DIAMETER 8 in. | | PUMP SETTING DEPTH 100 ft. | | | |
| | ORIG STATIC WATER LEVEL No Record | | DRAWDOWN 35' | | RECOVERY TIME | | | |
| TEST DATA | | AIR LINES AND GAGES | | | SPECIFIC CAPACITY (Gal per ft) <u>GPM</u> <u>DRAWDOWN</u> | | | |
| Well capacity 850 GPM | Pumping level <input checked="" type="checkbox"/> | X | Yes | No | Length | | | |
| WELL PUMPING EQUIPMENT | | | | | | | | |
| P U M P | TYPE AND MAKE Vertical Turbine Layne Pump No. 17097 | | | | | | CAPACITY 850 GPM | |
| SUCTION (FT) | MEF. AND LENGTH 20 Ft. 6 in. | | COLUMN 8 in. | | | | | |
| HEAD | | | NUMBER BOWLS | | SIZE AND TYPE 12" RIMC | | NO. STAGES 4 | |
| Above grad <input checked="" type="checkbox"/> | Below grad <input type="checkbox"/> | Total <input checked="" type="checkbox"/> | 4 Stage | | | | | |
| MOTOR SERIAL NO. 286857 | TYPE CPU | MAKE U. S. Motor | 1/2" | RPM 1800 | FRAME 952 | PHASE 3 | CYCLES 60 | VOLTAGE 220/440 |
| STANDBY POWER Yes | MAKE General Motors diesel | | | | | | | MEF |
| HP 90 | RPM 1800 | DESCRIPTION Ser. No. 4A-90389; Model 4030C | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED | | | | | | SETTING DEPTH | LENGTH EACH | |
| 75 ft. of 20" pit casing cemented in place. | | | | | | | | |
| Top of original 12" screen line at 60' | | | | | | | | |
| Top of 8" screen line at 108' | | | | | | | | |
| 8" stainless steel screen at 110' - 130' and 245' - 265' | | | | | | | | |
| NOTE: Above well was relined in March 1953 to date shown above. | | | | | | | | |
| PUMP: Layne No. 17097 | | | | | | | | |
| 100' of 8" X 2 $\frac{1}{2}$ " X 1 $\frac{1}{2}$ " Column | | | | | | | | |
| 4 Stage 12" RIMC Bowls | | | | | | | | |
| 20' of 6" Suction | | | | | | | | |
| Gear Drives: Johnson 1 1/3 - 1 | | | | | | | | |

1A

MEASUREMENTS TAKEN FROM (GROUND) (TOP OF FOUNDATION) (TOP OF CASING) (TOP BASE PLATE)

DRAWING OF THE WELL

| | | | | | | |
|--------------------------------------|--------------------------------------|-------------------|---------------------|--------------------|-------------------|------------|
| WELL DATA | STARTED WELL | August 13 | 10 75 | AND COMPLETED | Sept. 17 | 10 75 |
| | TOTAL DEPTH | 360 | ELEVATION | STATIC WATER LEVEL | 37' | |
| | LENGTH SURFACE CASING | 156 | SIZE | 26 | THICKNESS | 0.375 |
| | CEMENTED WITH | 400 | SACKS CEMENT | TYPE PACKER | | |
| | LENGTH WELL CASING | | SIZE | | WEIGHT | |
| | CEMENTED WITH | | SACKS CEMENT | TYPE PACKER | | |
| | INNER CASING LENGTH | 360 | SIZE | 12" | WEIGHT | 0.375 wall |
| | WITH | as shown | GUIDES LOCATED | | TYRE BACKOFF | |
| | LEAD SEAL | | BACKPRESSURE VALVE | | GUIDE | |
| | WELL STRAINER MAKE Cook | size 12 | length .50 | OPENING .055 | | |
| TYPE MATERIAL | SS (304) | WITH | CONNECTIONS | | | |
| SIZE HOLE DRILLED FOR SURFACE CASING | 32 | WITH | Tri Cone | | | |
| SIZE HOLE DRILLED FOR WELL CASING | 26 | WITH | " " | | | |
| SIZE HOLE DRILLED FOR STRAINER | 26 | WITH | " " | | | |
| YARDS OF GRAVEL USED | 70 | NOW PLACED | Gravity & Back Flow | | | |
| NOW WAS WELL DEVELOPED | | Test Pump & Air | | | | |
| NOTES: | | | | | | |
| RIG USED | Gardner-Denver | DRILLER | S. Yawn | | | |
| PUMP RECORD | SERIAL NUMBER | 17097 | MAKE | Layne | FOUNDATION | |
| | LENGTH COLUMN | 100 | SIZE | 8 x 1½ x 2½ | TYPE OIL | 10 |
| | BOWL SIZE | 12 | TYPE R.K.A.M. | STAGES 4 | MATERIAL IMPELLER | bronze |
| | MATERIAL BOWL | C.I. | WITHDRAWN | PORTS AND | SHAFT | |
| | SUCTION SIZE | 8" | LENGTH | 10' | SUCTION STRAINER | cone |
| | IS PUMP SEALED NOW | | WHERE | | WITH WHAT | |
| | LUBRICATOR TYPE | | SIZE | | VOLTAGE | |
| | LENGTH OF AIRLINE | 100' | SIZE | 2" | TYPE MATERIAL | galvanized |
| | AIR RELEASE VALVE TYPE | | SIZE | | | |
| | SIZE SURFACE DISCHARGE | | TYPE | | DAYTON COUPLING | |
| PRESSURE GAUGE | | | | SPEED | | |
| NOTES | | | | | | |
| RIG USED TO SET PUMP | | INSTALLER | | | | |
| DATE PUMP INSTALLED | 10 | DATE IN OPERATION | 10 | | | |
| MOTOR | MAKE U.S. HP 100 | FRAME 404TP | PHASE 3 | CYCLE 60 | VOLT. 220/440 | |
| | SPEED 1800 | MODEL | | SERIAL NUMBER | | |
| | TOP BEARING | BOTTOM BEARING | | RATCHET | | |
| | STARTER | | PRESSURE SWITCH | FLOAT | | |
| GEAR | MAKE | MODEL | SIZE | RATIO | NO. | |
| | SIZE PULLEY | | TYPE MOTOR FRAME | | | |
| ENGINE | MAKE | MODEL | HP | SERIAL NUMBER | | |
| | SPEED | SIZE PULLEY | | FOUNDATION | | |
| | TYPE FUEL TANK | | MAKE MAG | NO. | | |
| | MAKE STARTER | NO | TYPE FUEL | | | |
| | MAKE FLEXIBLE SHAFT | SIZE | LENGTH | BELT LENGTH | | |
| GENERAL | PURPOSE FOR WHICH THIS WATER IS USED | | | | | |
| | TEMPERATURE | IS WATER CLEAR | | CAPACITY | | |
| | SAND | HARDNESS | PH | IRON | NACl | |
| | TYPE TREATMENT USED | | | | | |
| | IS THERE A DERRICK OVER THE WELL | | HEIGHT | TYPE | | |
| | CAN TRUCK OR RIG EASILY GET TO WELL | | | | | |
| | PUMP HOUSE | | SIZE MATCH | | | |

CONTRACT NO. 13254 - 171

OUR WELL NO. 1(a) THEIR WELL NO. 1(a) IN TEST HOLE NO.

LOCATION OF THE WELL Robins Air Force Base

INSTALLED FOR Mid-South Construction Company

ADDRESS CITY Warner Robins COUNTY Houston STATE Georgia

IGAPP Contract No. F09650-75-C-0083

Hedrill Well No. 1

Project No. WR 134-5

YEAR 1975

No. 1 A

Contract No. 13264

FORMATION LOG OF THE WELL OR TEST HOLE

STARTED TEST HOLE AUG. 20 1975 FINISHED Aug. 26 1975 TEST HOLE NUMBER 1
LOCATION Well No. 1 (a) SEC. 16 TS. RANGE ELEVATION
North of old Well No. 1, Bldg. No. 186 approximately 300'

LAYNE ATLANTIC COMPANY ~~b. n. sw.~~

NORFOLK, VA.

670

LOG OF WELL For Robins Field (Georgia Air Impor.)
 Located at Melton in (Near Macon, Ga.) County, State Georgia 122
 Date Drilling Started September 19, 1941 Date Started August 21, 1941
 Finished Drilling September 27, 1941 Finished October 28, 1941

FORMATION AND DEPTH OF WELL

DIMENSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS and CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN |
|---------------------------|-----------------------|--|---|---|--------------------------|--------------------------|-----------------|
| FT. IN. | FT. IN. | Well #2 | FT. | IN. | FT. IN. | IN. | |
| 45 | 45 | Fine brown sand | 75 | 75 | Casing | 20 | 6/16 |
| 67 | 22 | Medium white and yellow sand | 12" | casing commences 56'-6". | | | |
| 72 | 5 | Fine white sand | | | | | |
| 78 | 8 | Coarse sand and gravel - very hard | | | | | |
| 80 | 2 | Clay | | | | | |
| 95 | 16 | Coarse dark sand | | | | | |
| 108 | 13 | Medium white sand - soft | | | | | |
| 122 | 14 | Clay and chalk - soft | | | | | |
| 140 | 18 | Coarse sand and gravel - soft, used 2 pits of water | | | | | |
| 173 | 33 | Very soft white sand - used water | | | | | |
| 196 | 22 | Coarse white sand - cut medium | | | | | |
| 199 | 4 | Clay | | | | | |
| 206 | 6 | Fine sand and chalk | | | | | |
| 210 | 5 | Fine white sand | | | | | |
| 216 | 5 | Fine white sand and chalk | | | | | |
| 220 | 6 | Clay and gravel | | | | | |
| 225 | 5 | Coarse gravel - hard | | | | | |
| 230 | 5 | Coarse white sand, Cut medium, used 1/4 pit of water | | | | | |
| 240 | 8 | Coarse white sand - hard | | | | | |
| 250 | 10 | Fine white sand - medium | | | | | |
| 260 | 10 | " " " - soft | | | | | |
| 265 | 5 | Coarse " " - hard | | | | | |
| 270 | 5 | Coarse gravel - hard | | | | | |
| 290 | 20 | Chalk and gravel bottom of well 255' | | | | | |
| | | Under-reamed from 125 to 170 and from 225 to 255 | | | | | |

WELL DATA:

Preliminary Test

Date Tested 10-3 1941 Static Level 32'
 Production 900 to GPM Pumping Level
 925 GPM Permanent Test

Date Tested 1941 Static Level
 Production GPM Active St. Level
 Drawdown Pumping Level
 Remarks:

PUMP DATA:

| | |
|----------------|-----------------|
| Shop No. | Type Lubr. |
| Type Head | Size Suction |
| Depth Setting | (BP to MB) |
| Size Column | Length Suction |
| Type Bowl | Length Air Line |
| No. Stages | Discharge- |
| Cap'y and Head | Pressure |

MOTOR DATA:

| | |
|------------|-----------|
| Horsepower | Voltage |
| RPM | Phase |
| Type | Cycles |
| Make | Frame No. |

and be construed as a modification of Contract No. 13-122.


FORMATION LOG OF THE WELL OR TEST HOLE

STARTED TEST HOLE 10/11/64 FINISHED 10/11/64 TEST HOLE NUMBER 1
LOCATION SW 1/4, SE 1/4, NW 1/4, Section 10, Twp 10, Range 10, Marion Co., Ill. SEC 1 TS 1 RANGE 10 ELEVATION 1000 ft

No. 2

ALL MEASUREMENTS TAKEN FROM (GROUND) (TOP OF FOUNDATION) (TOP OF CABING) (TOP BASE PLATE)

DRAWING OF THE WELL



5" GUIDES @ 145'
5" " 200'
5" " 255'
5" " 300'
5" " 365'

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--------------------------------------|------------------|---------------------|------------------------|---------------|-------------|---------------|---------------|------|--------|-------------|--|--------------------------------------|----|------|----------|--|-----------------------------------|----|------|-----|--|--------------------------------|----|------|-----|--|----------------------|---------|------------|---------------------|--|------------------------|----------------------|--|--|--|--------|--|--|--|--|--|----------|---------------|--|---------|----------------|--|-------------|---------------|------|------------|--|--|---------------|------|------|----|-----|-----------|------|--------|-------------------|--|---------------|------|-----------|-----|--|--------------|--------|------------------|--|--|--------------------|-------|-----------|--|--|-----------------|------|---------|--|--|-------------------|------|---------------|--|--|------------------------|------|--|--|--|------------------------|------|-----------------|--|--|----------------|--|-------|--|--|-------|--|--|--|--|--|----------------------|--|--|-----------|--|--|---------------------|----|--|-------------------|----|--|-------|------|-----|-------|-------|-------|-------|-------|--|--|---------------|-------------|----------------|--|---------|--|---------|-----------------|--|-------|--|------|------|-------|------|-------|-----|-------------|------------------|--|--|--|--------|------|-------|-----|---------------|--|-------|-------------|------------|--|--|----------------|----------|--|-----|--|--------------|-----|-----------|--|--|---------------------|------|--------|-------------|--|---------|--------------------------------------|--|--|--|--|-------------|----------------|--|-----|--------------|------|------|----------|------------------------|---------------------|-----|--|--|--|----------------------------------|----|--------|------|--|-------------------------------------|-----|--|--|--|------------|------------|--|--|--|-------------------------|--|--|--|--|--|-------------------|---------------------|--|--------------------|--|--|----------------------|------------------------|--|--|--|--|---------------|-----------------------|--|--|--|--|--------------|---------------|--|--------|---------|---------------|--------------|--------------|--|--|--|--|---|--|--|--|--|--|------|------|--|--|--|
| WELL DATA | STARTED WELL | July 1 | 1974 | AND COMPLETED | August 2 | 1974 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | TOTAL DEPTH | 320 | ELEVATION | STATIC WATER LEVEL | 50' | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LENGTH SURFACE CABING | 150' | SIZE | 26" | THICKNESS | 0.375 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | CEMENTED WITH | 260 | SACKS CEMENT | TYPE PACKER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LENGTH WELL CABING | | SIZE | | WEIGHT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | CEMENTED WITH | | SACKS CEMENT | TYPE PACKER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | INNER CABING LENGTH | 320' | SIZE | 12" 1/2 | WEIGHT | 0.375 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | WITH | 5 X 5 | GUIDES LOCATED | SHOWN | TYPE BACKOFF | Orange Peel | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LEAD SEAL | | BACKPRESSURE VALVE | | GUIDE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | WELL STRAINER MAKE | COOK | SIZE | 12" | LENGTH | 50' | TYPE MATERIAL | S.S. Type 304 | WITH | Welded | CONNECTIONS | | SIZE HOLE DRILLED FOR SURFACE CABING | 32 | WITH | Tri-Cone | | SIZE HOLE DRILLED FOR WELL CABING | 26 | WITH | " " | | SIZE HOLE DRILLED FOR STRAINER | 25 | WITH | " " | | YARDS OF GRAVEL USED | 60 TONS | NOW PLACED | Pumped Low Pressure | | HOW WAS WELL DEVELOPED | Test Pump & Surgeing | | | | NOTES: | | | | | | RIG USED | Curdwell 1946 | | DRILLER | Sylvester Yawn | | PUMP RECORD | SERIAL NUMBER | MAKE | FOUNDATION | | | LENGTH COLUMN | SIZE | TYPE | 10 | LEN | BOWL SIZE | TYPE | STAGES | MATERIAL IMPELLER | | MATERIAL BOWL | WITH | PORTS AND | SHA | | SUCTION SIZE | LENGTH | SUCTION STRAINER | | | IS PUMP SEALED HOW | WHERE | WITH WHAT | | | LUBRICATOR TYPE | SIZE | VOLTAGE | | | LENGTH OF AIRLINE | SIZE | TYPE MATERIAL | | | AIR RELEASE VALVE TYPE | SIZE | | | | SIZE SURFACE DISCHARGE | TYPE | DAYTON COUPLING | | | PRESSURE GAUGE | | SPEED | | | NOTES | | | | | | RIG USED TO SET PUMP | | | INSTALLER | | | DATE PUMP INSTALLED | 10 | | DATE IN OPERATION | 10 | | MOTOR | MAKE | HP. | FRAME | PHASE | CYCLE | SPEED | MODEL | | | VOLT. 220/440 | TOP BEARING | BOTTOM BEARING | | RATCHET | | STARTER | PRESSURE SWITCH | | FLOAT | | GEAR | MAKE | MODEL | SIZE | RATIO | NO. | SIZE PULLEY | TYPE MOTOR FRAME | | | | ENGINE | MAKE | MODEL | HP. | SERIAL NUMBER | | SPEED | SIZE PULLEY | FOUNDATION | | | TYPE FUEL TANK | MAKE MAG | | NO. | | MAKE STARTER | NO. | TYPE FUEL | | | MAKE FLEXIBLE SHAFT | SIZE | LENGTH | BELT LENGTH | | GENERAL | PURPOSE FOR WHICH THIS WATER IS USED | | | | | TEMPERATURE | IS WATER CLEAR | | YES | CAPACITY 900 | SAND | NONE | HARDNESS | 5 PH 5.6 IRON .05 NACL | TYPE TREATMENT USED | C/2 | | | | IS THERE A DERRICK OVER THE WELL | NO | HEIGHT | TYPE | | CAN TRUCK OR RIG EASILY GET TO WELL | YES | | | | PUMP HOUSE | SIZE HATCH | | | | CONTRACT NO. 1312 - 100 | | | | | | OUR WELL NO. 2(a) | THEIR WELL NO. 2(a) | | IN TEST HOLE NO. 1 | | | LOCATION OF THE WELL | 100 ft. Air Force Base | | | | | INSTALLED FOR | Robins Air Force Base | | | | | ADDRESS CITY | Corner Col 18 | | COUNTY | Houston | STATE Georgia | Contract No. | 1966-74-0376 | | | | | Mid-South Construction Co. Warren Brothers, Inc., Prime Contractor | | | | | | YEAR | 1974 | | | |
| TYPE MATERIAL | S.S. Type 304 | WITH | Welded | CONNECTIONS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SIZE HOLE DRILLED FOR SURFACE CABING | 32 | WITH | Tri-Cone | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SIZE HOLE DRILLED FOR WELL CABING | 26 | WITH | " " | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SIZE HOLE DRILLED FOR STRAINER | 25 | WITH | " " | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| YARDS OF GRAVEL USED | 60 TONS | NOW PLACED | Pumped Low Pressure | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| HOW WAS WELL DEVELOPED | Test Pump & Surgeing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| NOTES: | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| RIG USED | Curdwell 1946 | | DRILLER | Sylvester Yawn | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PUMP RECORD | SERIAL NUMBER | MAKE | FOUNDATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LENGTH COLUMN | SIZE | TYPE | 10 | LEN | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | BOWL SIZE | TYPE | STAGES | MATERIAL IMPELLER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | MATERIAL BOWL | WITH | PORTS AND | SHA | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SUCTION SIZE | LENGTH | SUCTION STRAINER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | IS PUMP SEALED HOW | WHERE | WITH WHAT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LUBRICATOR TYPE | SIZE | VOLTAGE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | LENGTH OF AIRLINE | SIZE | TYPE MATERIAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | AIR RELEASE VALVE TYPE | SIZE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SIZE SURFACE DISCHARGE | TYPE | DAYTON COUPLING | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PRESSURE GAUGE | | SPEED | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| NOTES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| RIG USED TO SET PUMP | | | INSTALLER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DATE PUMP INSTALLED | 10 | | DATE IN OPERATION | 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MOTOR | MAKE | HP. | FRAME | PHASE | CYCLE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SPEED | MODEL | | | VOLT. 220/440 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | TOP BEARING | BOTTOM BEARING | | RATCHET | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | STARTER | PRESSURE SWITCH | | FLOAT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GEAR | MAKE | MODEL | SIZE | RATIO | NO. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SIZE PULLEY | TYPE MOTOR FRAME | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ENGINE | MAKE | MODEL | HP. | SERIAL NUMBER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SPEED | SIZE PULLEY | FOUNDATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | TYPE FUEL TANK | MAKE MAG | | NO. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | MAKE STARTER | NO. | TYPE FUEL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MAKE FLEXIBLE SHAFT | SIZE | LENGTH | BELT LENGTH | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GENERAL | PURPOSE FOR WHICH THIS WATER IS USED | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | TEMPERATURE | IS WATER CLEAR | | YES | CAPACITY 900 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SAND | NONE | HARDNESS | 5 PH 5.6 IRON .05 NACL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | TYPE TREATMENT USED | C/2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | IS THERE A DERRICK OVER THE WELL | NO | HEIGHT | TYPE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CAN TRUCK OR RIG EASILY GET TO WELL | YES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PUMP HOUSE | SIZE HATCH | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CONTRACT NO. 1312 - 100 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| OUR WELL NO. 2(a) | THEIR WELL NO. 2(a) | | IN TEST HOLE NO. 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| LOCATION OF THE WELL | 100 ft. Air Force Base | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| INSTALLED FOR | Robins Air Force Base | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ADDRESS CITY | Corner Col 18 | | COUNTY | Houston | STATE Georgia | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Contract No. | 1966-74-0376 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Mid-South Construction Co. Warren Brothers, Inc., Prime Contractor | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| YEAR | 1974 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| WELL DATA | | | INSTALLATION | | | WELL NO. | | | |
|---|---|---------------------------------------|-------------------|--------------|--|------------------------------|----------------|---------------------|--------------------|
| ELEVATION (FT) | | LOCATION Bldg # 164 | | | Robins AFM, Georgia | | | | |
| | | | | | DATE CONSTR ENDED 28 October 1941 | | | | |
| W E L L | TYPE Drilled Well (Underreamed Gravel - Packed Well) | | | | | | | | |
| | DEPTH 247 ft. | | DIAMETER 8 in. | | | PUMPSETTING DEPTH 120 ft. | | | |
| | ORIG STATIC WATER LEVEL 32 ft. | | DRAWDOWN | | | RECOVERY TIME | | | |
| TEST DATA | | AIR LINES AND GAGES | | | SPECIFIC CAPACITY (Gal per ft) $\frac{\text{GPM}}{\text{DRAWDOWN}}$ | | | | |
| Well capacity 950 GPM | Pumping level | X | Yes | No | Length | | | | |
| WELL PUMPING EQUIPMENT | | | | | | | | | |
| P U M P | TYPE AND MAKE Vertical Turbine Layne Pump No. 14428 | | | | | | | CAPACITY 950 GPM | |
| | SUCTION (FT) 30' 6" | SIZE AND LENGTH | | | COLUMN 8 in. | | | | |
| | HEAD | | | NUMBER BOWLS | | SIZE AND TYPE | | NO STAGES | |
| Above grad | Below grad | Total | 4 Stage | | 12" RKHC | | 4 | | |
| M O T R | SERIAL NO. 6276089 | TYPE KF | MAKE G. E. | HP 100 | RPM 1765 | FRAME N-6508 | PHASE 3 | CYCLES 60 | VOLTAGE 220/440 |
| STANDBY POWER YES | MAKE Sterling - Model Nr. LC-6 | | | | | | | SIZE | |
| HP 135 | RPM 1350 | DESCRIPTION Gasoline Engine 135 HP | | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED | | | | | | SETTING DEPTH | LENGTH EACH | | |
| 75' of 20" pit casing cemented in place. | | | | | | | | | |
| Top of original 12" screen line 56' - 6" | | | | | | | | | |
| Top of 8" screen line at 128' - 6" | | | | | | | | | |
| 8" stainless steel screen at 130 - 150' and 227 - 247' | | | | | | | | | |
| <u>NOTE:</u> Above well was relined in May 1954 to date as shown above. | | | | | | | | | |
| <u>PUMP:</u> Layne No. 14428 | | | | | | | | | |
| 120' of 8" X 2½" X 1½" Column | | | | | | | | | |
| 4 Stage 12" RKHC Bowls | | | | | | | | | |
| 30' of 6" Suction | | | | | | | | | |
| Gear Drive: Johnson 1 1/3 - 1 | | | | | | | | | |

LAYNE ATLANTIC COMPANY

NORFOLK, VA.

LOG OF WELL For WILMING Field (Well # 3)

Located at Wilmington, Georgia (Baldwin County, State Georgia)

Date Drilling Started 19 Date Started 19

Finished Drilling 19 Finished Oct. 10 19

FORMATION AND DEPTH OF WELL

IMMERSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS OR CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN |
|------------------------------------|-----------------------------|---|---|--|-----------------------------------|-----------------------------------|-----------------------|
| FT. | IN. | FT. | IN. | FT. | IN. | FT. | IN. |
| 21 | 10 | Coarse sand & gravel | 75 | 75 | Casing | 10 | |
| 21 | 10 | Coarse sand | (25 ft.) | 100 | Casing | 10 | |
| 21 | 10 | Coarse sand | 100 | 100 | Casing | 10 | |
| 21 | 10 | Coarse sand & gravel | 210 | 30 | Screen | 12 | |
| 21 | 7 | Coarse sand | 215 | 75 | Casing | 12 | |
| 21 | 7 | Coarse sand, chalk, gravel - bedrock | 205 | 20 | Screen | 12 | |
| 22 | 5 | Coarse chalk | | | | | |
| 22 | 3 | Clay & chalk, bedrock | | | | | |
| 22 | 15 | Coarse sand, gravel, grit bedrock, hard rock | | | | | |
| 22 | 10 | Fine white sand, soft | | | | | |
| 22 | 10 | Coarse white sand, very soft | | | | | |
| 22 | 5 | Dark, brown, white sand, soft | | | | | |
| 22 | 10 | Coarse yellow sand | | | | | |
| 22 | 10 | Coarse fine white sand, soft | | | | | |
| 22 | 5 | Soft coarse white sand | | | | | |
| 22 | 1 | Hard | | | | | |
| 22 | 15 | Chalk & gravel | | | | | |
| 22 | 5 | Soft coarse white sand | | | | | |
| 22 | 5 | Med. coarse white sand | | | | | |
| 24 | 10 | Med. & hard white sand | | | | | |
| 24 | 5 | Chalk & coarse sand | | | | | |
| 26 | 15 | Chalk & sand | | | | | |
| 26 | 5 | Med. fine sand & chalk | | | | | |
| 22 | 15 | Med. coarse sand | | | | | |
| 22 | 11 | Coarse white sand | | | | | |
| 22 | 10 | Med. coarse white sand | | | | | |
| 22 | 15 | Coarse sand & chalk | | | | | |
| 22 | 10 | Coarse white sand, soft | | | | | |
| 328 | 5 | Coarse sand & gravel | | | | | |
| 328 | 10 | Fine sand | | | | | |
| 344 | 6 | Clay & chalk | | | | | |
| 350 | 5 | Coarse sand & gravel | | | | | |
| 360 | 7 | Chalk | | | | | |
| 365 | 7 | Chalk, clay & coarse sand | | | | | |
| 375 | 10 | Hard clay - bottom of hole | | | | | |

WELL DATA:

Preliminary Test

Date Tested 19 Static Level 30

Production GPM Pumping Level

Permanent Test

Date Tested 19 Static Level

Production GPM Active St. Level

Drawdown Pumping Level

Remarks:

PUMP DATA:

Shop No. 1400 Type Lubr.

Type Head Size Section

Depth Setting (BP to MB)

Size Column Length Suction

Type Bowl Length Air Line

No. Stages Discharge-

Cap'y and Head Pressure

MOTOR DATA:

Horsepower Voltage

RPM Phase

Type Cycles

Make Frame No.

#4

NORFOLK, VA.

LOG OF WELL For Job No. 1451 (Well 14) Located at Lincoln in Lincoln County, State Oregon
 Date Drilling Started 19 Date Started 19
 Finished Drilling 19 Finished Key 19

FORMATION AND DEPTH OF WELL

DIMENSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF EACH SEC. OF SCREEN ON CASING | SPECIFY SCREEN ON CASING | SIZE OF SCREEN ON CASING | Gauge of SCREEN |
|------------------------------------|-----------------------------|--|--|--|-----------------------------------|-----------------------------------|-----------------------|
| FT. | IN. | FT. | IN. | FT. | IN. | FT. | IN. |
| 10 | 10 | Top soil | | | | | |
| 20 | 10 | Red clay, gravel | | | | | |
| 30 | 5 | Red clay, coarse sand, dry hard, little white chalk | | | | | |
| 35 | 5 | White chalk, clay, slow drill- ing | | | | | |
| 40 | 10 | Sand & clay, slow drilling | | | | | |
| 50 | 10 | Dense sand, fast drilling | | | | | |
| 50 | 20 | Dense sand & clay, med. drilling | | | | | |
| 55 | 20 | Coarse sand, soft drilling | | | | | |
| 60 | 10 | Blue clay, slow drilling | | | | | |
| 70 | 50 | Blue & white chalk, clay, medium drilling | | | | | |
| 70 | 40 | Sand, fast drilling | | | | | |
| 70 | 30 | White clay, cut hard | | | | | |
| 70 | 28 | Fine white sand, cut fast & rough, hard water | | | | | |
| 70 | 10 | Coarse sand, soft drilling | | | | | |
| 70 | 21 | Coarse white sand, soft drilling | | | | | |

WELL DATA:

Preliminary Test
 Date Tested 19 Static Level
 Production GPM Pumping Level
 Permanent Test
 Date Tested 19 Static Level
 Production GPM Active St. Level
 Drawdown Pumping Level
 Remarks:

PUMP DATA:

| | |
|----------------|-----------------|
| Shop No. | Type Lubr. |
| Type Head | Size Suction |
| Depth Setting | (BP to MB) |
| Size Column | Length Suction |
| Type Bowl | Length Air Line |
| No. Stages | Discharge- |
| Cap'y and Head | Pressure |

MOTOR DATA:

| | |
|------------|-----------|
| Horsepower | Voltage |
| RPM | Phase |
| Type | Cycles |
| Make | Frame No. |

Name of Well: Field
 Located at: Houston
 Date Drilling Started: April 25
 Finished Drilling: May 9

in: 1956
 Date Started: April 19
 Finished: May 24

County, State: Georgia
 1956

FORMATIONS AND DEPTHS OF WELL

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | |
|---------------------------|-----------------------|---|-----|
| FT. | IN. | FT. | IN. |
| 1 | 1 | Top Soil | |
| 19 | 18 | Red Clay and Sand | |
| 33 | 14 | Sand & Gravel | |
| 45 | 12 | Fine Sand | |
| 56 | 11 | Kaolin | |
| 66 | 9 | Fine Sand & Clay | |
| 105 | 40 | Coarse Sand Soft | |
| 111 | 6 | Cavity-no returns | |
| 121 | 20 | Coarse Sand, Soft | |
| 140 | 9 | Coarse Sand & Clay | |
| 152 | 12 | Ind Sand & Clay | |
| 166 | 13 | Fine Sand with Clay | |
| 186 | 21 | Blue & Chalky Clay, Soft | |
| 204 | 18 | Chalky Clay, Mod. Drilling | |
| 231 | 27 | Mod. Coarse Sand | |
| 236 | 5 | Chalky Clay, Slow Drilling | |
| 248 | 12 | Coarse Sand, Soft | |
| 250 | 12 | Coarse Sand, very little clay | |
| 340 | 80 | Coarse sand with thin streaks of Kaolin | |
| 346 | 29 | Coarse Sand, Soft | |
| 375 | 6 | Coarse Sand with a little clay | |
| 388 | 17 | Sand & Clay, mod. drilling | |
| 422 | 10 | Coarse Sand, soft. | |
| 446 | 38 | Coarse White Sand with streaks of Kaolin. | |

DIMENSIONS OF CASING AND SCREEN

| TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN |
|---|---|--|--------------------------|-------------------|
| FT. | IN. | FT. | IN. | IN. |
| 32 | 32 | Casing | 20 | Cemented in place |
| | | Top of screen line is at surface | | |
| 190 | 195 | Casing | 12 | |
| 220 | 225 | Casing | 10 | |
| 230 | 10 | Screen | 10 | |
| 300 | 70 | Casing | 10 | |
| 310 | 10 | Screen | 10 | |
| 330 | 20 | Casing | 10 | |
| 350 | 20 | Screen | 10 | |
| 360 | 10 | Casing | 10 | |
| 370 | 10 | Screen | 10 | |
| 385 | 10 | Casing | 10 | |
| | | Bottom of finished well is at 325' with steel plate welded across screen line. | | |

WELL DATA:

Preliminary Test

Date Tested: 19 Static Level
Production GPM Pumping Level

Permanent Test

Date Tested: 19 Static Level
Production 982 GPM Active St. Level 39'
Drawdown 46' Pumping Level 87'
Remarks: Ran pumping test 12 hours, installed pump from old well #4.

PUMP DATA:

Shop No. 11860 Type Lubr. Oil
Type Head 17" S25 Size Section 2"
Depth Setting 60" (BP to MB)
Size Column 17" x 2" Length Section 28'
Type Bowl 17" RMC Length Air Line 100'
No. Stages 3 Discharge-
Cap'y and Head Pressure

MOTOR DATA:

Horsepower 60 Voltage 220/440
RPM 1800 Phase 3
Type Cycles 60
Mains. S. Electrical Frame No. 950

No. 4

LAYNE ATLANTIC COMPANY
NORFOLK, VA.

LOG OF WELL For Robbins Field (Well #4)

| | | | |
|---|------------------------------|----------------------------|--------------|
| Located at <u>Belltown</u> (New Haven, Georgia) | County, State <u>Georgia</u> | | |
| Date Drilling Started <u>May 26</u> | 19 <u>43</u> | Date Started <u>May 19</u> | 19 <u>43</u> |
| Finished Drilling <u>June 25</u> | 19 <u>43</u> | Finished <u>July 2</u> | 19 <u>43</u> |

FORMATION AND DEPTH OF WELL

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM |
|------------------------------------|-----------------------------|---------------------------------|
|------------------------------------|-----------------------------|---------------------------------|

| FT. | IN. | PT. IN. |
|-----|-----|---|
| 10 | 10 | Top Soil |
| 20 | 10 | Red clay & gravel |
| 25 | 5 | Red clay & coarse sand. Co hard. Little white chalk |
| 30 | 5 | White chalk, clay, slow drilling |
| 40 | 10 | Sand & clay slow drilling |
| 50 | 10 | Coarse sand, fast drilling |
| 60 | 10 | Coarse sand & clay, good drilling |
| 115 | 25 | Coarse sand & soft drilling |
| 125 | 10 | Blue clay, slow drilling |
| 175 | 10 | Blue & white chalk, clay and drilling 300 |
| 210 | 10 | Sand, fast drilling |
| 225 | 10 | White clay, cut hard |
| 250 | 10 | Fine white sand, cut fast & rough wood water |
| 272 | 10 | Coarse sand, soft drilling |
| 280 | 10 | Smooth white sand, soft drilling |
| 290 | 10 | Smooth white sand, soft drilling |
| 300 | 25 | Coarse white sand, small lumps of white clay. Cut & rough drilling |
| 430 | 90 | Coarse white sand with little sand. Lumps white clay. |

*Old Well #4, has been
discontinued, done
away with,
and new well drilled*

DIMENSIONS OF CASING AND SCREEN

| TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | Gauge of screen |
|--|----------------------------------|-----------------------------------|-----------------------------------|-----------------------|
|--|----------------------------------|-----------------------------------|-----------------------------------|-----------------------|

| FT. | IN. | PT. IN. | IN. | IN. |
|----------------------------------|--------|---------------------|-----|--------------------|
| 80 | 80 | Casing | 18 | Completed in place |
| Top of 12" | Screen | Line at surface (1) | | |
| 300 | 300 | Casing | 12 | |
| 310 | 10 | Screen | 12 | |
| 320 | 90 | Casing | 12 | |
| 330 | 10 | Screen | 12 | |
| 340 | 80 | Casing | 12 | |
| 350 | 10 | Screen | 12 | |
| 360 | 90 | Casing | 12 | |
| Bottom of completed well at 390' | | | | |

WELL DATA:**Preliminary Test**

| | | |
|----------------|---|------------------------------|
| Date Tested | 19 | Static Level |
| Production | GPM | Pumping Level |
| Permanent Test | | |
| Date Tested | 7/23 19 <u>43</u> | Static Level 32° (1) |
| Production | 775 | GPM Active St. Level 32° (1) |
| Drawdown | 47 | Pumping Level 79° |
| Remarks: | Am test 13 hours. Installed new pump tool assembly June 6, 1952. | |

PUMP DATA:

| | |
|-------------------------------|--------------------|
| Shop No. 11860 | Type Lubr. Oil |
| Type Head T7625 | Size Section 5" |
| Depth Setting 110' (BP to MB) | |
| Size Column 12" (BP to MB) | Length Suction 10' |
| Type Bowl 12" RRLC | Length Air Line |
| No. Stages 5 | Discharge- |
| Cap'y and Head | Pressure |

MOTOR DATA:

| | |
|--------------|-----------------|
| Horsepower 6 | Voltage 220/440 |
| RPM 1750 | Phase 3 |
| Type 1/2 | Cycles 60 |
| Date | Frame No. 20 |

| | | | | | | | | |
|---|--|-------------------------------------|-------------------------------|--|---------------------|------------------|----------------|---------|
| WELL DATA | | INSTALLATION Robins AFB, Georgia | | WELL NO #4 | | | | |
| ELEVATION (FT) | LOCATION Bldg # 648 | | | DATE CONSIDERED 24 May 1956 | | | | |
| TYPE Drilled Well (Underreamed Gravel - Packed well) | | | | | | | | |
| W E L | DEPTH 385 ft. | DIAMETER 8 in. | PUMP SETTING DEPTH 100 ft. | | | | | |
| L | ORIG STATIC WATER LEVEL 39 ft. | DRAWDOWN | RECOVERY TIME | | | | | |
| TEST DATA | | AIR LINES AND GAGES | | SPECIFIC CAPACITY (Gal per ft.) GPM = DRAWDOWN | | | | |
| Well capacity 900 GPM | Pumping level <input checked="" type="checkbox"/> | Yes | No | Length | | | | |
| WELL PUMPING EQUIPMENT | | | | | | | | |
| P U M P | TYPE AND MAKE Vertical Turbine Layne Pump No. 11860 | | | | CAPACITY 900 GPM | | | |
| SUCTION (FT) 28 ft. 8 in. | SIZE AND LENGTH | | COLUMN 8 in. | | | | | |
| HEAD | | NUMBER BOWLS | | SIZE AND TYPE 12" RKLC | NO STAGES 5 | | | |
| Above grad | Below grad | Total | 5 Stage | | | | | |
| M O T O R | SEIMAL NO. NO | TYPE MAKE | HP | RPM | FRAME | PHASE | CYCLES | VOLTAGE |
| | | | | | | SIZE | | |
| HP | RPM | DESCRIPTION | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED | | | | | | SETTING DEPTH | LENGTH EACH | |
| 52' of 20" pit casing cemented in place. | | | | | | | | |
| Top of 12 X 10" screen line at ground surface. | | | | | | | | |
| 12" pipe to 195' | | | | | | | | |
| 10" pipe from 195' to 220' | | | | | | | | |
| 10" stainless steel screen line - 220' to 230' | | | | | | | | |
| 300' to 310' | | | | | | | | |
| 330' to 350' | | | | | | | | |
| 360' to 370' | | | | | | | | |
| NOTE: Attempted to reline old well #4 in February 1956, but was unable to do so. | | | | | | | | |
| PUMP: Layne No. 11860 | | | | | | | | |
| 100' of 8" X 1 $\frac{1}{2}$ " X 2 $\frac{1}{2}$ " Column | | | | | | | | |
| 5 Stage 12" RKLC Bowls | | | | | | | | |
| 28' of 8" Suction | | | | | | | | |

Contract No. AF 33 (603)-50148
Building 311

Job No. 10447

No. 5 A-1

LAYNE ATLANTIC COMPANY

Albany, Georgia

LOG OF WELL For **Mobius Air Force Base** - Well No. 5 (Relocated 1963)
Located **Mobius AFB** in **Houston**, County, State **Georgia**
Date Drilling Started **July 23** 19 **63** Date Started **July 23** 19 **63**
Finished Drilling **Oct. 25** 19 **63** Finished **Oct. 25** 19 **63**

| FORMATION AND DEPTH OF WELL | | | | DIMENSIONS OF CASING AND SCREEN | | | | | | | | | |
|--|-----|---|-----|---------------------------------|-----|--|-----|---|-----|--------------------------|--------------------------|-----------------|--|
| TOTAL DEPTH OF ALL STRATA | | DEPTH OF EACH STRATUM | | FORMATION FOUND AT EACH STRATUM | | TOTAL LENGTH OF ALL SCREENS AND CASINGS | | LENGTH OF EACH SEC. OF SCREEN OR CASING | | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN | |
| FT. | IN. | FT. | IN. | | | FT. | IN. | FT. | IN. | | | | |
| 1 | 1 | Top soil | | 40 | 90 | casing | 20 | Pit Casing | | | | | |
| 12 | 11 | sand Clay | | | | Connected in 26" Hole | | | | | | | |
| 23 | 14 | Coarse sand | | | | Screen line starts at ground | | | | | | | |
| 38 | 13 | Clay - sand band | | 253 | 253 | casing | 12 | | | | | | |
| 54 | 13 | Sand - Clay | | 263 | 10 | screen | 12 | #7 gauge | 12 | | | | |
| 78 | 28 | Coarse white sand | | 310 | 47 | casing | 12 | | | | | | |
| 92 | 15 | Clay + little sand | | 328 | 9 | screen | 12 | #7 gauge | 12 | | | | |
| 123 | 30 | Coarse sand | | 330 | 25 | casing | 12 | | | | | | |
| 125 | 6 | Clay | | 363 | 15 | screen | 12 | #7 gauge | 12 | | | | |
| 140 | 31 | Coarse sand | | 370 | 9 | casing | 12 | #7 gauge | 12 | | | | |
| 186 | 28 | Coarse sand with streaks of yellow clay | | 380 | 10 | screen | 12 | #7 gauge | 12 | | | | |
| 214 | 31 | Coarse sand | | 390 | 10 | casing | 12 | | | | | | |
| 226 | 10 | Coarse sand, streaks of white clay | | | | Bottom of screen line orange painted weld. | | | | | | | |
| 236 | 16 | Clay | | | | Total 40' Layne Stainless Steel | | | | | | | |
| 238 | 102 | Coarse sand and little white clay | | | | shutter screen #7 gauge. | | | | | | | |
| 330 | 52 | Coarse sand and some white clay | | | | | | | | | | | |
| <i>Changed existing Johnson Gear Drive Model 59100 Series No. 7723 from 1771 to 172 New Continental Engine Speed 1800 RPM, Type RD572.</i> | | | | | | | | | | | | | |
| <i>Pumped well 32 GPM. Installed existing pump and electric motor with new auxiliary engine.</i> | | | | | | | | | | | | | |
| <i>Shop No. 12868A Type Lubr. G11 Type Head 38025 Size Suction 10" Depth Setting 130 (BP to MD) Length Suction 30" Size Column 10x12x21 Type Blow 12" HKMC Length Air Line 121' No. Stages 5 Discharge Cup'y and Head Pressure</i> | | | | | | | | | | | | | |
| <i>MOTOR DATA: Horsepower 100 Voltage 440 RPM 1800 Phase 3 Type CFU Cycles 60 Make US Frame No. 952</i> | | | | | | | | | | | | | |

Telephone 45-1111 (ext) - 36143
Building 311

Job No. 10547

LAYNE ATLANTIC COMPANY
Albany, Georgia

LOG OF WELL For Robins Air Force Base
Located **Robins AFB** in **Houston**
Date Drilling Started July 25 1963 Date Started
Finished Drilling Oct. 25 1963 Finished

Well No. 5 (relocated 1963)
County, State Georgia

| | FORMATIONS AND DEPTHS OF WELL | | | | DIMENSIONS OF CAVING AND SCREEN | | | | | | | |
|------------------|--|-----------------------------|---|-----|--|--|-----------------------------------|-----------------------------------|-----------------------|--|--|--|
| | TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | | TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN | | | |
| | FT. | IN. | FT. | IN. | FT. | IN. | FT. | IN. | FT. | | | |
| 1 | 1 | 1 | Top soil | | 40 | 40 | Casing | 20 | Pit Casing | | | |
| 12 | 11 | | Sand Clay | | Concrete in 26" Hole | | | | | | | |
| 23 | 14 | | Coarse sand | | 6' from line starts at ground | | | | | | | |
| 34 | 13 | Clay and sand | | | surface. | | | | | | | |
| 36 | 12 | | Sandy Clay | | 233 | 233 | Casing | 12 | | | | |
| 78 | 28 | | Coarse white sand | | 26 | 10 | screen | 12 | #7 gauge 33 | | | |
| 82 | 19 | | Clay, little sand | | 310 | 47 | Casing | 12 | | | | |
| 123 | 36 | | Coarse sand | | 325 | 5 | screen | 12 | #7 gauge 33 | | | |
| 126 | 6 | | Clay | | 350 | 25 | Casing | 12 | | | | |
| 140 | 31 | | Coarse sand | | 365 | 15 | screen | 12 | #7 gauge 33 | | | |
| 185 | 25 | | Coarse sand with streaks of yellow clay | | 370 | 5 | Casing | 12 | | | | |
| 214 | 31 | | Coarse Sand | | 380 | 10 | screen | 12 | #7 gauge 33 | | | |
| 226 | 10 | | Coarse sand, other of white clay | | 390 | 10 | Casing | 12 | | | | |
| 236 | 16 | | Clay | | | | Bottom of screen line orange | | | | | |
| 238 | 102 | | Coarse sand and little white clay. | | | | painted w/ld. | | | | | |
| 30 | 92 | | Coarse sand and some white clay | | | | Total 40' Layne Stainless Steel | | | | | |
| | | | | | | | Shutter Screen #7 gauge. | | | | | |
| WELL DATA: | | | | | | | | | | | | |
| Preliminary Test | | | | | | | | | | | | |
| Date Tested | | | | | 19 | Static Level | | | | | | |
| Production | 10000 GPM | | | | 45' | Pumping Level | 45' | | | | | |
| | 1220 | | | | 45' | Permanent Test | | | | | | |
| Date Tested | 4/28 | | | | 19 | Static Level | | | | | | |
| Production | 1220 GPM | | | | 45' | Active St. Level | 45' | | | | | |
| Drawdown | 20' | | | | | Pumping Level | 45' | | | | | |
| Remarks: | Test pumped well 12 hrs. Installed existing pump and electric motor with new auxiliary engine. | | | | | | | | | | | |
| PUMP DATA: | | | | | | | | | | | | |
| Shop No. | 12868A | | | | | Type Lubr. | 611 | | | | | |
| Type Head | TF029 | | | | | Size Suction | | | | | | |
| Depth Setting | 130 | | | | | 10" | | | | | | |
| Size Column | 10x1x2 | | | | | Length Suction | | | | | | |
| Type Bowl | 12" RHEC | | | | | 30" | | | | | | |
| No. Stages | 5 | | | | | Length Air Line | 121' | | | | | |
| Cap'y and Head | | | | | | Discharge Pressure | | | | | | |
| MOTOR DATA: | | | | | | | | | | | | |
| Horsepower | 100 | | | | | Voltage | 440 | | | | | |
| RPM | 1800 | | | | | Phase | 3 | | | | | |
| Type | CFU | | | | | Cycles | 60 | | | | | |
| Make | GE | | | | | Frame No. | 282 | | | | | |

LAYNE ATLANTIC COMPANY
NORFOLK, VA.

LOG OF WELL For drilling Field (Well # 5)
 Located at Tolson in (County, State) County, State Georgia
 Date Drilling Started 19 Date Started 19
 Finished Drilling 19 Finished June 19

| FORMATION AND DEPTH OF WELL | | | DIMENSIONS OF CASING AND SCREEN | | | | |
|------------------------------------|-----------------------------|---------------------------------|--|--|-----------------------------------|-----------------------------------|-----------------------|
| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN |
| FT. | IN. | FT. | IN. | FT. | IN. | FT. | IN. |
| 26 | 25 | Red sandy clay | 80 | 80 | Casing | 18 | |
| 37 | 5 | White clay | 200 | 140 | Casing | 12 | |
| | | | 210 | 10 | Screen | 12 | 7 |
| 46 | 10 | Dough sand & clay | 260 | 50 | Casing | 12 | |
| | | | 270 | 10 | Screen | 12 | |
| 77 | 30 | Coarse sand | 290 | 20 | Casing | 12 | |
| | | | 300 | 10 | Screen | 12 | |
| 96 | 20 | Coarse sandy clay | 360 | 60 | Casing | 12 | |
| | | | 370 | 10 | Screen | 12 | |
| 115 | 21 | Coarse sand, soft | | | | | |
| 134 | 60 | Fine & white clay | | | | | |
| 154 | 10 | Soft sand | | | | | |
| 173 | 10 | Hard white clay | | | | | |
| 192 | 28 | Fine white sand | | | | | |
| 256 | 93 | Coarse white sand | | | | | |

WELL DATA:

Preliminary Test

Date Tested 6/10 1960 Static Level 33

Production 700 GPM Pumping Level

Permanent Test

Date Tested 19 Static Level

Production GPM Active St. Level

Pumping Level

Remarks:

PUMP DATA:

| | |
|----------------|-----------------|
| Shop No. 1 | Type Lubr. |
| Type Head | Size Suction |
| Depth Setting | (BP to MB) |
| Size Column | Length Suction |
| Type Bowl | Length Air Line |
| No. Stages | Discharge- |
| Cap'y and Head | Pressure |

| | | | | | | | | |
|---|---|---|-------------------------------------|-------------------------|--------------------------------------|---------------------------|------------------|------------------|
| WELL DATA | | | INSTALLATION Robins AFB, Georgia | | | WELL NO. #5 | | |
| ELEVATION (FT) | | LOCATION Bldg # 511 | | | DATE CONSTR ENDED 25 October 1963 | | | |
| W E L L | TYPE Drilled Well (Underreamed Gravel - Packed Well) | | | | | | | |
| | DEPTH 390 ft. | | DIAMETER 10 in. | | PUMPSETTING DEPTH 130 ft. | | | |
| | ORIG STATIC WATER LEVEL 45 ft. | | DRAWDOWN 20 ft. | | RECOVERY TIME | | | |
| TEST DATA | | AIR LINES AND GAGES | | | SPECIFIC CAPACITY (Gal per ft.) | | | |
| Well capacity 1050 | Pumping level 65 ft. | <input checked="" type="checkbox"/> Yes | No | Length 121 ft. | GPM | = | DRAWDOWN | |
| WELL PUMPING EQUIPMENT | | | | | | | | |
| P U M P | TYPE AND MAKE Vertical Turbine Layne Pump No. 12868A | | | | | | | CAPACITY 1050 |
| | SUCTION (FT) | SIZE AND LENGTH 30 ft. | | COLUMN 10 in. | | | | |
| | HEAD | | | NUMBER BOWLS 5 Stage | | SIZE AND TYPE 12" RIMC | | NO. STAGES 5 |
| | SERIAL NO. 328387 | TYPE CPU | MAKE U.S. Motors | HP 100 | RPM 1800 | FRAME 982-4 | PHASE 3 | CYCLES 60 |
| STANDBY POWER Yes | | MAKE Continental Red Seal | | | | | | SIZE |
| HP 154 | RPM 1800 | DESCRIPTION Model - 39100 | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED | | | | | | | SETTING DEPTH | LENGTH EACH |
| 90' of 20" pit casing cemented in place. | | | | | | | | |
| Screen line starts at ground surface. | | | | | | | | |
| Total 40' Layne stainless steel shutter. | | | | | | | | |
| Screen #7 gauge | | | | | | | | |
| NOTE: This well was drilled to replace the old #5 well. | | | | | | | | |
| PUMP: 130' of 10 X 1½" X 2½" Column | | | | | | | | |
| 5 Stage 12" RIMC Bowls | | | | | | | | |
| 30' of 10" Suction | | | | | | | | |
| NOTE: Changed existing Johnson Gear Drive | | | | | | | | |
| Model 39100 Serial No. 7723 from 1:1 to 1:1 | | | | | | | | |
| New Continental engine installed. | | | | | | | | |

| | | | | | | | | | |
|---|---|--|---------------------------------|---|----------------------|----------------|------------|--------------|--------------------|
| WELL DATA | | INSTALLATION Robins AFB, Georgia | | WELL NO. #6 | | | | | |
| ELEVATION (FT) | | LOCATION Bldg # 1688 | | DATE CONSTN. ENDED 29 July 1943 | | | | | |
| W | TYPE Drilled Well (Underreamed Gravel - Packed Well) | | | | | | | | |
| E | DEPTH 311 ft. | DIAMETER 8 in. | PUMPSETTING DEPTH 100 ft. | | | | | | |
| L | ORIG STATIC WATER LEVEL 45 ft. | DRAWDOWN | RECOVERY TIME | | | | | | |
| TEST DATA | | AIR LINES AND GAGES | | SPECIFIC CAPACITY (Gal per (1) GPM DRAWDOWN | | | | | |
| Well capacity 1500 GPM | Pumping level | Yes <input checked="" type="checkbox"/> No | Length | | | | | | |
| WELL PUMPING EQUIPMENT | | | | | | | | | |
| P | TYPE AND MAKE Vertical Turbine Layne Pump No. 49616 | | | | CAPACITY 1500 GPM | | | | |
| U | SUCTION (FT) 30 ft. | SIZE AND LENGTH 8 in. | COLUMN 8 in. | | | | | | |
| M | HEAD Above grad Below grad Total | | NUMBER BOWLS | | SIZE AND TYPE | NO. STAGES | | | |
| P | SERIAL NO. BJJ221005 | TYPE K | MAKE G. E. | HP 150 | RPM 1775 | FRAME 6542 | PHASE 3 | CYCLES 60 | VOLTAGE 220/440 |
| O | STANDBY POWER Yes | | MAKE Waukesha | | | | SIZE | | |
| T | HP 145 | RPM 1750 | DESCRIPTION Model Nr. 145-GK | | | | | | |
| R | CASING AND WELL SCREENING MATERIAL USED | | | | SETTING DEPTH | LENGTH EACH | | | |
| 80' of 18" pit casing submitted in place. | | | | | | | | | |
| Top of 12" screen line at 53' | | | | | | | | | |
| 12" screen set as follows: 151' - 161' | | | | | | | | | |
| 221' - 231' | | | | | | | | | |
| 251' - 261' | | | | | | | | | |
| 301' - 311' | | | | | | | | | |
| <u>PUMP:</u> | | | | | | | | | |
| 100' of 8" Column | | | | | | | | | |
| 100' of 2½" tubing | | | | | | | | | |
| 100' stainless steel shaft | | | | | | | | | |
| 30' of 8" Suction | | | | | | | | | |
| A new concrete foundation for pump under work completed | | | | | | | | | |
| 8 June 1964. | | | | | | | | | |

LAYNE ATLANTIC COMPANY

NORFOLK, VA.

#6

LOG OF WELL For Robbins Field (Well # 6)
 Located at Wellston in (near Macon, Ga.) County, State Georgia
 Date Drilling Started June 21, 1943 Date Started 19
 Finished Drilling 19 Finished July 29, 1943

FORMATION AND DEPTH OF WELL

DIMENSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS AND CASINGS | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SIZE OF SCREEN OR CASING | SIZE OF SCREEN ON CASING | GAUGE OF SCREEN |
|------------------------------------|-----------------------------|--|--|--|--|-----------------------------------|-----------------------|
| FT. | IN. | FT. IN. | FT. | IN. | FT. | IN. | IN. |
| 8 | 8 | Red clay, cut slow | 80 | 80 | Casing | 18 | |
| 36 | 28 | Brown sand, fast drilling | 151 | 98 | Casing | 12 | |
| 40 | 4 | White chalk clay | 161 | 10 | Screen | 12 | #7 |
| 60 | 20 | Fine white sand, med. drilling | 221 | 60 | Casing | 12 | |
| | | | 231 | 10 | Screen | 12 | #7 |
| 100 | 40 | Coarse white sand, medium drilling | 251 | 20 | Casing | 12 | |
| | | | 261 | 10 | Screen | 12 | #7 |
| 157 | 57 | Coarse white sand, medium drilling (lumps of white clay) | 301 | 40 | Casing | 12 | |
| | | | 311 | 10 | Screen | 12 | #7 |
| 199 | 82 | Coarse white sand, medium drilling | | | | | |
| 230 | 31 | Fine white sand, cut soft | | | | | |
| 240 | 10 | Sand & chalk clay, medium drilling | | | | | |
| 300 | 60 | Coarse white sand, medium drilling | | | | | |
| 315 | 15 | Fine white sand, medium drilling | | | | | |
| 367 | 52 | Sandy clay, slow drilling | | | | | |

Preliminary Test

Date Tested 8/21 1943 Static Level 45
 Production 250 GPM Pumping Level 58.5
 1500 Drawdown 12.5
 Permanent Test

Date Tested 19 Static Level
 Production GPM Active St. Level
 Drawdown Pumping Level
 Remarks:

PUMP DATA:

| | |
|-------------------------------|-----------------|
| Shop No. 12869 | Type Lube. |
| Type Head | Size Section |
| Depth Setting 115' (BP to MB) | |
| Size Column | Length Section |
| Type Bowl | Length Air Line |
| No. Stages | Discharge |
| Cap'y and Head | Pressure |

MOTOR DATA:

| | |
|------------|-----------|
| Horsepower | Voltage |
| RPM | Phase |
| Type | Cycles |
| Make | Frame No. |

LAYNE ATLANTIC COMPANY

NORFOLK, VA.

LOG OF WELL For Robins Air Force Base - Caphart Offsite Utilities

| | | | | | |
|-----------------------|--------------|-------|--------------|---------------|---------|
| Located at | Robins Field | in | Houston | County, State | Georgia |
| Date Drilling Started | Sept. 17 | 19 58 | Date Started | Sept. 8 | 10 58 |
| Finished Drilling | Oct. 9 | 19 58 | Finished | Dec. 18 | 19 58 |

#7

FORMATION AND DEPTH OF WELL

DIMENSIONS OF CASING AND SCREEN

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | TOTAL LENGTH OF ALL SCREENS AND CASING | LENGTH OF EACH SEC. OF SCREEN OR CASING | SPECIFY SCREEN OR CASING | SIZE OF SCREEN OR CASING | GAUGE OF SCREEN |
|------------------------------------|-----------------------------|---|---|--|-----------------------------------|-----------------------------------|------------------------------------|
| | | | | | FT. | IN. | IN. |
| FT. | IN. | PT. | FT. | IN. | FT. | IN. | IN. |
| 3 | 3 | Top Soil | 165 | 160 | Casing | 20 | Pit ... and concreted in place. |
| 15 | 12 | Red Sand | | | | | |
| 65 | 50 | Sand with thin streaks clay | | | | | |
| 83 | 18 | Coarse sand | | | | | |
| 105 | 20 | Coarse sand with clay particles | 200 | 60 | casing | 12 | |
| 125 | 20 | Coarse sand | 266 | 66 | Casing | 10 | |
| 161 | 26 | Yellowish coarse sand. | 286 | 20 | Screen 10 | #7 S. S. | |
| 168 | 7 | Grey clay & some shell rock | 215 | 29 | Casing | 10 | |
| 195 | 26 | White Coarse sand | 225 | 10 | Screen | 10 | #7 S. S. |
| 195 | 1 | Streak of Clay | 240 | 15 | Casing | 10 | # |
| 203 | 6 | Grey Coarse Sand | 350 | 10 | Screen | 10 | #7 S. S. |
| 220 | 17 | Mixture of Clays. Gray & White | 420 | 70 | Casing | 10 | |
| 220 | 10 | White Coarse Sand | 430 | 10 | Screen | 10 | #7 S. S. |
| 244 | 12 | Clay with streaks of coarse sand | 440 | 10 | Casing | 10 | |
| 27 | 13 | White Coarse sand | | | | | |
| 28 | 3 | Kaolin | | | | | |
| 264 | 6 | Soft sand. | | | | | |
| 266 | 2 | Kaolin | | | | | |
| | | Coarse white sand | | | | | |
| 320 | 50 | Coarse sand with thin streaks of clay | | | | | |
| 339 | 4 | Kaolin | | | | | |
| 355 | 15 | Coarse sand. Soft | | | | | |
| 355 | 30 | Coarse sand with thin streaks of clay | | | | | |
| 400 | 15 | Sand with more clay than above. | | | | | |
| 414 | 14 | Pink clay. Slow Drilling | | | | | |
| 430 | 16 | Coarse white sand | | | | | |
| 490 | 60 | Coarse white sand with very thin streaks of kaolin. Soft. | | | | | |

WELL DATA:

Preliminary Test

| | |
|-------------|-------------------|
| Date Tested | 19 Static Level |
| Production | GPM Pumping Level |

Permanent Test

| | |
|--------------------------|---------------------|
| Date Tested Oct. 17 1958 | Static Level 38 |
| Production 992 GPM | Active St. Level 23 |
| Drawdown 24' | Pumping Level 62' |

Remarks: Ran pumping test 12 hours.

PUMP DATA:

| | |
|--------------------|-----------------|
| Shop No. 39690 | Type Lubr. Oil |
| Type Head TF318 | Size Suction 8" |
| Dentl. Suction 10" | |

| WELL DATA | | | INSTALLATION Kobins AFB, Georgia | | | | WELL NO #7 | | |
|---|---|---|-------------------------------------|---|---|-----------------------------|----------------|----------------------|--------------------|
| ELEVATION (FT) | LOCATION Bldg # 1004 | | | DATE CONSTR. FINISHED 18 December 1958 | | | | | |
| W F L | TYPE Drilled Well (Underreamed Gravel - Packed Well) | | | | | | | | |
| | DEPTH 440 ft. | DIAMETER 8 in. | | | PUMPSETTING DEPTH 100 ft. | | | | |
| | ORIG STATIC WATER LEVEL 38 ft. | DRAWDOWN 24 ft. | | | RECOVERY TIME | | | | |
| TEST DATA | | AIR LINES AND GAGES | | | SPECIFIC CAPACITY (Gal per (t) GPM DRAWDOWN = | | | | |
| Well capacity 1100 GPM | Pumping level | <input checked="" type="checkbox"/> Yes | No | Length | | | | | |
| WELL PUMPING EQUIPMENT | | | | | | | | | |
| P U M P | TYPE AND MAKE Vertical Turbine Layne Pump No. 39690 | | | | | | | CAPACITY 1100 GPM | |
| SUCTION (FT) | SIZE AND LENGTH 10 ft. 8 in. | | | COLUMN 8 in. | | | | | |
| HEAD | | | NUMBER BOWLS 5 Stage | | | SEE AND TYPE 12 in. RKMC | NO STAGES 5 | | |
| M O T T R | SERIAL NO. 1158727 | TYPE CFU | MAKE U.S. Motors | HP 100 | RPM 1800 | FRAME 504-P4 | PHASE 3 | CYCLES 60 | VOLTAGE 220/440 |
| STANDBY POWER No | MAKE | | | | | | | | SIZE |
| HP | RPM | DESCRIPTION | | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED | | | | | | | SETTING DEPTH | LENGTH EACH | |
| 165' of 20" pit casing cemented in place. | | | | | | | | | |
| Top of 12" x 10" screen line 140' | | | | | | | | | |
| 12" pipe 140' to 200' | | | | | | | | | |
| 10" pipe and screen line below. | | | | | | | | | |
| 10" stainless steel screen set at: 266'- 286' | | | | | | | | | |
| 315' - 325' | | | | | | | | | |
| 340' - 350' | | | | | | | | | |
| 420' - 430' | | | | | | | | | |
| PUMP: Layne No. 39690 | | | | | | | | | |
| 100' of 8" x 1 11/16" x 2 1/2" Column | | | | | | | | | |
| 5 Stage 12" RKMC Bowls | | | | | | | | | |
| 10' of 6" Suction | | | | | | | | | |

LAYNE ATLANTIC COMPANY
NORFOLK, VA.

#8

LOG OF WELL For SAC Paving Y-60
 Located at Bubba Plaza in Houston, County, State Georgia
 Date Drilling Started October 20 1968 Date Started Oct. 23 1968
 Finished Drilling November 14 1968 Finished June 16 1969

FORMATION AND DEPTH OF WELL

| TOTAL DEPTH OF ALL STRATA | DEPTH OF EACH STRATUM | FORMATION FOUND AT EACH STRATUM | PT. | IN. | PT. | IN. | PT. | IN. | PT. | IN. | PT. | IN. | PT. | IN. | PT. | IN. |
|---------------------------|-----------------------|--|--|------------------------------------|---------------|-----------|------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 7 | 7 | Clay | 82 | 82 | Casing | 20 | Pit Casing | | | | | | | | | |
| 20 | 21 | Soft sand | | | | | | | | | | | | | | |
| 36 | 12 | Coarse sand & clay | | | | | | | | | | | | | | |
| 76 | 40 | Sand, soft | 170 | 170 | Casing | 12 | | | | | | | | | | |
| 81 | 5 | Clay, Slow | 180 | 180 | Screen | 12 | 77 | | | | | | | | | |
| 104 | 23 | Coarse sand with thin streaks of Kaolin | 275 | 98 | Casing | 12 | | | | | | | | | | |
| 111 | 11 | Clay with sand, Slow | 295 | 7 | Casing | 12 | | | | | | | | | | |
| 176 | 63 | Coarse sand with very thin streaks of clay. Drilled fast. | 315 | 20 | Screen | 12 | 77 | | | | | | | | | |
| 186 | 8 | Coarse sand with clay. Soft | 325 | 10 | Screen | 12 | 77 | | | | | | | | | |
| 207 | 19 | Coarse sand with a little clay. | 400 | 10 | Casing | 12 | | | | | | | | | | |
| 217 | 10 | Coarse sand & clay. Medium | | | | | | | | | | | | | | |
| 241 | 24 | Coarse sand. Soft. | | | | | | | | | | | | | | |
| 252 | 11 | Kaolin. Slow drilling. | | | | | | | | | | | | | | |
| 265 | 13 | Kaolin with thin streaks sand. | | | | | | | | | | | | | | |
| 286 | 22 | Kaolin with heavy sand. | | | | | | | | | | | | | | |
| | | Bottom of screen line orange pealed. | | | | | | | | | | | | | | |
| | | Completed well depth 400'. | | | | | | | | | | | | | | |
| 320 | 65 | Coarse sandish sand with streaks of clay. Medium soft. | | | | | | | | | | | | | | |
| 320 | 4 | Kaolin, slow drilling. | | | | | | | | | | | | | | |
| 321 | 12 | Kaolin with coarse sand. Soft. | | | | | | | | | | | | | | |
| 325 | 9 | Yellow sandy clay. Slow. | | | | | | | | | | | | | | |
| 330 | 2 | Coarse sand. Soft. | | | | | | | | | | | | | | |
| 367 | 2 | Clay. Slow drilling | | | | | | | | | | | | | | |
| 377 | 10 | Coarse sand soft. | | | | | | | | | | | | | | |
| 383 | 21 | Clay. Slow drilling | | | | | | | | | | | | | | |
| 407 | 9 | Coarse sand with streaks of clay | | | | | | | | | | | | | | |
| 411 | 4 | Pink clay. Slow | Date Tested | 19 | Static Level | | | | | | | | | | | |
| 421 | 10 | Mixture of clays with thin streaks of sand. Medium. | Production | GPM Pumping Level | | | | | | | | | | | | |
| 431 | 10 | Red clay. Slow drilling | Date Tested | Dec. 2 1968 | Static Level | 90° | | | | | | | | | | |
| 441 | 10 | Red and white clay. Some sand. | Production | 1500 GPM Active St. Level | 90° | | | | | | | | | | | |
| 474 | 33 | Sandy red and yellow clay. | Drawdown | 20° - 40° | Pumping Level | 30° - 30° | | | | | | | | | | |
| 482 | 18 | Coarse yellow sand. Soft. | Remarks: | See test 17 hours. Pumped 1500 gpm | | | | | | | | | | | | |
| 493 | 3 | Yellow and white clay. | test 6 hours. Installed Johnson Combination Gear | | | | | | | | | | | | | |
| 508 | 13 | Coarse white sand. | Drive and Fairbanks Morse Diesel 400 ft. engine on | | | | | | | | | | | | | |
| 511 | 3 | Kaolin - Slow drilling. | Standby. | | | | | | | | | | | | | |
| 522 | 11 | Coarse white sand. | | | | | | | | | | | | | | |

WELL DATA:

Preliminary Test

Date Tested 19 Static Level

Production GPM Pumping Level

Permanent Test

Date Tested Dec. 2 1968 Static Level 90°

Production 1500 GPM Active St. Level 90°

Drawdown 20° - 40° Pumping Level 30° - 30°

Remarks: See test 17 hours. Pumped 1500 gpm

test 6 hours. Installed Johnson Combination Gear

Drive and Fairbanks Morse Diesel 400 ft. engine on

Standby.

PUMP DATA:

Shop No. 39623 Type Lube. Oil

Type Head 5014 Size Suction 6"

Depth Setting 60° (BP to MB)

Size Column 6" x 12" x 12" Length Suction 10'

12" ARM Length Air Line 60'

Type Bowl 5 No. Stages 3 Discharge-

Cap'y and Head 1000 GPM Pressure

MOTOR DATA:

75 HP Voltage 440

RPM 1800 Phase 3

Type CPU Cycles 60

Make U. S. Electrical Frame No. 403

| WELL DATA | | | INSTALLED WORK | | | WELL NO. | | |
|--|--|---|----------------|-------------|------------------------------|------------|----------------------|--------------------|
| ELEVATION (FT) | | LOCATION Bldg # C1 | | | DATE CONCRETE BENTONITE | | | |
| TYPE Drilled Well (Underreamed Gravel - Packed well) | | | | | | | | |
| DEPTH 400 ft. | | DIAMETER 6 in. | | | PUMPSETTING OFF TO 80 ft. | | | |
| ORIG STATIC WATER LEVEL 9 ft. | | DRAWDOWN | | | RECOVERY TIME | | | |
| TEST DATA | | AIR LINES AND GAGES | | | SPECIFIC CAPACITY (GPM/ft.) | | | |
| Well capacity 900 GPM | Pumping level <input checked="" type="checkbox"/> | X | Yes | No | Length | (ft) | GPM = DRAWDOWN | |
| WELL PUMPING EQUIPMENT | | | | | | | | |
| TYPE AND MAKE Vertical Turbine Layne Pump No. 39623 | | | | | | | CAPACITY 900 GPM | |
| SUCTION (FT) 10 ft. 8" | | SIZE AND LENGTH | | | COLUMN 8 in. | | | |
| HEAD | | NUMBER BOWLS | | | SIZE AND TYPE | | NO STAGES | |
| Above grad | Below grad | Total | 5 Stage | | 12" RIMC | | 5 | |
| SERIAL NO. 1089523 | TYPE CFU | MAKE U.S. Motors | H.P. 75 | RPM 1800 | FRAME 445P | PHASE 3 | CYCLES 60 | VOLTAGE 220/440 |
| STANDBY POWER Yes | | MAKE Fairbanks - Morse, Diesel | | | | | | SIZE |
| H.P. 90 | RPM 1800 | DESCRIPTION Model Nr. 49B-4 $\frac{1}{2}$ -18S | | | | | | |
| CASING AND WELL SCREENING MATERIAL USED. | | | | | | | SETTING DEPTH | LENGTH EACH |
| 82' of 20" pit casing cemented in place. | | | | | | | | |
| Top of 12" screen line at ground surface. | | | | | | | | |
| 12" stainless steel screen set at: 170' - 180' | | | | | | | | |
| 278' - 288' | | | | | | | | |
| 295' - 315' | | | | | | | | |
| 375' - 385' | | | | | | | | |
| PUMP: Layne No. 39623 | | | | | | | | |
| 80' of 8" X 1 $\frac{1}{2}$ " X 2 $\frac{1}{2}$ " Column | | | | | | | | |
| 5 Stage 12" RIMC Bowls | | | | | | | | |
| 10' of 8" Suction | | | | | | | | |

APPENDIX G
HAZARD EVALUATION METHODOLOGY

APPENDIX G

USAF INSTALLATION RESTORATION PROGRAM HAZARD ASSESSMENT RATING METHODOLOGY

BACKGROUND

The Department of Defense (DOD) has established a comprehensive program to identify, evaluate, and control problems associated with past disposal practices at DOD facilities. One of the actions required under this program is to:

"develop and maintain a priority listing of contaminated installations and facilities for remedial action based on potential hazard to public health, welfare, and environmental impacts." (Reference: DEQPPM 81-5, 11 December 1981).

Accordingly, the United States Air Force (USAF) has sought to establish a system to set priorities for taking further actions at sites based upon information gathered during the Records Search phase of its Installation Restoration Program (IRP).

The first site rating model was developed in June 1981 at a meeting with representatives from USAF Occupational Environmental Health Laboratory (OEHL), Air Force Engineering Services Center (AFESC), Engineering-Science (ES) and CH₂M Hill. The basis for this model was a system developed for EPA by JRB Associates of McLean, Virginia. The JRB model was modified to meet Air Force needs.

After using this model for 6 months at over 20 Air Force installations, certain inadequacies became apparent. Therefore, on January 26 and 27, 1982, representatives of USAF OEHL, AFESC, various major commands, Engineering Science, and CH₂M Hill met to address the inadequacies. The result of the meeting was a new site rating model designed to present a better picture of the hazards posed by sites at Air Force installations. The new rating model described in this presentation is referred to as the Hazard Assessment Rating Methodology.

PURPOSE

The purpose of the site rating model is to provide a relative ranking of sites of suspected contamination from hazardous substances. This model will assist the Air Force in setting priorities for follow-on site investigations and confirmation work under Phase II of IRP.

This rating system is used only after it has been determined that (1) potential for contamination exists (hazardous wastes present in sufficient quantity), and (2) potential for migration exists. A site can be deleted from consideration for rating on either basis.

DESCRIPTION OF MODEL

Like the other hazardous waste site ranking models, the U.S. Air Force's site rating model uses a scoring system to rank sites for priority attention. However, in developing this model, the designers incorporated some special features to meet specific DOD program needs.

The model uses data readily obtained during the Record Search portion (Phase I) of the IRP. Scoring judgments and computations are easily made. In assessing the hazards at a given site, the model develops a score based on the most likely routes of contamination and the worst hazards at the site. Sites are given low scores only if there are clearly no hazards at the site. This approach meshes well with the policy for evaluating and setting restrictions on excess DOD properties.

As with the previous model, this model considers four aspects of the hazard posed by a specific site: the possible receptors of the contamination, the waste and its characteristics, potential pathways for waste contaminant migration, and any efforts to contain the contaminants. Each of these categories contains a number of rating factors that are used in the overall hazard rating.

The receptors category rating is calculated by scoring each factor, multiplying by a factor weighting constant and adding the weighted scores to obtain a total category score.

The pathways category rating is based on evidence of contaminant migration or an evaluation of the highest potential (worst case) for contaminant migration along one of three pathways. If evidence of contaminant migration exists, the category is given a subscore of 80 to 100 points. For indirect evidence, 80 points are assigned and for direct evidence 100 points are assigned. If no evidence is found, the highest score among three possible routes is used. These routes are surface water migration, flooding, and ground-water migration. Evaluation of each route involves factors associated with the particular migration route. The three pathways are evaluated and the highest score among all four of the potential scores is used.

The waste characteristics category is scored in three steps. First, a point rating is assigned based on an assessment of the waste quantity and the hazard (worst case) associated with the site. The level of confidence in the information is also factored into the assessment. Next, the score is multiplied by a waste persistence factor, which acts to reduce the score if the waste is not very persistent. Finally, the score is further modified by the physical state of the waste. Liquid wastes receive the maximum score, while scores for sludges and solids are reduced.

The scores for each of the three categories are then added together and normalized to a maximum possible score of 100. Then the waste management practice category is scored. Sites at which there is no containment are not reduced in score. Scores for sites with limited containment can be reduced by 5 percent. If a site is contained and well managed, its score can be reduced by 90 percent. The final site score is calculated by applying the waste management practices category factor to the sum of the scores for the other three categories.

FIGURE 1

HAZARDOUS ASSESSMENT RATING METHODOLOGY FLOW CHART




FIGURE 2
HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE _____
 LOCATION _____
 DATE OF OPERATION OR OCCURRENCE _____
 OWNER/OPERATOR _____
 COMMENTS/DESCRIPTION _____
 SITE RATED BY _____

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | | 4 | | |
| B. Distance to nearest well | | 10 | | |
| C. Land use/zoning within 1 mile radius | | 3 | | |
| D. Distance to reservation boundary | | 6 | | |
| E. Critical environments within 1 mile radius of site | | 10 | | |
| F. Water quality of nearest surface water body | | 6 | | |
| G. Ground water use of uppermost aquifer | | 9 | | |
| H. Population served by surface water supply within 3 miles downstream of site | | 6 | | |
| I. Population served by ground-water supply within 3 miles of site | | 6 | | |

Subtotals _____

Receptors subscore (100 X factor score subtotal/maximum score subtotal) _____

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) _____
2. Confidence level (C = confirmed, S = suspected) _____
3. Hazard rating (H = high, M = medium, L = low) _____

Factor Subscore A (from 20 to 100 based on factor score matrix) _____

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

_____ X _____ = _____

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

_____ X _____ = _____

FIGURE 2 (Continued)

Page 2 of 2

III. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|--|--------------------------------|-------------------|---------------------|-------------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| <u>Subscore</u> _____ | | | | |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Surface erosion</u> | | 8 | | |
| <u>Surface permeability</u> | | 6 | | |
| <u>Rainfall intensity</u> | | 8 | | |
| <u>Subtotals</u> _____ | | | | |
| Subscore (100 x factor score subtotal/maximum score subtotal) _____ | | | | |
| 2. <u>Flooding</u> _____ | | | | |
| Subscore (100 x factor score/3) _____ | | | | |
| 3. <u>Ground-water migration</u> | | | | |
| <u>Depth to ground water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Soil permeability</u> | | 8 | | |
| <u>Subsurface flows</u> | | 8 | | |
| <u>Direct access to ground water</u> | | 8 | | |
| <u>Subtotals</u> _____ | | | | |
| Subscore (100 x factor score subtotal/maximum score subtotal) _____ | | | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore _____**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|--------------------------------|-----------------------------|
| <u>Receptors</u> | _____ |
| <u>Waste Characteristics</u> | _____ |
| <u>Pathways</u> | _____ |
| <u>Total</u> _____ | <u>divided by 3</u> = _____ |
| <u>Gross Total Score</u> _____ | |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

HAZARDOUS ASSESSMENT RATING METHODOLOGY GUIDELINES

I. RECEPTORS CATEGORY

| Rating Factors | Rating Scale Levels | | | Multiplier |
|--|--|--|---|---|
| | 0 | 1 | 2. | |
| A. Population within 1,000 feet (includes on-base facilities) | 0 | 1 - 25 | 26 - 100 | Greater than 100 |
| B. Distance to nearest water well | Greater than 3 miles | 1 to 3 miles | 3,001 feet to 1 mile | 0 to 3,000 feet |
| C. Land Use/Zoning (within 1 mile radius) | Completely remote (zoning not applicable) | Agricultural | Commercial or Industrial | Residential |
| D. Distance to installation boundary | Greater than 2 miles | 1 to 2 miles | 1,001 feet to 1 mile | 0 to 1,000 feet |
| E. Critical environments (within 1 mile radius) | Not a critical environment | Natural areas | Pristine natural areas; minor wetlands; preserved areas; presence of economically important natural resources susceptible to contamination. | Major habitat of an endangered or threatened species; presence of recharge area; major wetlands. |
| F. Water quality/use designation of nearest surface water body | Agricultural or industrial use. | Recreation, propagation and management of fish and wildlife. | Shellfish propagation and harvesting. | Potable water supplies |
| G. Ground-Water use of uppermost aquifer | Not used, other sources readily available. | Commercial, industrial, or irrigation, very limited other water sources. | Drinking water, municipal water available. | Drinking water, no municipal water available; commercial, industrial, or irrigation, no other water source available. |
| H. Population served by surface water supplies within 3 miles downstream of site | 0 | 1 - 50 | 51 - 1,000 | Greater than 1,000 |
| I. Population served by aquifer supplies within 3 miles of site | 0 | 1 - 50 | 51 - 1,000 | Greater than 1, 000 |

TABLE 1 (Continued)
HAZARDOUS ASSESSMENT RATING METHODOLOGY GUIDELINES (Cont'd)

III. WASTE CHARACTERISTICS

A-1 Hazardous Waste Quantity

S = Small quantity (<5 tons or 20 drums of liquid)
 M = Moderate quantity (5 to 20 tons or 21 to 85 drums of liquid)
 L = Large quantity (>20 tons or 85 drums of liquid)

A-2 Confidence Level of Information

C = Confirmed confidence level (minimum criteria below)

o Verbal reports from interviewer (at least 2) or written information from the records.

o Knowledge of types and quantities of wastes generated by shops and other areas on base.

o Based on the above, a determination of the types and quantities of waste disposed of at the site.

A-3 Hazard Rating

| Hazard Category | Rating Scale Levels | | |
|-----------------|--------------------------------|--------------------------------|--------------------------------|
| | 0 | 1 | 2 |
| Toxicity | Sax's Level 0 | Sax's Level 1 | Sax's Level 2 |
| Ignitability | Flash point greater than 200°F | Flash point at 140°F to 200°F | Flash point at 80°F to 140°F |
| Radioactivity | At or below background levels | 1 to 3 times background levels | 3 to 5 times background levels |

Use the highest individual rating based on toxicity, ignitability and radioactivity and determine the hazard rating.

| Hazard Rating | Points |
|---------------|--------|
| High (H) | 3 |
| Medium (M) | 2 |
| Low (L) | 1 |

TABLE 1 (Continued)

HAZARDOUS ASSESSMENT RATING METHODOLOGY GUIDELINES (Cont'd)

II. WASTE CHARACTERISTICS (Continued)

Waste Characteristics Matrix

| Point Rating | Hazardous Waste Quantity | Confidence Level of Information | Hazard Rating |
|--------------|--------------------------|---------------------------------|---------------|
| 100 | L | C | H |
| 80 | L H | C C | H H |
| 70 | L | S | H |
| 60 | S H | C C | B H |
| 50 | L | S | H |
| | H | C | L |
| | S | C | H |
| 40 | S | S | H |
| | H | S | H |
| | H | C | L |
| | L | S | L |
| 30 | S | C | L |
| | H | S | L |
| | S | S | H |
| 20 | S | S | L |

Notes:

For a site with more than one hazardous waste, the waste quantities may be added using the following rules:

- o Confirmed confidence levels (C) can be added
- o Suspected confidence levels (S) can be added
- o Confirmed confidence levels cannot be added with suspected confidence levels

Waste Hazard Rating

- o Wastes with the same hazard rating can be added
- o Wastes with different hazard ratings can only be added in a downgrade mode, e.g., MCN + SCH = LCN if the total quantity is greater than 20 tons.

Example: Several wastes may be present at a site, each having an MCN designation (60 points). By adding the quantities of each waste, the designation may change to LCN (80 points). In this case, the correct point rating for the waste is 80.

B. Persistence Multiplier for Point Rating

| Persistence Criteria | Multiply Point Rating From Part A by the Following |
|---|--|
| Metals, polycyclic compounds, and halogenated hydrocarbons Substituted and other ring compounds | 1.0 |
| Straight chain hydrocarbons | 0.9 |
| Easily biodegradable compounds | 0.8 |
| | 0.4 |

C. Physical State Multiplier

| Physical State | Multiply Point Total From Parts A and B by the Following |
|----------------|--|
| Liquid | 1.0 |
| Sludge | 0.75 |
| Solid | 0.50 |

TABLE 1 (Continued)

HAZARDOUS ASSESSMENT RATING METHODOLOGY GUIDELINES (Cont'd)

III. PATHWAYS CATEGORYA. Evidence of Contamination

Direct evidence is obtained from laboratory analyses of hazardous contaminants present above natural background levels in surface water, ground water, or air. Evidence should confirm that the source of contamination is the site being evaluated.

Indirect evidence might be from visual observation (i.e., leachate), vegetation stress, sludge deposits, presence of taste and odors in drinking water, or reported discharges that cannot be directly confirmed as resulting from the site, but the site is greatly suspected of being a source of contamination.

B-1 POTENTIAL FOR SURFACE WATER CONTAMINATION

| Rating Factor | Rating Scale Levels | | | Multiplier | |
|---|--|---|---|--|---|
| | 0 | 1 | 2 | | |
| Distance to nearest surface water (includes drainage ditches and storm sewers) | Greater than 1 mile | 2,000 feet to 1 mile | 500 feet to 2,000 feet | 0 to 500 feet | 8 |
| Net precipitation | Less than -10 in. | -10 to +5 in. | +5 to +20 in. | Greater than +20 in. | 6 |
| Surface erosion | None | Slight | Moderate | Severe | 8 |
| Surface permeability | 0% to 15% clay (>10 ⁻² cm/sec) | 15% to 30% clay (10 ⁻² to 10 ⁻³ cm/sec) | 30% to 50% clay (10 ⁻³ to 10 ⁻⁴ cm/sec) | Greater than 50% clay (<10 ⁻⁴ cm/sec) | 6 |
| Rainfall intensity based on 1 year 24-hr rainfall | <1.0 inch | 1.0-2.0 inches | 2.1-3.0 inches | >3.0 inches | 8 |
| <u>B-2 POTENTIAL FOR FLOODING</u> | | | | | |
| Floodplain | Beyond 100-year floodplain | In 25-year floodplain | In 10-year floodplain | Floods annually | 1 |
| <u>B-3 POTENTIAL FOR GROUND-WATER CONTAMINATION</u> | | | | | |
| Depth to ground water | Greater than 500 ft | 50 to 500 feet | 11 to 50 feet | 0 to 10 feet | 8 |
| Net precipitation | Less than -10 in. | -10 to +5 in. | +5 to +20 in. | Greater than +20 in. | 6 |
| Soil permeability | Greater than 50% clay (>10 ⁻² cm/sec) | 15% to 50% clay (10 ⁻² to 10 ⁻³ cm/sec) | 5% to 30% clay (10 ⁻³ to 10 ⁻⁴ cm/sec) | 0% to 15% clay (<10 ⁻⁴ cm/sec) | 8 |
| Subsurface flows | Bottom of site greater than 5 feet above high ground-water level | Bottom of site occasionally submerged | Bottom of site frequently submerged | Bottom of site located below mean ground-water level | 8 |
| Direct access to ground water (through faults, fractures, faulty well casings, subsidence fissures, etc.) | No evidence of risk | Low risk | Moderate risk | High risk | 8 |

TABLE 1 (Continued)
HAZARDOUS ASSESSMENT RATING METHODOLOGY GUIDELINES (Cont'd)

IV. WASTE MANAGEMENT PRACTICES CATEGORY

A. This category adjusts the total risk as determined from the receptors, pathways, and waste characteristics categories for waste management practices and engineering controls designed to reduce this risk. The total risk is determined by first averaging the receptors, pathways, and waste characteristics subscores.

B. WASTE MANAGEMENT PRACTICES FACTOR

The following multipliers are then applied to the total risk points (from A):

| <u>Waste Management Practice</u> | <u>Multiplier</u> |
|--|-------------------|
| No containment | 1.0 |
| Limited containment | 0.95 |
| Fully contained and in full compliance | 0.10 |

Guidelines for fully contained:

Landfills:

- o Clay cap or other impermeable cover
- o Leachate collection system
- o Liners in good condition
- o Adequate monitoring wells

Surface Impoundments:

- o Liners in good condition
- o Sound dikes and adequate freeboard
- o Adequate monitoring wells

Spills:

- o Quick spill cleanup action taken
- o Contaminated soil removed
- o Soil and/or water samples confirm total cleanup of the spill
- o Concrete surface and berms
- o Oil/water separator for pretreatment of runoff
- o Effluent from oil/water separator to treatment plant

General Note: If data are not available or known to be complete the factor ratings under items I-A through I, III-B-1 or III-B-3, then leave blank for calculation of factor score and maximum possible score.

APPENDIX H
SITE RATING FORMS

SITE RATING FORMS

TABLE OF CONTENTS

| <u>Site</u> | <u>Page</u> |
|---------------------------------------|-------------|
| Sludge Lagoon | H-1 |
| Landfill No. 4 | H-3 |
| DDT Spill at Pesticide Storage Area | H-5 |
| Fire Protection Training Area No. 2 | H-7 |
| Landfill No. 1 | H-9 |
| Landfill No. 2 | H-11 |
| JP-4 Spill (1965) | H-13 |
| Hazardous Waste Burial Site | H-15 |
| Fire Protection Training Area No. 1 | H-17 |
| Laboratory Chemical Disposal Site | H-19 |
| Landfill No. 3 | H-21 |
| Fire Training Pit No. 3 | H-23 |
| Radioactive (Solid) Waste Burial Site | H-25 |

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Sludge Lagoon
 LOCATION North of and Adjacent to Landfill No. 4
 DATE OF OPERATION OR OCCURRENCE 1962 to 1978
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION
 SITE RATED BY S. J. Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 2 | 4 | 8 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 2 | 10 | 20 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | <u>103</u> | | <u>180</u> | |

Receptors subscore (100 x factor score subtotal/maximum score subtotal) 57

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) L
2. Confidence level (C = confirmed, S = suspected) C
3. Hazard rating (H = high, M = medium, L = low) H

Factor Subscore A (from 20 to 100 based on factor score matrix) 100

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\frac{100}{ } \times \frac{1.0}{ } = \frac{100}{ }$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\frac{100}{ } \times \frac{0.75}{ } = \frac{75}{ }$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|------------------------|------------|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | Subscore | <u>100</u> |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | | | 8 | |
| <u>Net precipitation</u> | | | 6 | |
| <u>Surface erosion</u> | | | 8 | |
| <u>Surface permeability</u> | | | 6 | |
| <u>Rainfall intensity</u> | | | 8 | |
| Subtotals _____ | | | | |
| Subscore (100 x factor score subtotal/maximum score subtotal) <u>N/A</u> | | | | |
| 2. <u>Flooding</u> | | | | |
| Subscore (100 x factor score/3) <u>N/A</u> | | | | |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | | | 8 | |
| <u>Net precipitation</u> | | | 6 | |
| <u>Soil permeability</u> | | | 8 | |
| <u>Subsurface flows</u> | | | 8 | |
| <u>Direct access to ground water</u> | | | 8 | |
| Subtotals _____ <u>N/A</u> | | | | |
| Subscore (100 x factor score subtotal/maximum score subtotal) _____ | | | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 100**IV. WASTE MANAGEMENT PRACTICES**

A. Average the three subscores for receptors, waste characteristics, and pathways.

| | |
|------------------------------|--------------------------|
| <u>Receptors</u> | <u>57</u> |
| <u>Waste Characteristics</u> | <u>75</u> |
| <u>Pathways</u> | <u>100</u> |
| Total <u>232</u> | divided by 3 = <u>77</u> |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

$$\underline{77} \times \underline{1.0} = \boxed{\underline{77}}$$

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Landfill No. 4
 LOCATION Southeast of Industrial Waste Treatment Plant No. 1
 DATE OF OPERATION OR OCCURRENCE 1965 to 1978
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION
 SITE RATED BY EJ (Editor)

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 3 | 4 | 12 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 2 | 10 | 20 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| | | Subtotals | 107 | 180 |
| | | | | 59 |

Receptors subscore (100 X factor score subtotal/maximum score subtotal)

II. WASTE CHARACTERISTICS

A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)

M

2. Confidence level (C = confirmed, S = suspected)

C

3. Hazard rating (H = high, M = medium, L = low)

H

Factor Subscore A (from 20 to 100 based on factor score matrix)

80

B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\frac{80}{\underline{\hspace{2cm}}} \times \frac{1}{\underline{\hspace{2cm}}} = \frac{80}{\underline{\hspace{2cm}}}$$

C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\frac{80}{\underline{\hspace{2cm}}} \times \frac{0.75}{\underline{\hspace{2cm}}} = \frac{60}{\underline{\hspace{2cm}}}$$

III. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|---|--------------------------------|--|---------------------|-------------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| Subscore <u>100</u> | | | | |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Surface erosion</u> | | 8 | | |
| <u>Surface permeability</u> | | 6 | | |
| <u>Rainfall intensity</u> | | 8 | | |
| | | <u>Subtotals</u> | <u> </u> | <u>N/A</u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) | | | | |
| 2. Flooding | | 1 | | |
| | | <u>Subscore (100 x factor score/3)</u> | <u> </u> | <u>N/A</u> |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Soil permeability</u> | | 8 | | |
| <u>Subsurface flows</u> | | 8 | | |
| <u>Direct access to ground water</u> | | 8 | | |
| | | <u>Subtotals</u> | <u> </u> | <u> </u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) | | | | |
| <u>N/A</u> | | | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 100**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|------------------------------|--------------------------|
| <u>Receptors</u> | <u>59</u> |
| <u>Waste Characteristics</u> | <u>60</u> |
| <u>Pathways</u> | <u>100</u> |
| Total <u>219</u> | divided by 3 = <u>73</u> |

Gross Total Score

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

73 x 1.0 = 73

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE DDT Spill at Pesticide Storage Area
 LOCATION Asphalt Pad Adjacent to Building 295
 DATE OF OPERATION OR OCCURRENCE 1979
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION DDT solution spilled over a gravel lot
 SITE RATED BY E. Schreder

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 3 | 4 | 12 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 3 | 6 | 18 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| | | | Subtotals | 93 180 |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 51

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) S

2. Confidence level (C = confirmed, S = suspected) C

3. Hazard rating (H = high, M = medium, L = low) H

60

Factor Subscore A (from 20 to 100 based on factor score matrix) 60

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\frac{60}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{60}{\underline{\hspace{2cm}}}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\frac{60}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{60}{\underline{\hspace{2cm}}}$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|------------------------|---|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | Subscore | 100 |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Surface erosion</u> | | 8 | | |
| <u>Surface permeability</u> | | 6 | | |
| <u>Rainfall intensity</u> | | 8 | | |
| | | Subtotals | | |
| | | Subscore (100 x factor score subtotal/maximum score subtotal) | | |
| 2. <u>Flooding</u> | | 1 | | |
| | | Subscore (100 x factor score/3) | | |
| 3. <u>Ground-water migration</u> | | | | |
| <u>Depth to ground water</u> | | 8 | | |
| <u>Net precipitation</u> | | 6 | | |
| <u>Soil permeability</u> | | 8 | | |
| <u>Subsurface flows</u> | | 8 | | |
| <u>Direct access to ground water</u> | | 8 | | |
| | | Subtotals | | |
| | | Subscore (100 x factor score subtotal/maximum score subtotal) | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 100

IV. WASTE MANAGEMENT PRACTICES**A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|-----------------------|-------------------|
| Receptors | 51 |
| Waste Characteristics | 60 |
| Pathways | 100 |
| Total | 211 |
| | divided by 3 = |
| | 70 |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

70 x 1.0 = 70

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Fire Protection Training Area No. 2
 LOCATION Near Northwest Corner of Luna Lake
 DATE OF OPERATION OR OCCURRENCE Mid-1950's to mid-1960's
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION May have been several pit areas between Luna & Scout Lakes.
 SITE RATED BY C / Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|---|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 1 | 3 | 3 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 1 | 6 | 6 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| | | | Subtotals | 82 180 |
| | | | | Receptors subscore (100 X factor score subtotal/maximum score subtotal) |
| | | | | 46 |

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)
2. Confidence level (C = confirmed, S = suspected)
3. Hazard rating (H = high, M = medium, L = low)

Factor Subscore A (from 20 to 100 based on factor score matrix)

100

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$100 \quad \times \quad 0.9 \quad = \quad 90$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$90 \quad \times \quad 1.0 \quad = \quad 90$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|---|------------|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | Subscore | N/A |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| Distance to nearest surface water | 3 | 8 | 24 | 24 |
| Net precipitation | 1 | 6 | 6 | 18 |
| Surface erosion | 0 | 8 | 0 | 24 |
| Surface permeability | 1 | 6 | 6 | 18 |
| Rainfall intensity | 3 | 8 | 24 | 24 |
| | Subtotals | 60 | 108 | |
| | Subscore (100 x factor score subtotal/maximum score subtotal) | | 55 | |
| 2. Flooding | 0 | 1 | 0 | 3 |
| | Subscore (100 x factor score/3) | | 0 | |
| 3. Ground-water migration | | | | |
| Depth to ground water | 2 | 8 | 16 | 24 |
| Net precipitation | 1 | 6 | 6 | 18 |
| Soil permeability | 2 | 8 | 16 | 24 |
| Subsurface flows | 1 | 8 | 8 | 24 |
| Direct access to ground water | 0 | 8 | 0 | 24 |
| | Subtotals | 46 | 114 | |
| | Subscore (100 x factor score subtotal/maximum score subtotal) | | 40 | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 55**IV. WASTE MANAGEMENT PRACTICES**

A. Average the three subscores for receptors, waste characteristics, and pathways.

| | |
|-----------------------|-------------------|
| Receptors | 46 |
| Waste Characteristics | 90 |
| Pathways | 55 |
| Total | 191 |
| | divided by 3 = |
| | 64 |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

64 x 1.0 = 64

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Landfill No. 1
 LOCATION East of Second Street near Fuel Storage Tanks
 DATE OF OPERATION OR OCCURRENCE 1946-1951
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION Site was previously filled with sandy loam
 SITE RATED BY E / Schreuder

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 2 | 4 | 8 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| | | Subtotals | 83 | 180 |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 46

II. WASTE CHARACTERISTICS

A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

- 1. Waste quantity (S = small, M = medium, L = large) M
- 2. Confidence level (C = confirmed, S = suspected) S
- 3. Hazard rating (H = high, M = medium, L = low) H

Factor Subscore A (from 20 to 100 based on factor score matrix) 50

B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$50 \quad \times \quad 1.0 \quad = \quad 50$$

C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$50 \quad \times \quad 1.0 \quad = \quad 50$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Factor Multiplier | Maximum Possible Score |
|---------------|------------------------|-------------------|------------------------|
|---------------|------------------------|-------------------|------------------------|

A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B.

Subscore 80

B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C.

1. Surface water migration

| | | | | |
|--|---|---|----|----|
| <u>Distance to nearest surface water</u> | 1 | 8 | 8 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 1 | 8 | 8 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |

Subtotals 52 108Subscore (100 x factor score subtotal/maximum score subtotal) 48

2. Flooding

Subscore (100 x factor score/3) 0

3. Ground-water migration

| | | | | |
|--------------------------------------|---|---|----|----|
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |

Subtotals 46 114Subscore (100 x factor score subtotal/maximum score subtotal) 40

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 80**IV. WASTE MANAGEMENT PRACTICES**

A. Average the three subscores for receptors, waste characteristics, and pathways.

| | |
|------------------------------|-----------|
| <u>Receptors</u> | <u>46</u> |
| <u>Waste Characteristics</u> | <u>50</u> |
| <u>Pathways</u> | <u>80</u> |

Total 176 divided by 3 = 59
Gross Total Score

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

59 x 1.0 = 59

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Landfill No. 2
 LOCATION North of Second Street near Main Runway
 DATE OF OPERATION OR OCCURRENCE 1951 to 1963
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION Site was previously filled with sandy loam.
 SITE RATED BY E. J. Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 0 | 4 | 0 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | | <u>75</u> | <u>180</u> | |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 42

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)

L

2. Confidence level (C = confirmed, S = suspected)

S

3. Hazard rating (H = high, M = medium, L = low)

H

70

Factor Subscore A (from 20 to 100 based on factor score matrix)

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\underline{70} \quad \times \quad \underline{1.0} \quad = \quad \underline{70}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\underline{70} \quad \times \quad \underline{0.75} \quad = \quad \underline{52.5}$$

III. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|---|--------------------------------|-------------------|--|-------------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | <u>Subscore</u> | <u>80</u> |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 3 | 8 | 24 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 1 | 8 | 8 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | <u>Subtotals</u> | <u>68</u> | <u>108</u> |
| | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> | <u>63</u> |
| 2. Flooding | 0 | 1 | 0 | 3 |
| | | | <u>Subscore (100 x factor score/3)</u> | <u>0</u> |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 2 | 8 | 16 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | | <u>Subtotals</u> | <u>54</u> | <u>114</u> |
| | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> | <u>47</u> |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

| | |
|--------------------------|-----------|
| <u>Pathways Subscore</u> | <u>80</u> |
|--------------------------|-----------|

IV. WASTE MANAGEMENT PRACTICES**A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|------------------------------|-------------------|
| <u>Receptors</u> | 42 |
| <u>Waste Characteristics</u> | 52.5 |
| <u>Pathways</u> | 80 |
| <u>Total</u> | <u>174.5</u> |
| divided by 3 = | 58 |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

| | | | | |
|-----------|----------|------------|----------|-----------|
| <u>58</u> | <u>x</u> | <u>1.0</u> | <u>=</u> | <u>58</u> |
|-----------|----------|------------|----------|-----------|

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE JP-4 Spill
 LOCATION POL Bulk Storage Area
 DATE OF OPERATION OR OCCURRENCE 1965
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION Leak in four-inch diameter JP-4 supply line
 SITE RATED BY E. J. Schneider

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 2 | 4 | 8 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | | <u>83</u> | <u>180</u> | |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 46

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) L
2. Confidence level (C = confirmed, S = suspected) S
3. Hazard rating (H = high, M = medium, L = low) M

Factor Subscore A (from 20 to 100 based on factor score matrix) 50

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\underline{50} \quad \times \quad \underline{0.9} \quad = \quad \underline{45}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\underline{45} \quad \times \quad \underline{1.0} \quad = \quad \underline{45}$$

II. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|---|--------------------------------|--|---------------------------|-------------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | <u>Subscore</u> <u>80</u> | |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | N/A | 8 | - | - |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | <u>Subtotals</u> <u>52</u> | <u>84</u> | |
| | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> <u>62</u> | | |
| 2. Flooding | | 0 | 1 | 0 |
| | | <u>Subscore (100 x factor score/3)</u> <u>0</u> | | |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | | <u>Subtotals</u> <u>46</u> | <u>114</u> | |
| | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> <u>40</u> | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 80**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|------------------------------|------------------------------------|
| <u>Receptors</u> | <u>46</u> |
| <u>Waste Characteristics</u> | <u>45</u> |
| <u>Pathways</u> | <u>80</u> |
| <u>Total</u> <u>171</u> | divided by 3 = |
| | <u>Gross Total Score</u> <u>57</u> |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

57 x 1.0 = 57

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Hazardous Waste Burial Site
 LOCATION Near Radioactive (Solid) waste Disposal Site
 DATE OF OPERATION OR OCCURRENCE 1976, 1977
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION
 SITE RATED BY EJ Toland

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 0 | 3 | 0 | 9 |
| D. Distance to reservation boundary | 3 | 6 | 18 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | 79 | | 180 | |
| Receptors subscore (100 X factor score subtotal/maximum score subtotal) | | | | |
| 44 | | | | |

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)

M

2. Confidence level (C = confirmed, S = suspected)

C

3. Hazard rating (H = high, M = medium, L = low)

H

80

Factor Subscore A (from 20 to 100 based on factor score matrix)

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\frac{80}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{80}{\underline{\hspace{2cm}}}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\frac{80}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{80}{\underline{\hspace{2cm}}}$$

III. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|---|--------------------------------|-------------------|--|--|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | <u>Subscore</u> | <u>N/A</u> |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 1 | 8 | 8 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 1 | 8 | 8 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | <u>Subtotals</u> | <u>52</u> | <u>108</u> |
| | | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> |
| | | | | <u>48</u> |
| 2. <u>Flooding</u> | 0 | 1 | 0 | 3 |
| | | | <u>Subscore (100 x factor score/3)</u> | <u>0</u> |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | | <u>Subtotals</u> | <u>46</u> | <u>114</u> |
| | | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> |
| | | | | <u>40</u> |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 48**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|------------------------------|------------|
| <u>Receptors</u> | <u>44</u> |
| <u>Waste Characteristics</u> | <u>80</u> |
| <u>Pathways</u> | <u>48</u> |
| <u>Total</u> | <u>172</u> |

divided by 3 = 57

Gross Total Score

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

$$\frac{57}{ } \times \frac{0.95}{ } = \boxed{54}$$

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Fire Protection Training Area No. 1
LOCATION Second Street near Bulk Fuel Storage Tank
DATE OF OPERATION OR OCCURRENCE 1943 to mid-1950's
OWNER/OPERATOR Robins AFB
COMMENTS/DESCRIPTION Exact location not determined
SITE RATED BY EJ Toliver

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 2 | 3 | 6 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | 79 | | 180 | |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 44

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) M

2. Confidence level (C = confirmed, S = suspected) S

3. Hazard rating (H = high, M = medium, L = low) H

Factor Subscore A (from 20 to 100 based on factor score matrix) 50

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\frac{50}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{50}{\underline{\hspace{2cm}}}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\frac{50}{\underline{\hspace{2cm}}} \times \frac{1.0}{\underline{\hspace{2cm}}} = \frac{50}{\underline{\hspace{2cm}}}$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|------------------------|------------|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| Subscore <u>N/A</u> | | | | |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | N/A | 8 | - | - |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | Subtotals | <u>52</u> | <u>84</u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) <u>62</u> | | | | |
| 2. Flooding | 0 | 1 | 0 | 3 |
| Subscore (100 x factor score/3) <u>0</u> | | | | |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | | Subtotals | <u>46</u> | <u>114</u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) <u>40</u> | | | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 62**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|-----------------------|------------|
| Receptors | <u>44</u> |
| Waste Characteristics | <u>50</u> |
| Pathways | <u>62</u> |
| Total | <u>156</u> |

divided by 3 = 52

Gross Total Score

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

52 x 1.0 = 52

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Laboratory Chemical Disposal Site
 LOCATION Near Luna Lake
 DATE OF OPERATION OR OCCURRENCE 1962 to 1964
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION One time disposal of expired shelf life chemicals
 SITE RATED BY EJ Schmandt

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 1 | 3 | 3 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| | | | Subtotals | 180 |
| | | | | 42 |

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)

M

2. Confidence level (C = confirmed, S = suspected)

C

3. Hazard rating (H = high, M = medium, L = low)

M

Factor Subscore A (from 20 to 100 based on factor score matrix)

60

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\underline{60} \quad \times \quad \underline{1.0} \quad = \quad \underline{60}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\underline{60} \quad \times \quad \underline{0.5} \quad = \quad \underline{30}$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|------------------------|---|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | Subscore | 80 |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 0 | 8 | 0 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | Subtotals | 52 | 108 |
| | | | | 48 |
| | | Subscore (100 x factor score subtotal/maximum score subtotal) | | |
| 2. Flooding | 0 | 1 | 0 | 3 |
| | | Subscore (100 x factor score/3) | | 0 |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 3 | 8 | 24 | 24 |
| | | Subtotals | 70 | 114 |
| | | | | 61 |
| | | Subscore (100 x factor score subtotal/maximum score subtotal) | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore _____ 80

IV. WASTE MANAGEMENT PRACTICES**A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|-----------------------|-------------------|
| Receptors | 42 |
| Waste Characteristics | 30 |
| Pathways | 80 |
| Total | 152 |
| | divided by 3 = |
| | 51 |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

51 X 1.0 = 51

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Landfill No. 3
 LOCATION West Side of Luna Lake
 DATE OF OPERATION OR OCCURRENCE 1964
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION
 SITE RATED BY S / Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 1 | 3 | 3 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 1 | 6 | 6 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | <u>82</u> | | <u>180</u> | |

Receptors subscore (100 X factor score subtotal/maximum score subtotal) 46

II. WASTE CHARACTERISTICS

A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)

S

2. Confidence level (C = confirmed, S = suspected)

S

3. Hazard rating (H = high, M = medium, L = low)

H

Factor Subscore A (from 20 to 100 based on factor score matrix) 40

B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$40 \quad \times \quad 1.0 \quad = \quad 40$$

C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$40 \quad \times \quad 1.0 \quad = \quad 40$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|---|------------|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | Subscore | 0 |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 3 | 8 | 24 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 0 | 8 | 0 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | Subtotals | 60 | 108 | |
| | Subscore (100 x factor score subtotal/maximum score subtotal) | | 56 | |
| 2. <u>Flooding</u> | 0 | 1 | 0 | 3 |
| | Subscore (100 x factor score/3) | | 0 | |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 2 | 8 | 16 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | Subtotals | 54 | 114 | |
| | Subscore (100 x factor score subtotal/maximum score subtotal) | | 47 | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 56**IV. WASTE MANAGEMENT PRACTICES****A. Average the three subscores for receptors, waste characteristics, and pathways.**

| | |
|-----------------------|--------------------------|
| Receptors | 46 |
| Waste Characteristics | 40 |
| Pathways | 56 |
| Total <u>142</u> | divided by 3 = <u>47</u> |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

$$47 \times 1.0 = \boxed{47}$$

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Fire Training Pit No. 3
 LOCATION North of Existing Site in SAC area
 DATE OF OPERATION OR OCCURRENCE Mid-1960's to 1969
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION
 SITE RATED BY E. J. Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|---------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 0 | 4 | 0 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 1 | 3 | 3 | 9 |
| D. Distance to reservation boundary | 2 | 6 | 12 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | | <u>72</u> | <u>180</u> | |
| Receptors subscore (100 X factor score subtotal/maximum score subtotal) | | | | <u>40</u> |

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large) M
2. Confidence level (C = confirmed, S = suspected) S
3. Hazard rating (H = high, M = medium, L = low) M

Factor Subscore A (from 20 to 100 based on factor score matrix) 40

- B. Apply persistence factor

Factor Subscore A X Persistence Factor = Subscore B

$$\underline{40} \quad \times \quad \underline{1.0} \quad = \quad \underline{40}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\underline{40} \quad \times \quad \underline{1.0} \quad = \quad \underline{40}$$

III. PATHWAYS

| <u>Rating Factor</u> | <u>Factor Rating (0-3)</u> | <u>Multiplier</u> | <u>Factor Score</u> | <u>Maximum Possible Score</u> |
|---|--------------------------------|-------------------|---------------------|--|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| | | | <u>Subscore</u> | <u>N/A</u> |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 3 | 8 | 24 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 0 | 8 | 0 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| | | <u>Subtotals</u> | <u>60</u> | <u>108</u> |
| | | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> |
| | | | | <u>56</u> |
| 2. Flooding | 0 | 1 | 0 | 3 |
| | | | | <u>Subscore (100 x factor score/3)</u> |
| | | | | <u>0</u> |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| | | <u>Subtotals</u> | <u>46</u> | <u>114</u> |
| | | | | <u>Subscore (100 x factor score subtotal/maximum score subtotal)</u> |
| | | | | <u>40</u> |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 56**IV. WASTE MANAGEMENT PRACTICES**

A. Average the three subscores for receptors, waste characteristics, and pathways.

| | |
|---------------------------------|-------------------|
| <u>Receptors</u> | <u>40</u> |
| <u>Waste Characteristics</u> | <u>40</u> |
| <u>Pathways</u> | <u>56</u> |
| Total <u>136</u> divided by 3 = | <u>45</u> |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

45 X 1.0 = 45

HAZARDOUS ASSESSMENT RATING FORM

Page 1 of 2

NAME OF SITE Radioactive (Solid) Waste Burial Site
 LOCATION Facility No. 8315 near Pistol Range
 DATE OF OPERATION OR OCCURRENCE 1940's to 1950's
 OWNER/OPERATOR Robins AFB
 COMMENTS/DESCRIPTION _____
 SITE RATED BY E J Schaefer

I. RECEPTORS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|--|------------------------|------------|--------------|------------------------|
| A. Population within 1,000 feet of site | 1 | 4 | 4 | 12 |
| B. Distance to nearest well | 3 | 10 | 30 | 30 |
| C. Land use/zoning within 1 mile radius | 0 | 3 | 0 | 9 |
| D. Distance to reservation boundary | 3 | 6 | 18 | 18 |
| E. Critical environments within 1 mile radius of site | 0 | 10 | 0 | 30 |
| F. Water quality of nearest surface water body | 0 | 6 | 0 | 18 |
| G. Ground water use of uppermost aquifer | 1 | 9 | 9 | 27 |
| H. Population served by surface water supply within 3 miles downstream of site | 0 | 6 | 0 | 18 |
| I. Population served by ground-water supply within 3 miles of site | 3 | 6 | 18 | 18 |
| Subtotals | | <u>79</u> | <u>180</u> | |
| Receptors subscore (100 X factor score subtotal/maximum score subtotal) | | | | <u>44</u> |

II. WASTE CHARACTERISTICS

- A. Select the factor score based on the estimated quantity, the degree of hazard, and the confidence level of the information.

1. Waste quantity (S = small, M = medium, L = large)
2. Confidence level (C = confirmed, S = suspected)
3. Hazard rating (H = high, M = medium, L = low)

S _____
C _____
L _____

30 _____

Factor Subscore A (from 20 to 100 based on factor score matrix)

- B. Apply persistence factor
 Factor Subscore A X Persistence Factor = Subscore B

$$\underline{30} \quad \times \quad \underline{0.9} \quad = \quad \underline{27}$$

- C. Apply physical state multiplier

Subscore B X Physical State Multiplier = Waste Characteristics Subscore

$$\underline{27} \quad \times \quad \underline{0.5} \quad = \quad \underline{13.5}$$

III. PATHWAYS

| Rating Factor | Factor Rating (0-3) | Multiplier | Factor Score | Maximum Possible Score |
|---|------------------------|------------|--------------|------------------------|
| A. If there is evidence of migration of hazardous contaminants, assign maximum factor subscore of 100 points for direct evidence or 80 points for indirect evidence. If direct evidence exists then proceed to C. If no evidence or indirect evidence exists, proceed to B. | | | | |
| Subscore <u>ND</u> | | | | |
| B. Rate the migration potential for 3 potential pathways: surface water migration, flooding, and ground-water migration. Select the highest rating, and proceed to C. | | | | |
| 1. Surface water migration | | | | |
| <u>Distance to nearest surface water</u> | 1 | 8 | 8 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Surface erosion</u> | 0 | 8 | 0 | 24 |
| <u>Surface permeability</u> | 1 | 6 | 6 | 18 |
| <u>Rainfall intensity</u> | 3 | 8 | 24 | 24 |
| Subtotals <u>44</u> | | | | <u>108</u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) <u>41</u> | | | | |
| 2. Flooding | 0 | 1 | 0 | 3 |
| Subscore (100 x factor score/3) <u>0</u> | | | | |
| 3. Ground-water migration | | | | |
| <u>Depth to ground water</u> | 2 | 8 | 16 | 24 |
| <u>Net precipitation</u> | 1 | 6 | 6 | 18 |
| <u>Soil permeability</u> | 2 | 8 | 16 | 24 |
| <u>Subsurface flows</u> | 1 | 8 | 8 | 24 |
| <u>Direct access to ground water</u> | 0 | 8 | 0 | 24 |
| Subtotals <u>46</u> | | | | <u>114</u> |
| Subscore (100 x factor score subtotal/maximum score subtotal) <u>40</u> | | | | |

C. Highest pathway subscore.

Enter the highest subscore value from A, B-1, B-2 or B-3 above.

Pathways Subscore 41**IV. WASTE MANAGEMENT PRACTICES**

A. Average the three subscores for receptors, waste characteristics, and pathways.

| | |
|-----------------------|--------------------------|
| Receptors | <u>44</u> |
| Waste Characteristics | <u>14</u> |
| Pathways | <u>41</u> |
| Total <u>99</u> | divided by 3 = <u>33</u> |
| | Gross Total Score |

B. Apply factor for waste containment from waste management practices

Gross Total Score X Waste Management Practices Factor = Final Score

| | | | |
|-----------|----------|-------------|-------------|
| <u>33</u> | <u>x</u> | <u>0.95</u> | = <u>31</u> |
|-----------|----------|-------------|-------------|

APPENDIX I

REFERENCES

APPENDIX I

REFERENCES

- Chow, V. T., 1964, Handbook of Applied Hydrology, McGraw-Hill Book Company, New York, New York.
- Fenn, D. G., Hanley, K. J., and DeGeare, T. V., 1975, Use of the Water Balance Method for Predicting Leachate Generation from Solid Waste Disposal Sites, U. S. Environmental Protection Agency publication EPA/530/SW-168.
- Georgia Department of Natural Resources, 1976, Geologic Map of Georgia.
- Georgia Game and Fish Division, Department of Natural Resources, 1982, Telephone conversation with Ken Grahl, Fort Valley office, March 30, 1982.
- Giger, W. and Molnar-Kubica, E., 1978, Tetrachloroethylene in Contaminated Ground and Drinking Waters, Bulletin Environ. Contamination Toxicol. Vol. 19, No. 4, April, pp. 475-480.
- Herrick, Stephen M., 1961, Well Logs of the Coastal Plain of Georgia, Georgia Geological Survey Bulletin Number 70.
- Herrick, Stephen M., 1965, A Subsurface Study of Pleistocene Deposition Coastal Georgia, Georgia Geological Survey Information Circular 31.
- Herrick, Stephen M. and Vorhis, Robert C., 1963, Subsurface Geology of the Georgia Coastal Plain, Georgia Geological Survey Information Circular 25.
- Law Engineering Testing Co., 1980, Final Report, Ground Water Monitoring Program, Landfill Closure, Robins Air Force Base, Warner Robins, Georgia.
- LeGrand, H. E., 1962, Geology and Ground-Water Resources of the Macon Area, Georgia, Georgia Geological Survey Bulletin Number 72.
- Mitchell, Gail D., 1979, Potentiometric Surface of the Principal Artesian Aquifer in Georgia, Georgia Geological Survey Hydrologic Atlas Number 4.
- Pollard, L. D. and Vorhis, R. C., The Geohydrology of the Cretaceous Aquifer System in Georgia, Georgia Geological Hydrologic Atlas Number 3.
- Robins Air Force Base, TAB A-1, Environmental Narrative, Updated 1976.

Roberts, P.V., McCarty, P.L., Reinhard, M. and Schreiner, J., 1980,
Organic Contaminant Behavior During Ground-Water Recharge, Journal
Water Poll. Control Fed., Vol. 52, No. 1, January, pp. 161-171.
SGB/Bioenvironmental Engineers Office, Stabilization of DDT Spill.
January 4, 1980. Robins AFB, Georgia.

Sonderegger, J. L., Pollard, L. D., and Cressler, C. W., 1978, Quality
and Availability of Groundwater in Georgia, Georgia Geological
Survey Information Circular 48.

Talley, et al., Non-Potable Water Chemical Testing 1978-1979. Bio-
environmental Engineering Services Division, U.S. Air Force.
Robins AFB, Georgia.

Thomson, M. T., Herrick, S. M., and Brown, E., 1956, The Availability
and Use of Water in Georgia, Georgia Geological Survey Bulletin 65.

APPENDIX J

GLOSSARY

APPENDIX J

GLOSSARY OF TERMINOLOGY AND ABBREVIATIONS

AF: Air Force

AFB: Air Force Base

AFFF: Aqueous Film Forming Foam

AFLC: Air Force Logistics Command

AFR: Air Force Regulation

AFSC: Air Force Systems Command

AG: Adjutant General

Ag: Chemical symbol for silver

AGE: Aircraft Ground Equipment

Al: Chemical symbol for aluminum

ALIPHATIC SOLVENTS: Those solvents derived from straight chain hydrocarbon compounds.

AROMATIC SOLVENTS: Those solvents derived from benzene whose molecule contains one or more carbon rings.

ARTESIAN: Ground water contained under hydrostatic pressure

AQUICLUDE: Poorly permeable formation that impedes ground-water movement and does not yield water to a well or spring

AQUIFER: A geologic formation, group of formations, or part of a formation that is capable of yielding water to a well or spring

AQUITARD: A soils formation which impedes groundwater flow

AVGAS: Aviation Gasoline

Ba: Chemical symbol for barium

BESD: Bioenvironmental Engineering Services Division

Cd: Chemical symbol for cadmium

CERCLA: Comprehensive Environmental Response, Compensation and Liability Act

CES: Civil Engineering Squadron

CIRCA: About; used to indicate an approximate date

CLOSURE: The completion of a set of rigidly defined functions for a hazardous waste facility no longer in operation

CN: Chemical symbol for cyanide

COD: Chemical Oxygen Demand, a measure of the amount of oxygen required to oxidize organic and oxidizable inorganic compounds in water

COE: Corps of Engineers

CONFINED AQUIFER: An aquifer bounded above and below by impermeable beds or by beds of distinctly lower permeability than that of the aquifer itself

CONTAMINATION: The degradation of natural water quality to the extent that its usefulness is impaired; there is no implication of any specific limits since the degree of permissible contamination depends upon the intended end use or uses of the water

Cr: Chemical symbol for chromium

Cu: Chemical symbol for copper

DASC: Direct Air Support Center

DET: Detachment

DISPOSAL FACILITY: A facility or part of a facility at which hazardous waste is intentionally placed into or on land or water, and at which waste will remain after closure

DISPOSAL OF HAZARDOUS WASTE: The discharge, deposit, injection, dumping, spilling, or placing of any hazardous waste into or on land or water so that such waste or any constituent thereof may enter the environment or be emitted into the air or discharged into any waters, including ground water

DOD: Department of Defense

DOWNGRADIENT: In the direction of decreasing hydraulic static head; the direction in which ground water flows

DPDO: Defense Property Disposal Office - previous designation R&M, Redistribution and Marketing

DUMP: An uncovered land disposal site where solid and/or liquid wastes are deposited with little or no regard for pollution control or aesthetics; dumps are susceptible to open burning and are exposed to the elements, disease vectors and scavengers

EOD: Explosive Ordnance Disposal

ECM: Electronic Countermeasures

EFFLUENT: A liquid waste discharge from a manufacturing or treatment process, in its natural state, or partially or completely treated, that discharges into the environment

EPA: U. S. Environmental Protection Agency

EROSION: The wearing away of land surface by wind or water

EPHEMERAL AQUIFER: An aquifer usually near the surface which is only temporary in nature

FAA: Federal Aviation Administration

FACILITY: Any land and appurtenances thereon and thereto used for the treatment, storage and/or disposal of hazardous wastes

Fe: Chemical symbol for iron

FLOOD PLAIN: The lowland and relatively flat areas adjoining inland and coastal areas of the mainland and off-shore islands, including, at a minimum, areas subject to a one percent or greater chance of flooding in any given year

FLOW PATH: The direction or movement of ground water and any contaminants that may be contained therein, as governed principally by the hydraulic gradient

GROUND WATER: Water beneath the land surface in the saturated zone that is under atmospheric or artesian pressure

GROUND WATER RESERVOIR: The earth materials and the intervening open spaces that contain ground water

HALF-LIFE: The time required for half the atoms present in radioactive substance to disintegrate

HARDFILL: Disposal sites receiving construction debris, wood, miscellaneous spoil material

HAZARDOUS WASTE: A solid waste, or combination of solid wastes, which because of its quantity, concentration, or physical, chemical or infectious characteristics may cause or significantly contribute to an increase in mortality or an increase in serious, irreversible, or incapacitating reversible illness; or pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, or disposed of, or otherwise managed

HAZARDOUS WASTE GENERATION: The act or process of producing a hazardous waste

HEAVY METALS: Metallic elements, including the transition series, which include many elements required for plant and animal nutrition in trace concentrations but which become toxic at higher concentrations

Hg: Chemical symbol for mercury

HQ: Headquarters

INCOMPATIBLE WASTE: A waste unsuitable for commingling with another waste or material because the commingling might result in generation of extreme heat or pressure, explosion or violent reaction, fire, formation of substances which are shock sensitive, friction sensitive, or otherwise have the potential for reacting violently, formation of toxic dusts, mists, fumes, and gases, volatilization of ignitable or toxic chemicals due to heat generation in such a manner that the likelihood of contamination of ground water or escape of the substance into the environment is increased, any other reaction which might result in not meeting the Air, Human Health, and Environmental Standard

INFILTRATION: The flow of liquid through pores or small openings

IRP: Installation Restoration Program

KETONE SOLVENTS: Organic solvents containing a ketone functional group

LEACHATE: A solution resulting from the separation or dissolving of soluble or particulate constituents from solid waste or other man-placed medium by percolation of water

LEACHING: The process by which soluble materials in the soil, such as nutrients, pesticide chemicals or contaminants, are washed into a lower layer of soil or are dissolved and carried away by water

LETCO: Law Engineering Testing Company, Marietta, Georgia

LINER: A continuous layer of natural or man-made materials beneath or on the sides of a surface impoundment, landfill, or landfill cell which restricts the downward or lateral escape of hazardous waste, hazardous waste constituents or leachate

LOX: Liquid Oxygen

LYSIMETERS: A thimble or cup device used for extracting ground water samples at various depths

MAC: Military Airlift Command

MAS: Military Air Service

MGD: million gallons per day

MOA: Military Operating Area

Mn: Chemical symbol for manganese

MONITORING WELL: A well used to measure ground-water levels and to obtain samples

Mr/hr: millirem/hour; a measure of radioactivity

MSL: Mean Sea Level

Ni: Chemical symbol for nickel

OEHL: Occupational and Environmental Health Laboratory

ORGANIC: Being, containing or relating to carbon compounds, especially in which hydrogen is attached to carbon

O&G: Symbols for oil and grease

OT&E: Operations, Training and Evaluation

Pb: Chemical symbol for lead

PCB: Polychlorinated Biphenyls are highly toxic to aquatic life; they persist in the environment for long period and are biologically accumulative

PERCOLATION: Movement of moisture by gravity or hydrostatic pressure through interstices of unsaturated rock or soil

PD-680: Cleaning solvent, safety solvent, Stoddard's solvent

pH: Negative logarithm of hydrogen ion concentration, measurement of acids and bases

PL: Public Law

POL: Petroleum, Oils and Lubricants

POLLUTANT: Any introduced gas, liquid or solid that makes a resource unfit for a specific purpose

RCRA: Resource Conservation and Recovery Act

RECHARGE AREA: An area in which water is absorbed that eventually reaches the zone of saturation in one or more aquifers

RECHARGE: The addition of water to the ground-water system by natural or artificial processes

RECON: Reconnaissance

SANITARY LANDFILL: A land disposal site using an engineered method of disposing solid wastes on land in a way that minimizes environmental hazards

SATURATED ZONE: That part of the earth's crust in which all voids are filled with water

SLUDGE: The solid residue resulting from a manufacturing or wastewater treatment process which also produces a liquid stream

SOLID WASTE: Any garbage, refuse, or sludge from a waste treatment plant, water supply treatment, or air pollution control facility and other discarded material, including solid, liquid, semi-solid, or contained gaseous material resulting from industrial, commercial, mining, or agricultural operations and from community activities, but does not include solid or dissolved materials in domestic sewage; solid or dissolved materials in irrigation return flows; industrial discharges which are point source subject to permits under Section 402 of the Federal Water Pollution Control Act, as amended (86 USC 880); or source, special nuclear, or by-product material as defined by the Atomic Energy Act of 1954 (68 USC 923)

SPILL: Any unplanned release or discharge of a hazardous waste onto or into the air, land, or water

STORAGE OF HAZARDOUS WASTE: Containment, either on a temporary basis or for a longer period, in such a manner as not to constitute disposal of such hazardous waste

TAC: Tactical Air Command

TOXICITY: The ability of a material to produce injury or disease upon exposure, ingestion, inhalation, or assimilation by a living organism

TRANSMISSIVITY: The rate at which water is transmitted through a unit width under a unit hydraulic gradient

TREATMENT OF HAZARDOUS WASTE: Any method, technique, or process including neutralization designed to change the physical, chemical, or biological character or composition of any hazardous waste so as to neutralize the waste or so as to render the waste nonhazardous

UPGRADIENT: In the direction of increasing hydraulic static head; the direction opposite to the prevailing flow of groundwater

USAF: United States Air Force

V: Chemical symbol for vanadium

WATER TABLE: Surface of a body of unconfined ground water at which the pressure is equal to that of the atmosphere

Zn: Chemical symbol for zinc